

Request for Proposal – Winter Sand

2022-06 Addendum #1

Q#1: Does the sand you are looking to have supplied really need to have 0% passing the 150um and 75um sieves? OPSS 1004 allows 0-15% on the 150um and 0-5% on the 75um, could you please clarify as it could be quite a bit more costly for us to achieve these sieve results.

A#1: Under Section 2 Scope of Work and Project Requirements it does state “exception that for manufactured sand the maximum percent passing the 75um sieve shall be three percent (3%).

Q#2: Could you define “” ... the successful contractor will mix mechanically an estimated 6500t”. Is the township looking to have a bin system to mix the sand and salt?

A#2: Mechanically mixed by calibration the sand and salt at a 3% salt and 97% sand.

Q#3: The RFP states that the total tonnage is 6500 but then you have 2-line items each at 6500t. In my mind “supply” includes the haulage of the material to the town yard, why is the town requiring us to show the trucking broken out?

A#3: This is the form of Tender we have set out previously and future wording will change as this will be revised, to note to bring in a Live Bottom is confined and difficult