



2025 Annual Monitoring Report

Chapman Waste Disposal Site
Magnetawan, Ontario

Prepared for:

Municipality of Magnetawan

4304 Highway 520
Magnetawan, Ontario P0A 1P0

February 13, 2026

Pinchin File: 225335.010



2025 Annual Monitoring Report

Chapman Waste Disposal Site, Magnetawan, Ontario
Municipality of Magnetawan

February 13, 2026

Pinchin File: 225335.010

Issued to: Municipality of Magnetawan
Issued on: February 13, 2026
Pinchin file: 225335.010
Issuing Office: Sudbury, ON
Primary Pinchin Contact: Alana Valle, B. Eng, EIT
Project Manager
705.521.0560
avalle@pinchin.com

Author: _____
Jennifer Porter
Project Coordinator

Reviewer: _____
Tim McBride, B.Sc., P. Geo., QP_{ESA}
Practice Specialist – Hydrogeology
Director, Northern Ontario



TABLE OF CONTENTS

1.0 INTRODUCTION 1

1.1 Location 1

1.1.1 Site Survey and Aerial Photography 1

1.2 Ownership and Key Personnel 2

1.3 Description and Development of the Site 3

1.3.1 Site Document Review 3

1.4 Monitoring and Reporting Program Objectives and Requirements 4

1.5 Assumptions and Limitations 5

2.0 PHYSICAL SETTING 6

2.1 Geology and Hydrogeology 6

2.2 Surface Water Features 7

2.3 Historical Data 8

2.3.1 Historical Groundwater Data 8

2.3.2 Historical Surface Water Data 9

2.3.3 Historical Site Performance 9

3.0 METHODOLOGY 10

3.1 Scope of Work 10

3.2 Groundwater Monitoring Well Locations 11

3.3 Surface Water Monitoring Locations 13

3.4 Monitoring Frequency 13

3.5 Monitoring Parameters 14

3.5.1 Groundwater Monitoring Parameters 14

3.5.2 Surface Water Monitoring Parameters 14

3.6 Monitoring Procedures and Methods 14

3.6.1 Standard Operating Procedures 14

3.6.2 Groundwater Monitoring Activities 14

3.6.3 Surface Water Monitoring Activities 15

3.6.4 Groundwater and Surface Water Field Measurements 16

3.6.5 Record Keeping and Field Notes 18

3.7 Quality Assurance for Sampling and Analysis 18

3.8 Data Quality Evaluation 19

4.0 ASSESSMENT, INTERPRETATION AND DISCUSSION 20

4.1 Groundwater Flow Interpretation 20

4.2 Groundwater Quality Monitoring 21

4.2.1 The Reasonable Use Criteria Assessment (RUC) 21

4.2.2 The Ontario Drinking Water Quality Standards (ODWQS) 22

4.2.3 Aquatic Protection Values (APV) 23

4.3 Groundwater Results 23

4.3.1 Background Water Quality Evaluation 24

4.3.2 Leachate Source Quality Evaluation 24

4.3.3 Cross-gradient Water Quality Evaluation 26

4.3.4 Immediately Downgradient Water Quality Evaluation 26

4.3.5 Downgradient Water Quality Evaluation 27

4.4 Groundwater Trend Analysis 30

4.5 Groundwater Field Measurement Results 30

4.6 Surface Water Quality Monitoring 31



4.6.1	<i>The Provincial Water Quality Objectives (PWQO)</i>	31
4.6.2	<i>Canadian Water Quality Guidelines (CWQG)</i>	31
4.7	Surface Water Results	31
4.8	Surface Water Trend Analysis	32
4.9	Surface Water Field Measurement Results	33
4.10	Surface Water Flow Measurement Results	33
4.11	Leachate Characterization	33
4.12	Contaminant Attenuation Zone	33
4.13	Adequacy of the Monitoring Program	34
4.13.1	<i>Monitoring Well Network Efficiency</i>	34
4.14	Supplemental Monitoring: Sediment, Benthic and/or Toxicity Monitoring	34
4.15	Assessment of the Need for Implementation of Contingency Measures	34
4.16	Waste Disposal Site Gas Impacts	35
4.17	Effectiveness of Engineered Controls	35
4.18	Control Systems Monitoring	35
4.19	QA/QC Results	35
5.0	CONCLUSIONS	37
6.0	RECOMMENDATIONS	39
7.0	MONITORING AND SCREENING CHECKLIST	39
8.0	DISCLAIMER	40

APPENDICES

APPENDIX I	Figures
APPENDIX II	Certificate of Approval
APPENDIX III	Borehole Logs
APPENDIX IV	Summary Tables
APPENDIX V	Photoplates
APPENDIX VI	Laboratory Certificates of Analysis
APPENDIX VII	Groundwater Trend Analysis
APPENDIX VIII	Surface Water Trend Analysis
APPENDIX IX	Monitoring and Screening Checklist

FIGURES

Figure 1	Key Map
Figure 2	Site Plan
Figure 3	Topographic Survey
Figure 4	Monitoring Locations
Figure 5	Inferred Groundwater Contour Plan – Spring 2025
Figure 6	Inferred Groundwater Contour Plan – Fall 2025



TABLES

Table 1	Groundwater Monitoring Well Data
Table 2	Surface Water Monitoring Data
Table 3	Groundwater Quality Results – BH1
Table 4	Groundwater Quality Results – BH2
Table 5	Groundwater Quality Results – BH3
Table 6	Groundwater Quality Results – BH3-II
Table 7	Groundwater Quality Results – BH4
Table 8	Groundwater Quality Results – BH4-II
Table 9	Groundwater Quality Results – BH5-II
Table 10	Groundwater Quality Results – BH6-II
Table 11	Groundwater Quality Results – BH6-III
Table 12	Groundwater Quality Results – BH7-II
Table 13	Groundwater Quality Results – BH8-II
Table 14	Groundwater Quality Results – BH9-I
Table 15	Groundwater Quality Results – BH10-I
Table 16	Groundwater Quality Results – BH-11
Table 17	Guideline B-7 Calculations – Spring 2025
Table 18	Guideline B-7 Calculations – Fall 2025
Table 19	Surface Water Quality Results – SW1
Table 20	Surface Water Quality Results – SW2
Table 21	Surface Water Quality Results – SW3
Table 22	Surface Water Quality Results – SEEP
Table 23	Groundwater Duplicate Data
Table 24	Surface Water Duplicate Data



1.0 INTRODUCTION

Pinchin Ltd. (Pinchin) was retained by the Corporation of the Municipality of Magnetawan (Municipality) to prepare the 2025 annual groundwater and surface water monitoring report for the Chapman Waste Disposal Site (the Site). The following report provides a detailed evaluation and summary of the 2025 monitoring data and was completed to constitute the 2025 Annual Monitoring Report. This document includes but is not limited to a summary of historical geochemical data, a review/evaluation of the historical and current geochemical data (as well as groundwater flow) and a summary of geochemical trends.

The purpose of completing the monitoring program was to assess the hydraulic media for contaminants of concern as a compliance requirement under the Site Certificate of Approval (CofA, now referred to as Environmental Compliance Approval (ECA)) Number **A521202** and the applicable regulatory requirements during the spring and fall of 2025. To achieve the reporting objectives of this Site monitoring program, Pinchin carried out groundwater and surface water sampling at the Site in general accordance with the documents referenced within this report.

1.1 Location

The Site property is located on Lot 108, Concession A within the Municipality of Magnetawan, District of Parry Sound, Ontario and is located approximately 5.5 kilometres (km) northeast of the Township of Magnetawan, Ontario. The Site is situated in an undeveloped area, and the visibility of landfilling activities is limited from the adjacent roadway due to mature tree growth. The Site location is indicated on Figure 1 (all Figures are provided in Appendix I). The Site plan is illustrated on Figure 2.

The Site is located at Universal Transverse Mercator (UTM) coordinates Zone 17U, 606,831 metres (m) Easting and 5,063,200 m Northing (North American Datum 1983). Landfill coordinates were obtained using a Global Positioning System and are accurate within 10 m.

1.1.1 Site Survey and Aerial Photography

At the time of preparation of this report, previous survey information of the Site and existing monitoring well elevations were provided to Pinchin for review. During September 2018, Pinchin installed additional monitoring wells at the Site. A survey of the top of casings for these newly installed wells was completed by Pinchin in 2020. The available top of casing monitoring well elevation data obtained from the previous survey and the 2020 survey was used in the following sections of this report to calculate groundwater elevation contours. Repairs were completed at groundwater monitoring wells BH1 and BH3-II during the fall 2024 monitoring event which required the PVC riser to be cut; the top of casing



(TOC) surveyed elevations at these monitoring locations were adjusted for the 2025 groundwater elevation calculations by reducing the survey elevation by the measured length of cut PVC.

A topographic survey of the Site was completed by Pinchin using an Unmanned Aerial Vehicle (UAV) in 2021 and was utilized for the purpose of calculating the remaining waste capacity and remaining lifespan for the Site. The 2021 topographic survey is presented on Figure 3.

The results of the previous topographic survey completed in 2019 indicated that the Site had an approximate remaining capacity of 38,267.60 cubic meters (m³) and an approximate remaining Site lifespan of 15 years. Pinchin completed a report for the Municipality of Magnetawan titled “*Waste Capacity Study, Chapman Waste Disposal Site, Magnetawan, Ontario*” dated September 24, 2019, which further discussed the results of the 2019 topographic UAV survey.

In comparing the 2019 and 2021 topographic surveys, it was estimated that approximately 4,750 m³ of waste was deposited at the Site resulting in a remaining capacity of approximately 33,500 m³ as of 2021. An additional UAV survey was completed in 2023 in order to provide a current assessment of the existing deposited waste volume and an update of the waste disposal rates. The assessment of the existing waste volume, remaining capacity and waste deposition rate are included under a separate cover.

1.2 Ownership and Key Personnel

The Site is owned and operated by the Corporation of the Municipality of Magnetawan, located in Magnetawan, Ontario. The project was completed for the following representative on behalf of the Municipality:

Kerstin Vroom, Clerk/CAO
Municipality of Magnetawan Government Office
4304 Highway #520
Magnetawan, Ontario P0A 1P0

The Competent Environmental Practitioner (CEP) for the Site groundwater and surface water monitoring program was Tim McBride of Pinchin Ltd.:

Tim McBride, B.Sc., P.Geo., QP_{ESA}
Pinchin Ltd.
662 Falconbridge Road, Unit 3
Sudbury, Ontario P3A 4S4

1.3 Description and Development of the Site

The Site is operated as a landfill for municipal and non-hazardous solid, domestic and commercial wastes to be utilized by residences of the area. The Site was approved with a total fill area of 1.2 hectares (ha) within a 41-ha property. A copy of the Site's CofA is provided in Appendix II. A road with a locked gate is located northwest of the Site which provides access to the Site from the southeast side of Rocky Road approximately 200 m east of the intersection of Rocky Road and Nipissing Road North. Landfilling began at the Site prior to 1980, and the active landfilling area is currently located within the central portion of the Site.

A map illustrating the site features, landfill boundary and property boundary is provided as Figure 2.

1.3.1 Site Document Review

Pinchin reviewed the following reports for the Site and are referenced within this document:

- Report entitled “*2017 Annual Monitoring Report, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by D.M. Wills Associates Limited for the Corporation of the Municipality of Magnetawan dated March 2018 (the 2017 D.M. Wills Monitoring Report);
- Report entitled “*2018 Annual Monitoring Report, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by D.M. Wills Associates Limited for the Corporation of the Municipality of Magnetawan dated March 2019 (the 2018 D.M. Wills Monitoring Report);
- Report entitled “*Landfill Leachate Evaluation, Chapman Waste Disposal Site*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated July 6, 2018;
- Report entitled “*Leachate Management Plan Study, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated April 30, 2019 (the 2019 Leachate Management Study Report);
- Report entitled “*Waste Capacity Study, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated September 24, 2019 (the 2019 Waste Capacity Study Report);
- Report entitled “*2019 Annual Monitoring Report, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated December 12, 2019 (the 2019 Pinchin Monitoring Report);



- Report entitled “*2020 Annual Monitoring Report, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated February 5, 2021;
- Report entitled “*2021 Annual Monitoring Report, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated March 31, 2022;
- Report entitled “*Updated Trigger Level Monitoring Plan, Chapman Waste Disposal Site, Magnetawan, Ontario*” prepared by Pinchin dated September 13, 2022 (the Updated Trigger Plan Report);
- Report entitled “*2022 Annual Monitoring Report, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated January 30, 2023;
- Report entitled “*2023 Annual Monitoring Report, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated February 28, 2024;
- Report entitled “*2024 Landfill Closure and Post-Closure Care Liability Estimates, Chapman and Croft Waste Disposal Sites, Magnetawan, Ontario*” completed by Pinchin for the Municipality of Magnetawan, dated September 17, 2024;
- Report entitled “*2024 Annual Monitoring Report, Chapman Waste Disposal Site, Magnetawan, Ontario*” completed by Pinchin for the Corporation of the Municipality of Magnetawan dated March 17, 2025; and
- Report entitled “*2025 Landfill Closure and Post-Closure Care Liability Estimates, Chapman and Croft Waste Disposal Sites, Magnetawan, Ontario*” completed by Pinchin for the Municipality of Magnetawan, dated April 2, 2025.

A copy of these documents can be obtained from the Client. Pinchin has relied on the information available in the previous environmental reports reviewed for the Site as part of this assessment. Information reviewed within these reports is referenced in pertinent sections throughout this document.

1.4 Monitoring and Reporting Program Objectives and Requirements

The site specific CofA does not detail the monitoring and reporting requirements for the Site. The monitoring and reporting completed by Pinchin has been generally developed based on the Ministry of Environment, Conservation and Parks (MECP) document entitled “*Monitoring and Reporting for Waste Disposal Sites Groundwater and Surface Water Technical Guidance Document*” dated November 2010,



as well as the Client's request for 2025 monitoring and annual reporting. A copy of the CofA for the Site is provided in Appendix II.

1.5 Assumptions and Limitations

Pinchin has assumed that the information generated from historical investigations is accurate and has been completed in accordance with standard engineering practices and regulations. It should be noted that the historical background information made available to Pinchin by the Client was limited; and therefore, previous reports have been relied on for information where required.

The scope of the monitoring activities was limited to the parameters listed in the previous monitoring reports for groundwater and surface water and was limited to the immediate area surrounding the Site. The investigations were limited solely to the groundwater within the monitoring well installations on-Site and the surface water surrounding the Site. The investigation does not constitute an exhaustive investigation of the Site property or adjacent properties for potentially unknown contaminants and/or other unknown sources of environmental impact.

Pinchin's limitation of liability and scope of work is as follows:

- The work performed in this report was carried out in accordance with the Terms and Conditions made part of the contract. The conclusions presented herein are based solely upon the scope of services and time and budgetary limitations described in the contract;
- The report has been prepared in accordance with generally accepted environmental study and/or engineering practices. No other warranties, either expressed or implied, are made as to the professional services provided under the terms of the contract and included in this report;
- The services performed and outlined in this report were based in part upon a previously installed monitoring network established by others and approved by the applicable regulatory agencies. Pinchin's opinion cannot be extended to portions of the Site which were unavailable for direct observations reasonably beyond the control of Pinchin;
- The objective of this report was to assess the water quality conditions at the Site, given the context of the contract, with respect to existing environmental regulations within the applicable jurisdiction;
- The Site history interpreted herein relies on information supplied by others such as local, provincial and federal agencies, as well as Site personnel. No attempt has been made to independently verify the accuracy of such information unless specifically noted in this report;



- Pinchin’s interpretations relating to the landfill-derived leachate plume at the Site are described in this report. Where testing was performed, it was executed in accordance with the contract for these services. It should be noted that other compounds or materials not tested for may be present in the Site environment;
- The conclusions of this report are based in part on the information provided by others. The possibility remains that unexpected environmental conditions may be encountered at the Site in locations not specifically investigated. Should such an event occur, Pinchin must be notified in order that we may determine if modifications to the conclusions presented herein are necessary;
- The utilization of Pinchin’s services during future monitoring at the Site will allow Pinchin to observe compliance with the conclusions and recommendations contained herein. It will also provide for changes as necessary to suit field conditions as they are encountered; and
- Any use which a third party makes of this report, or any reliance on or decisions to be made based on it is the responsibility of such third parties. Pinchin accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

2.0 PHYSICAL SETTING

2.1 Geology and Hydrogeology

A detailed investigation of the Site geology and hydrogeology was outlined in the 2019 Leachate Management Study Report completed by Pinchin. Based on the report, the regional geology at the Site is dominated by the presence of shallow Precambrian bedrock with a thin veneer of overburden deposits and frequent bedrock outcroppings. Details provided in the 2017 and 2018 D.M. Wills Monitoring Reports indicated that an incised bedrock low was observed trending southwest to northeast and was infilled with glaciolacustrine sand deposits of depths of up to 10 m. Based on these observations, the hydrogeological setting of the Site can best be described as a buried bedrock valley of low permeability, infilled with coarse granular materials of high permeability. This setting results in a flow system that is contained within the overburden infill materials but significantly controlled by bedrock topography.

According to the 2019 Leachate Management Study Report, it has been suggested that the landfill development may have been initiated within a historical aggregate extraction pit on the western half of the Site with a bedrock high located in the central portion of the landfill footprint area. This second bedrock high trends easterly and results in bedrock outcrop east to the fill deposits with a significant topographic slope towards the south.



Pinchin installed seven new monitoring wells at the Site between September 26 to 28, 2018, for the Hydrogeology Assessment as part of the 2019 Leachate Management Plan Study. Based on the results of these well installations, the subsurface soil conditions at the Site are observed to consist of coarse sand or sand and silt overburden materials. Bedrock was encountered at the Site at depths of approximately 2 metres below ground surface (mbgs) to 4 mbgs in wells located towards the south and the east of the Site. Borehole logs for the newly installed monitoring wells on-Site are provided in Appendix III. No other borehole logs were provided to Pinchin for review.

Based on the 2019 Leachate Management Study report, the groundwater flow system most representative of the performance of the Site occurs within the underlying unconfined overburden aquifer. Bedrock drilling in the area suggests very competent rock with limited significant water-bearing fractures. The presence of a pronounced bedrock ridge located near the middle of the Site, which trends west to east, appears to present a buried bedrock valley. This feature confines the horizontal and vertical extent of the landfill leachate impacts but also results in the discharge of these waters to the surface along a bedrock plane that outcrops in the incised valley associated with adjacent surface water features.

Static water levels were recorded by Pinchin in all of the accessible wells for each of the 2025 groundwater monitoring events. Water levels were measured prior to purging and developing in preparation for sampling to ensure the water levels are representative of static conditions. A summary of the spring and fall 2025 groundwater elevations, as measured by Pinchin personnel, are presented in Table 1 (all tables are provided in Appendix IV).

In general, the static groundwater levels exist within 9.65 m of surface for most wells with the deepest depth to water in 2025 (9.64 mbgs) recorded at BH1 during the fall monitoring event. In the monitoring wells directly downgradient of the landfill deposits, the static water levels range between 1 to 7 m below grade and become deeper with distance from the landfill footprint with static levels ranging between 4 to 6 m towards the eastern portion of the existing groundwater monitoring network (i.e., BH5-II, BH6-III and BH8-I).

Groundwater movement at the Site has been established (by water level contouring) as being directed towards the northeast and is similar to that of the orientation of the buried bedrock valley confirming the conceptual model of a flow system influenced by the underlying bedrock topography.

2.2 Surface Water Features

According to previous annual water quality monitoring reports, the 2019 Leachate Management Study Report and the findings of a Site visit completed by Pinchin, it is documented that two surface water features are present in the immediate vicinity of the Chapman Waste Disposal site.



The first creek exists along the southern perimeter of the landfill area flowing from west to east. Surface water monitoring location SW1 is situated within this creek in an upstream area. This creek flows year-round with varying flow rates depending on meltwater and precipitation events. The second creek exists along the eastern perimeter of the landfill, flowing from north to southeast. Surface water monitoring location SW3 is situated within this creek. This creek is more ephemeral in nature with very small flows outside of seasonal precipitation-based events. The 2019 Leachate Management Study Report indicates that there is currently a leachate seep located on the banks of the second tributary upstream of the confluence with the larger creek. Surface water monitoring location SW2 is situated downstream of the confluence of the two streams at a culvert on Millers Road.

2.3 Historical Data

Pinchin reviewed the 2017 and 2018 D.M. Wills Annual Monitoring Reports, as well as the 2020 to 2024 Pinchin Monitoring Reports to evaluate historical data and groundwater and surface water quality conditions. No other water quality data from the existing monitoring well network was available to review as part of this monitoring program.

2.3.1 Historical Groundwater Data

Monitoring well BH3 was determined to be located upgradient of the waste deposits and has historically been used to monitor background water quality at the Site. This monitoring well was observed during the fall 2017 sampling event to have been destroyed as a result of earthmoving/landfilling operations at the Site. Monitoring well BH3-II was installed in 2018 by Pinchin as a replacement and was considered representative of background water quality at the Site. In 2019, an average of the historical results from previous background monitoring well BH3 and the current results from newly installed monitoring well BH3-II was applied as the source of background water quality for the Guideline B-7 calculations. In accordance with comments received from the MECP, the Guideline B-7 calculation was completed in 2020 and 2021 using an average of the results from the new upgradient monitoring wells BH3-II and BH11. However, in accordance with MECP comments received, groundwater quality at monitoring well BH3-II has observed exceedances of the ODWQS for DOC, aluminum and pH which appear to indicate potential leachate influence at this well. It is therefore interpreted that BH3-II is located too close to the landfill boundary to be considered representative of background water quality. Groundwater quality observed at new background monitoring well BH11, located downgradient and further from the landfill boundary, appears to indicate no leachate influence. Therefore, the new background well identified as BH11 has been utilized as the source for background water quality at the Site since 2022.

Based on the results of the previous monitoring reports, significant landfill related impacts at the Site were not identified. The reports indicated that moderate leachate impacts were observed immediately



downgradient of the Site which naturally attenuated with further distance from the Site; however, temperate leachate impacts were identified at the furthest downgradient wells. Elevated concentrations of total dissolved solids (TDS), iron, nitrate, dissolved organic carbon (DOC), aluminum and manganese parameters within the groundwater samples analyzed at the furthest downgradient monitoring locations were in exceedance of the Guideline B-7 criteria in 2020 to 2024.

These parameters are all related to operational guidelines and/or aesthetic objectives associated with drinking water systems set by the ODWQS and are not considered to be an immediate significant human health or environmental concern originating from the Site, with the exception of nitrate which is a health-related parameter. The elevated concentrations of nitrate were only quantified in some downgradient wells and often fluctuate throughout the historical record. It was noted that these concentrations should be confirmed during future monitoring events. Furthermore, concentrations of nitrate quantified at the downgradient groundwater wells were not interpreted to be impacting the surface water quality at the Site as nitrate concentrations are observed to be at low levels at downstream monitoring location SW2 and SW3.

2.3.2 *Historical Surface Water Data*

A review of the previous monitoring reports identified leachate effects at the immediately downgradient surface water location SW3 and minor leachate effects at further downstream surface water location SW2. The reports indicated that the leachate effects observed were relatively minor with concentrations below the Provincial Water Quality Objectives (PWQO) except for naturally elevated pH (low), iron, aluminum and cobalt which were also observed at background monitoring location SW1. In addition, concentrations of phosphorus during spring and cadmium in fall were observed to exceed the PWQO at SW2. These concentrations were interpreted to be anomalous and were recommended to be confirmed during future monitoring events. Based on the results of the report, significant concentrations of landfill related contaminants were not observed at downgradient surface water receptors.

2.3.3 *Historical Site Performance*

The Site currently operates as a typical natural attenuation waste disposal facility. No liner or other leachate collection/management system is in place at the Site. The 2019 Leachate Management Plan Study report indicated that a leachate-impacted groundwater seep/spring had been identified in a downgradient area (east of the Site, upstream from SW3 and in the vicinity of well BH9), resulting in the discharge of said waters to an adjacent surface water feature. This discharge essentially short circuits the natural attenuation process and has the potential to have negative effects on the surface water feature. The Municipality initiated a proactive approach to leachate management and retained Pinchin to complete the Leachate Management Plan Study. The surface water quality data collected for the study indicated

that an impact from the leachate seep is being observed in the two adjacent creeks, and it was recommended that steps should be taken to eliminate the seep. These steps include infilling the incised valley and relocating the creek to eliminate the seep, creating an extended CAZ boundary for additional leachate attenuation to occur prior to discharge to surface water bodies. The report also outlined a trigger level program and contingency plan recommended to be implemented at the Site following the elimination of the seep to monitor the impacts. The trigger level program is in the process of being developed as a stand-alone document in consultation with the MECP.

3.0 METHODOLOGY

3.1 Scope of Work

The objectives of the monitoring program as requested by the Client included the following scope of work:

- Mobilization to the Site during the spring and fall of 2025 and collection of groundwater and surface water samples from the existing well network and surface water monitoring locations;
- Submission of the groundwater and surface water samples to an accredited analytical laboratory for analysis of the chemical parameters outlined in the previous monitoring reports; and
- Preparation of a report outlining the 2025 field work completed and the analytical results, an evaluation of the results and any subsequent recommendations.

The investigation methodology was also conducted in general accordance with, and reference is made to the following regulatory and guidance documents:

- MECP document entitled "*Guidance on Sampling and Analytical Methods for Use at Contaminated Sites in Ontario*" dated December 1996 (MECP Sampling Guideline);
- MECP document entitled "*Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act*" dated March 9, 2004, amended July 1, 2011 (Analytical Methods);
- Ontario Regulation 169/03 "*Ontario Drinking Water Quality Standards*" under the Safe Drinking Water Act (ODWQS) dated 2002;
- MECP document entitled "*Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines*" dated June 2003 (ODWQS Guideline);
- MECP document entitled "*Incorporation of the Reasonable Use Concept into MECPE Groundwater Management Activities, Guideline B-7 (formerly 15-08)*" (Guideline B-7) dated April 1994;



- MECP document entitled “*Determination of Contaminant Limits and Attenuation Zones, Procedure B-7-1*”, (formerly referenced by 15-08) dated 2015 and updated in 2022;
- Ontario Regulation 903 R.R.O. 1990 “*Wells*” under the Ontario Water Resources Act (as amended);
- MECP document entitled “*Water Management Policies Guidelines Provincial Water Quality Objectives*” (PWQO) dated July 1994, revised February 1999;
- MECP document entitled “*Rationale for the Development of Soil and Groundwater Standards for Use at Contaminated Sites in Ontario*” (Table 3.1 - Aquatic Protection Values (APV)) dated April 15, 2011; and
- Canadian Council of Ministers of the Environment (CCME) document entitled “*Canadian Environmental Quality Guidelines*” (Water Quality Guidelines for the Protection of Freshwater Aquatic Life) dated 1999 (CWQG).

3.2 Groundwater Monitoring Well Locations

Seven (7) overburden groundwater monitoring wells have historically been utilized at the Site (BH1, BH2, BH3, BH4, BH5-II, BH6-II and BH7-II). As part of the leachate management plan study completed by Pinchin, several additional monitoring wells were installed at the Site during September 2018 to support the existing monitoring well network. This included the addition of two new background wells (BH11 and BH3-II) to replace the previously destroyed BH3, one cross-gradient well (BH10-I), deeper nested wells at two existing monitoring locations which are consistently dry (BH4-II and BH6-III) and two additional downgradient wells (BH8-I and BH9-I). The locations of all the monitoring wells included in the current monitoring program are illustrated on Figure 4. Detailed locations with coordinates in NAD 83 and the available monitoring well elevations for top of casing are provided in Table 1.

All groundwater monitoring wells were sampled during the spring and fall 2025 sampling events, with the exception of BH6-II during the spring and fall due to dry conditions observed at the time of the respective monitoring events, as well as BH4 during the fall due to insufficient volume at the time of sampling.

All wells were inspected and found to be in good condition, and no wells displayed evidence of a condition non-compliant with Ontario Regulation 903 (O. Reg. 903). During the fall 2024 monitoring event, Pinchin modified monitoring wells BH1 and BH3-II which had PVC riser too tall to close the casing lid. These new adjustments were accounted for when calculating the 2025 calculated water level elevations. A photographic log of all groundwater monitoring wells is provided in Appendix V.

The following table presents a summary of the construction details and respective on-Site positions of the newly installed groundwater monitoring wells based on the borehole logs provided in Appendix III.



Construction details for the other existing monitoring wells at the Site (BH1, BH2, BH4, BH5-II, BH6-II and BH7-II) are unknown as the borehole logs for the historic monitoring wells are not currently available.

Well ID	Total Depth (mbgs)	Screened Interval (mbgs)	Unit Screened
BH3-II	6.10	3.05 – 6.10	Sand and silt
BH4-II	8.44	5.1 – 8.44	Bedrock
BH6-III	6.30	3.05 – 6.05	Bedrock
BH8-I	6.05	3.0 – 6.05	Sand and gravel
BH9-I	7.50	4.4 – 7.5	Sand and Silt
BH10-I	4.88	1.8 – 4.88	Bedrock
BH11	4.88	1.8 – 4.88	Sand and silt

The following table summarizes the location of each of the monitoring wells with respect to its rationale in the annual monitoring program.

Well ID	Condition	Location	Rationale
BH1	Good	East portion of the Site adjacent to the waste deposits	Immediately Downgradient
BH2	Good	East portion of the Site adjacent to the waste deposits	Immediately Downgradient
BH3-II	Good	West of the Site	Upgradient
BH4	Good	East portion of the Site adjacent to the waste deposits	Immediately Downgradient
BH4-II	Good	East portion of the Site adjacent to the waste deposits	Immediately Downgradient
BH5-II	Good	East of the Site	Downgradient
BH6-II	Good	East of the Site	Downgradient
BH6-III	Good	East of the Site	Downgradient
BH7-II	Good	East of the Site	Downgradient



Well ID	Condition	Location	Rationale
BH8-I	Good	East of the Site	Downgradient
BH9-I	Good	East of the Site	Downgradient
BH10-I	Good	South of the Site	Cross-gradient
BH11	Good	Southwest of the Site	Background

3.3 Surface Water Monitoring Locations

The Site has three (3) historical points for surface water monitoring; SW, SW2 and SW3. An additional surface water monitoring location (SEEP) has been sampled for the Site since 2021 in accordance with comments received from the MECP regarding the existing leachate seep at the Site. All surface water monitoring locations were monitored during the spring and fall 2025 sampling events. The following table illustrates the location of each of the surface water monitoring locations with respect to its rationale in the annual monitoring program.

Monitoring Well ID	Location	Rationale
SW1	Within the creek located south of the Site.	Upstream Monitoring Location
SW2	Downgradient of the intersection of the two intermittent creeks at the Site at the culvert on Millers Road.	Further Downstream Monitoring Location
SW3	Within the creek located east of the Site.	Downstream Monitoring Location
SEEP	Leachate seep located upgradient of SW3.	Leachate Monitoring Location

The locations of the surface water monitoring locations are illustrated on Figure 4. Details regarding the surface water monitoring locations are provided in Table 2. Photos of all surface water monitoring locations are provided in Appendix V.

3.4 Monitoring Frequency

As per previous annual monitoring events, groundwater and surface water was sampled twice annually by Pinchin during 2025 in the spring and fall. The groundwater and surface water sampling events occurred on the following dates:

- Spring – May 7, 2025; and



- Fall – September 26, 2025.

3.5 Monitoring Parameters

3.5.1 Groundwater Monitoring Parameters

Groundwater samples were submitted for laboratory analysis of the parameters listed in the previous monitoring reports. Monitoring well BH4-II was also sampled for mercury and volatile organic compounds (VOCs). At the time of sample collection, field readings were measured for the following parameters: temperature, pH, conductivity, oxidation reduction potential (ORP) and dissolved oxygen (DO). Pinchin notes that the field pH parameters obtained during the fall sampling event may not be representative due to an equipment probe malfunction identified at the time of sampling.

3.5.2 Surface Water Monitoring Parameters

Surface water samples were submitted for laboratory analysis of the parameters listed in in the previous monitoring reports. At the time of sample collection, field readings were measured for the following parameters: temperature, pH, conductivity, ORP and DO were measured.

3.6 Monitoring Procedures and Methods

3.6.1 Standard Operating Procedures

The following Pinchin Standard Operating Procedures (SOPs) were followed by Pinchin field personnel for each portion of this project:

- Groundwater Sampling SOP; and
- Surface Water Sampling SOP.

All Pinchin monitoring SOPs have been developed in accordance with the MECP Sampling Document and are consistent with standard engineering practices.

3.6.2 Groundwater Monitoring Activities

To perform the groundwater monitoring activities, the following tasks were conducted:

- Pinchin notified the Client prior to field activities, and subsequently mobilized staff to the Site to complete the sampling program;
- Static groundwater levels were collected using a Solinst™ water level tape. Measurements were collected from the top of riser pipe;
- During the monitoring events, groundwater from each monitoring well was purged prior to the collection of the sample using a moderate-flow sample methodology via high-density

polyethylene (HDPE) or low-density polyethylene (LDPE) 3/8" tubing and a Waterra™ inertial foot valve system. The inertial pump system was chosen as an approved method to minimize sediment/particulate within each sample and to minimize sample agitation and well trauma in accordance with the MECP Sampling Document. Pinchin purged a minimum of three well volumes to a maximum of six well volumes, or until dry using the inertial pump system until the well volume column was representative of the surrounding formation. During purging activities, additional groundwater monitoring parameters were collected from each monitoring well using a YSI-556 water quality meter for measurement of field parameters. Sample residual was disposed of onto the ground surface, on-Site and upgradient within the landfill confines;

- Groundwater samples were collected using the inertial pump system in accordance with the MECP Sampling Document. Dissolved metals were field-filtered using a dedicated in-line 0.45-micron disposable filter. Upon completion of field sampling and monitoring activities, all samples collected were submitted to the project laboratory SGS Canada Inc. (SGS) in Lakefield, Ontario. All parameters were analyzed by the project laboratory using MECP approved procedures and are consistent with the analytical methods prescribed in the Analytical Methods document; and
- The groundwater samples collected were analyzed at the project laboratory for the parameters listed in the previous monitoring reports. Groundwater sample results were compared to the applicable ODWQS as applied in accordance with the ODWQS Guideline document. Groundwater wells located near surface water features were also compared to the applicable APV standards. Groundwater sample results were also compared to the reasonable usage parameters and were assessed using Guideline B-7 to establish and determine levels of contaminant discharges to the groundwater formation which would be considered acceptable by the MECP from naturally attenuating landfill sites with respect to human consumption and potable considerations.

3.6.3 *Surface Water Monitoring Activities*

To perform the surface water monitoring activities, the following tasks were conducted:

- Pinchin notified the Client prior to field activities, and subsequently mobilized to the Site;
- All field activities at each monitoring location were initiated at downstream locations working upstream to avoid sediment disturbance and influencing sample integrity;

- Care was taken during collection of surface water samples to ensure that a representative sample was collected, and that underlying sediments were not disturbed. For the surface water samples only, no filtration was done (in accordance with MECP surface water sampling protocols);
- Surface water samples were collected during each sampling event using a direct grab sampling methodology in accordance with the MECP Sampling Document. Upon completion of field sampling and monitoring activities, all samples collected were submitted to SGS. All parameters were analyzed by the project laboratory using MECP approved procedures and are consistent with the analytical methods prescribed in the Analytical Methods document;
- During sampling activities, surface water monitoring field parameters were collected at each surface water monitoring location using a YSI-556 water quality meter; and
- Surface water samples were analyzed during the monitoring event at the pre-determined monitoring locations for parameters listed in the previous monitoring reports. Sample results were compared to the applicable PWQO and CWQG criteria.

3.6.4 Groundwater and Surface Water Field Measurements

Prior to sampling groundwater in the wells, Pinchin monitored groundwater depth using a Solinst™ electronic water level meter. The water level tape is calibrated in 1.0 mm increments. Reproducibility of the depth measurements is generally within 2.0 mm or less.

Subsequent to groundwater depth measurement and during purging activities, additional groundwater monitoring parameters were collected from each monitoring well using a YSI-556 water quality meter for measurement of field parameters. Field parameters at each surface water monitoring location were also collected using the YSI-556. Additionally, in accordance with MECP comments, flows were measured at the surface water monitoring locations.

The following field parameters were measured during the monitoring program:

- Dissolved Oxygen (DO) refers to the relative quantity of oxygen molecules which are dissolved or carried within a quantity of water. Oxygen enters water as rooted aquatic plants and algae undergo photosynthesis and as oxygen is transferred across an air and water interface. Oxygen's solubility in water is indirectly correlated with water's temperature, salinity and pressure. DO concentrations have a significant effect on groundwater quality by regulating the valence state of trace of metals and constraining the bacterial metabolism of dissolved organic species;

- Conductivity is the measurement of water's capacity to pass an electrical current. It is considered to be a reasonable indicator of ionic activity and dissolved solids concentration levels. It is affected by the presence of inorganic dissolved solids which carry a negative charge such as chloride, nitrate, sulphate and phosphate anions or a positive charge such as sodium, magnesium, calcium, iron and aluminum cations. Organic compounds such as oil and phenol do not conduct an electrical current very well and would therefore have low conductivity in water. Conductivity is also directly correlated to the water temperature. Specific conductivity is a measurement of conductivity values which have been compensated to 25°C;
- pH is a measure of water's acidic/basic properties on a logarithmic scale from 1 (strongly acidic) to 14 (strongly alkaline or basic). It determines the solubility and biological availability of chemical constituents such as nutrients and heavy metals. For example, in addition to affecting how much and what form of phosphorus is most abundant in the water, pH also determines whether aquatic life can use it. The degree to which heavy metals are soluble determines their toxicity. Metals tend to be more toxic at lower pH values because they are more soluble. Excessively high and low pHs can have serious environmental and health effects. A high pH may cause the release of iron, copper or lead into potable water, corrosion on water pipes and water using appliances and reduces the effectiveness of water disinfection with chlorine. Low pH values corrode substances such as metals and plastics. Fluctuations in groundwater pH values may be indicative of groundwater contamination;
- Temperature has a dramatic influence on water quality. The rate of chemical reactions is generally correlated to temperature which in turn affects the biological availability of nutrients within the water. As previously mentioned, oxygen's solubility in water is indirectly correlated with its temperature. Declining concentrations of oxygen within warming water is magnified by aquatic plants increasing metabolism as water temperature increases. Low concentrations of DO weaken aquatic plants resistance to disease, parasites and other pollutants; and
- Oxidation-reduction potential (ORP) characterizes the oxidation-reduction state of the water on a scale from approximately -300mV (strongly reducing) up to +500mV (strongly oxidizing). The primary application of ORP is recording significant changes in the redox potential which is observed when purging a stagnant water column in piezometer and replacing it with "fresh" groundwater.

3.6.5 Record Keeping and Field Notes

Field notes were collected during the water quality monitoring events and recorded relevant observations, including, but not limited to:

- Dates and time of work being completed;
- Instrumentation and instrument condition;
- Calibration methods and results;
- Field parameter measurements;
- Field personnel conducting the investigations;
- Field methods used;
- Sampling location identifications;
- Sampling equipment and condition;
- Sample identification (i.e. type, media, number of containers, etc.);
- Sample preparation methods (i.e. preservatives, filtration, etc.);
- Field QA/QC measurements;
- Field and sample identifiers;
- Anomalous conditions (i.e. damage to monitoring wells);
- Photographs of monitoring wells and monitoring stations;
- Weather conditions at the time of the monitoring events; and
- Field conditions.

All raw data and field notes are preserved and retained in Pinchin's custody.

3.7 Quality Assurance for Sampling and Analysis

Pinchin uses recognized industry standards, including the Canadian Council of Ministers of the Environment (CCME) *Subsurface Assessment Handbook for Contaminated Sites* and MECP's manual *Guidance on Sampling and Analytical Methods for Use at Contaminated Sites in Ontario* for conducting environmental assessments. For quality assurance, all work is supervised and internally reviewed by senior staff members. Therefore, various QA/QC protocols were followed during the water quality sampling events to ensure that representative samples were obtained, and that representative analytical data were reported by the laboratory.



Field QA/QC protocols that were employed by Pinchin included the following:

- Clean, labelled and pre-preserved (when applicable) sample containers were provided by the laboratory;
- Water quality samples were placed in laboratory-supplied sample jars;
- The monitoring wells were purged to remove stagnant water prior to sample collection, so that representative groundwater samples could be obtained. Dedicated purging and sampling equipment was used for monitoring well development, purging and sampling to minimize the potential for cross-contamination;
- All water quality samples were placed in coolers on ice immediately upon collection with appropriate sample temperatures maintained prior submission to the laboratory;
- Dedicated and disposable Nitrile™ gloves were used for all sample handling;
- All non-dedicated monitoring and sampling equipment (i.e. water level meter and YSI-556) was cleaned before initial use and between uses to minimize the potential for cross-contamination by washing with an Alconox™ potable water mixture followed by a deionized water rinse;
- Field duplicate groundwater and surface water samples were collected during the spring and fall sampling event (1 in 10); and
- Sample collection and handling procedures were performed in general accordance with the MECP Sampling Guideline.

The SGS laboratory has an established QA/QC program and is a member of the Canadian Association for Laboratory Accreditation (CALA) and is accredited by the Standards Council of Canada (SCC) for specified environmental analyses.

SGS's internal laboratory QA/QC consisted of the analysis of laboratory duplicate, method blank, matrix spike and spiked blank samples, an evaluation of relative percent difference calculations for laboratory duplicate samples, and an evaluation of surrogate recoveries for the method blank, matrix spike and spiked blank samples.

3.8 Data Quality Evaluation

In order to provide confidence in the data obtained, a comprehensive QA/QC component was included in the monitoring program. The QA/QC procedures developed for this monitoring program are prepared in accordance with MECP Sampling Document and in most cases, exceed the minimum requirements.



Relative per cent difference (RPD) values (the absolute difference between two values divided by the average value and expressed as a per cent) were calculated between the parent sample and the field duplicate as part of the QA/QC program. RPD results of sample and duplicate analyses that are less than 50 percent indicate an acceptable level of analytical uncertainty. RPD values calculated for measured analyte concentrations for sample and duplicate pairs that exceed 50 per cent generally warrant discussion because they may indicate the presence of elevated analytical uncertainty and a potential for making interpretive errors based on the analysis results. Use of calculated RPD values to assess analytical uncertainty when using measured analyte concentrations for sample and sample duplicate pairs is not appropriate when either measured analyte concentration is within a multiple of 5 of the method detection limit (a value designated as the practical quantification limit (PQL)) where analytical uncertainty is typically elevated.

All field instrumentation calibration checks were completed by Pinchin field staff members prior to use on-Site. All field operations conducted by Pinchin field staff members were completed using standard equipment decontamination and sampling procedures, and no deviations from the sampling plan were noted.

4.0 ASSESSMENT, INTERPRETATION AND DISCUSSION

4.1 Groundwater Flow Interpretation

The hydraulic flow vector was historically estimated to range to the east. The groundwater flow direction may be influenced by seasonal variations in the amount of precipitation, by aquifer heterogeneity and the buried fill material at the Site. Groundwater level trends indicate seasonal fluctuations in the depth to groundwater which is consistent with seasonal fluctuations in precipitation events. The depth to groundwater measurement results are presented in Table 1.

During the spring monitoring event on May 7, 2025, the depth to groundwater was observed to range from 319.59 meters above sea level (masl) at BH3-II to 287.53 masl at BH5-II. During the fall monitoring event on September 26, 2025, the depth to groundwater was observed to range from 318.90 masl at BH3-II to 287.20 masl at BH5-II.

Accurate triangulation of the water table elevations was undertaken for the 2025 sampling events using the available monitoring well system and the survey elevation data. Pinchin completed a survey in 2020 to obtain elevation data for the newly installed wells at the Site and more accurate elevation data for the historical wells. The inferred groundwater contours for both the 2025 spring and fall events are presented on Figures 5 and 6, respectively. The presentation of the groundwater contours and the associated inferred groundwater flow direction for the 2025 sampling events, as illustrated on Figures 5 and 6,



confirms the previous findings of earlier Annual Monitoring Reports which indicate groundwater flow is directed towards the east.

4.2 Groundwater Quality Monitoring

4.2.1 The Reasonable Use Criteria Assessment (RUC)

Guideline B-7, the “reasonable use concept” (RUC) approach, is the MECP’s groundwater management strategy for mitigating the effect of contamination on properties adjacent to its source. It establishes procedures for determining what constitutes the reasonable use of groundwater on a property adjacent to sources of contaminants and establishes limits on the discharge of contaminants from landfills which have a potential to migrate hydraulically downgradient and off-site and impair the current and future groundwater use at downgradient properties.

The application of “reasonable use” is outlined in Procedure B-7-1 “*Determination of Contaminant Limits and Attenuation Zones*”. The procedure determines the maximum concentration (C_m) of a particular contaminant that would be acceptable in the groundwater beneath an adjacent property and is calculated in accordance with the relationship:

$$C_m = C_b + x (C_r - C_b)$$

C_b – This is the background concentration of the particular groundwater contaminant in consideration before it has been affected by human activities. From this, it is possible to calculate the extent of human activities impact on contaminant levels.

C_r – In accordance with the Ontario Water Management Guideline, this is the maximum concentration of a particular contaminant that should be present in the groundwater. This value is dependent on property’s use of the groundwater as outlined in B-7. It also allows for the total amount of contamination. Pinchin conservatively assumes that the reasonable use of the groundwater on-site is potentially for potable drinking purposes for which the ODWQS have been established.

X – As determined by the MECP, this constant determines the extent which the contamination has on the groundwater’s use. For drinking water, x is 0.5 for non-health related parameters or 0.25 for health-related parameters. For other reasonable uses, it is 0.5.

Contamination concentrations which exceed C_m may have an appreciable effect on the use of an adjacent property, and as such the Site should be managed in a manner to minimize environmental damage, or the operation should be modified. It is acceptable to modify the operation of the disposal site to meet the specified limits. However, if these limits are exceeded, all waste disposals, except for that done in conjunction with a reasonable plan for closure or with remedial activities, should be terminated until the



specified limits have been met, or until monitoring data indicate that these limits will be met.

Determination of the replacement of contaminated water supplies and the abatement of the contaminant plume must be made on a case-by-case basis in accordance with “*Resolution of Groundwater Quality Interference Problems*”, Guideline B-9. For the purpose of evaluating compliance with respect to the RUC, Pinchin has compared the calculated C_m values versus the applicable downgradient compliance monitoring wells (BH5-II, BH6-III, BH7-II, BH8-I and BH9-I).

Historically, monitoring well BH3 was considered representative of background water quality and was used in the Guideline B-7 calculations (C_b); however, this well was observed to have been destroyed during previous monitoring events. Newly installed monitoring wells BH3-II and BH11 are located furthest potentially hydraulically upgradient of the Site and have been used to estimate the background water quality coming onto the Site from 2019-2021. However, in accordance with MECP comments received, groundwater quality at monitoring well BH3-II has observed exceedances of the ODWQS for DOC, aluminum and pH which appear to indicate potential leachate influence at this well. It is therefore interpreted that BH3-II is located too close to the landfill boundary to be considered representative of background water quality. Groundwater quality observed at new background monitoring well BH11, located downgradient and further from the landfill boundary, appears to indicate no leachate influence. Therefore, the new background well identified as BH11 has been utilized as the source for background water quality at the Site since 2022. The average concentrations of all available sampling events at monitoring well BH11 have been applied as the source of background water quality (C_b) used to calculate the Guideline B-7 RUC values (C_m).

4.2.2 The Ontario Drinking Water Quality Standards (ODWQS)

Through the establishment of the ODWQS, the province of Ontario has determined legally enforceable standards on contaminants in drinking water. The standards are designed to protect public health by restricting the quality of specific contaminants in drinking water. Three categories of contaminants are regulated under the Ontario Regulation 169/03 Drinking Water Standards:

- Microbiological – Originating from human and animals waste, coliforms and bacteria are common in the environment. Most are harmless; however, their presence may be indicative of other harmful bacteria in the water. Under the ODWQS, *Escherichia coli* (“E. Coli”), fecal coliforms and total coliforms must be non-detectable in drinking water;

- Chemical – ODWQS regulates maximum quantities of organic and inorganic chemicals allowed in drinking water. Industrial discharges or agricultural runoff are not necessarily removed by drinking water treatment. Consuming water exhibiting a greater concentration of these chemicals than the ODWQS may cause serious health problems; and
- Radiation – Natural and artificial radio nuclides are also regulated in the ODWQS. Standards are expressed as maximum allowable concentrations in becquerels per litre (“L”). Radiological contaminants include radio nuclides, such as radium 228, which are caused from the erosion of naturally occurring deposits, or artificial radio nuclides, such as tritium, released into the water by nuclear power plants. Radiological contaminants do not naturally occur within the study area and the disposal of radiological waste was not suspected in the Site, and as a result, radiation was not monitored for this study.

The ODWQS Guideline Document is the MECP technical guidance document which provides guidance on applicability of the ODWQS and also provides applicable interim guidelines where legal standards are absent. Both the ODWQS and Guideline B-7 were used in assessing the groundwater results obtained during the 2025 monitoring program.

4.2.3 Aquatic Protection Values (APV)

Under Ontario Regulation 153/04, the MECP have developed APVs to protect aquatic organisms exposed to contaminants from migration of contaminated groundwater to surface water. Protection of aquatic biota from migration of contaminants by overland flow is provided by a Site being designated an environmentally sensitive area if the property includes or is adjacent to a water body or includes land that is within 30 m of a water body.

APVs are designed to provide a scientifically defensible and reasonably conservative level of protection for most aquatic organisms from the migration of contaminated groundwater to surface water resources. Groundwater monitoring wells nearest to the surface water features (BH6-III, BH7-II, BH8-I, BH9-I and BH10-I) are compared to the applicable APV standards to assess the potential impact of groundwater discharge to the surface water bodies.

4.3 Groundwater Results

The following discussion of parameters documents the groundwater quality in comparison to the ODWQS standards and the calculated reasonable use criteria as per Guideline B-7. To implement Guideline B-7, groundwater samples collected from the applicable downgradient monitoring wells (i.e., BH5-II, BH6-III, BH7-II, BH8-I and BH9-I) have been compared to the calculated RUC values (C_m). An average of all valid



sampling rounds at monitoring well BH11 has been applied as the source of background water quality for the Guideline B-7 calculations (C_b).

The analytical data for each well in comparison to the applicable regulatory criteria is provided in Tables 3 through 16. An evaluation of the RUC criteria in comparison to the downgradient compliance wells is provided in Tables 17 and 18 for the spring and fall events, respectively. Copies of the laboratory analytical reports are presented in Appendix VI. The following is a breakdown of the water quality observed the monitoring well locations with comparison to the background quality and leachate being produced on-Site.

4.3.1 *Background Water Quality Evaluation*

Monitoring Well BH3-II

Background water quality observed west of the waste fill area at BH3-II did not identify elevated levels of common landfill-related contaminant parameters such as conductivity, TDS, chloride, sulphate, calcium, sodium, potassium or nitrate. During the 2025 monitoring period, concentrations of pH (low), hardness (low), alkalinity (low) and turbidity were quantified outside of the recommended levels specified in the ODWQS. pH, hardness, alkalinity and turbidity are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site.

Monitoring Well BH11

Background water quality observed southwest of the waste fill area at BH11 did not identify elevated levels of common landfill-related contaminant parameters such as conductivity, TDS, chloride, sulphate, calcium, sodium, potassium or nitrate; although these concentrations are generally slightly higher compared to those quantified at BH3-II. During the 2025 monitoring period, concentrations of pH (low), hardness (low), alkalinity (low) and turbidity were quantified outside of the recommended levels specified in the ODWQS. pH, hardness, alkalinity and turbidity are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site. These concentrations are considered to be representative of local background groundwater quality.

4.3.2 *Leachate Source Quality Evaluation*

No groundwater monitoring wells in the existing monitoring well network are situated within the active landfill area to evaluate the source leachate quality. Monitoring wells BH4 and BH4-II are situated in closest proximity to the waste deposits and can be used to estimate the source strength prior to the further downgradient monitoring locations.



Monitoring Well BH4

In comparison to background water quality, groundwater observed immediately east of the waste fill area at BH4 is generally observed to have higher concentrations of conductivity, alkalinity, TDS, nitrate, chloride, sulphate, sodium and calcium indicating temperate impacts from the landfill which is consistent with historical observations at this location. It is expected that the groundwater at this location is impacted with minor amounts of landfill leachate considering its close proximity to the active fill zone. It is noted that an insufficient volume was observed at BH4 during the fall 2025 event. During the spring 2025 monitoring event, elevated hardness (high), DOC and turbidity concentrations were identified at BH4 that exceeded the ODWQS. Hardness, DOC and turbidity are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site.

Concentrations of nitrate were not observed at this location during the 2025 sampling events and are consistent with the considerable range of fluctuation throughout the historical monitoring record and have returned to concentrations within the ODWQS since the exceedance quantified in spring 2023; however, additional analytical data is required to confirm these decreasing concentrations.

Monitoring Well BH4-II

In comparison to background water quality, groundwater observed immediately east of the waste fill area (nested with well BH4) at BH4-II is generally observed to have higher concentrations of conductivity, alkalinity, TDS, nitrate, chloride, sulphate, calcium, sodium and potassium indicating temperate impacts from the landfill which are similar to those concentrations quantified at BH4. It is expected that the groundwater at this location is impacted with minor amounts of landfill leachate considering its close proximity to the active fill zone. During the 2025 monitoring period, elevated hardness (high), nitrate, DOC, manganese and turbidity concentrations were identified at BH4-II that exceeded the ODWQS. Hardness, DOC, manganese and turbidity are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site.

Concentrations of nitrate observed at this location are consistent with the considerable range of fluctuation throughout the historical monitoring record however has a spike during the spring 2025 sampling event. Additional analytical data is required to confirm a decreasing trend.

During the 2025 monitoring events, parameters of mercury and VOCs were not detected in the samples collected in both the spring and fall. This is consistent with the results obtained since the 2021 monitoring period.



4.3.3 *Cross-gradient Water Quality Evaluation*

Monitoring Well BH10-I

In comparison to background water quality, groundwater observed immediately south of the waste fill area at BH10-I is generally observed to have marginally elevated concentrations of conductivity, TDS, chloride, sodium, calcium and sulphate indicating temperate impacts from the landfill. It is expected that the groundwater at this location is impacted with minor amounts of landfill leachate considering its proximity to the Site. During the 2025 monitoring period, concentrations of hardness (low in spring and high in fall), DOC (fall only) and turbidity were observed to be outside of the values stated by the ODWQS. Hardness, DOC and turbidity are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site. Furthermore, elevated concentrations of turbidity are also quantified at the background monitoring location and therefore are not considered to be landfill derived.

Monitoring well BH10-I is located near the creek located south of the Site and was therefore also compared to the applicable APV standards. All parameter concentrations at BH10-I satisfied the APV during the 2025 monitoring period.

4.3.4 *Immediately Downgradient Water Quality Evaluation*

Monitoring Well BH1

In comparison to background water quality, groundwater observed immediately east and downgradient of the waste fill area at BH1 is generally observed to have slightly higher concentrations of conductivity, TDS, chloride, sulphate, sodium, potassium and nitrate indicating temperate impacts from the landfill which is consistent with historical observations at this location. It is expected that the groundwater at this location is impacted with minor amounts of landfill leachate considering its proximity to the active fill zone. During the 2025 monitoring period, elevated hardness (high in spring and low in fall), alkalinity (low), DOC, manganese and turbidity concentrations were identified at BH1 that exceeded the ODWQS. Hardness, DOC, alkalinity, manganese and turbidity are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site.

Alkalinity (low) exceeded the ODWQS during the fall sampling event. This exceedance has not been observed during previous monitoring events and is therefore interpreted to represent an anomalous result; however, Pinchin notes that continued monitoring during future sampling events is recommended to confirm whether this concentration is anomalous at BH1.



Concentrations of nitrate observed at this location are consistent with the considerable range of fluctuation throughout the historical monitoring record and have returned to concentrations within the ODWQS since the exceedance quantified in 2019. It is noted that an elevated concentration in comparison to those quantified in recent years was observed at BH1 in the fall 2024 monitoring event. Nitrate concentrations should continue to be closely monitored during future events.

Monitoring Well BH2

In comparison to background water quality, groundwater observed immediately east of the waste fill area at BH2 is generally observed to have higher concentrations of conductivity, alkalinity, TDS, chloride, sulphate, sodium and potassium indicating temperate impacts from the landfill which is consistent with historical observations at this location. It is expected that the groundwater at this location is impacted with minor amounts of landfill leachate considering its proximity to the active fill zone. During the 2025 monitoring period, elevated hardness (high), DOC, iron, manganese and turbidity concentrations were identified at BH2 that exceeded the ODWQS. Hardness, DOC, iron, manganese and turbidity are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site.

4.3.5 Downgradient Water Quality Evaluation

Monitoring Well BH5-II

In comparison to background water quality, groundwater observed east of the Site at BH5-II is generally observed to have higher concentrations of conductivity, alkalinity, TDS, nitrate, chloride, sulphate, calcium, sodium and potassium indicating temperate impacts from the landfill which is consistent with historical observations at this location. It is expected that the groundwater at this location is impacted with minor amounts of landfill leachate. During the 2025 monitoring period, hardness (high), DOC, manganese and turbidity concentrations were identified at BH5-II that exceeded the ODWQS. Guideline B-7 exceedances were quantified at BH5-II during 2025 for DOC and manganese. Hardness, DOC, TDS, manganese and turbidity are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site. Furthermore, elevated concentrations of DOC and turbidity are also quantified at the background monitoring location and therefore are not considered to be landfill derived.

Concentrations of nitrate observed at this location are consistent with the historical monitoring record and appear to have decreased over time since 2011 and stabilized with a spike in 2015, 2022 and 2024.



Monitoring Well BH6-II

Downgradient monitoring well BH6-II was observed to be dry at the time of sampling during the spring and fall 2025 monitoring events as is consistent with historical observations.

Monitoring Well BH6-III

In comparison to background water quality, groundwater observed east of the Site at BH6-III is generally observed to have slightly higher concentrations of conductivity, alkalinity, TDS, chloride, sulphate, calcium and potassium indicating minor impacts from the landfill. It is expected that the groundwater at this location is impacted with minor amounts of landfill leachate. During the 2025 monitoring period, elevated hardness (high), DOC and turbidity concentrations were identified at BH6-III that exceeded the ODWQS. Guideline B-7 exceedances were quantified at BH6-III during 2025 for TDS (spring only), DOC and manganese. Hardness, DOC and manganese are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site. Furthermore, elevated concentrations of DOC and turbidity are also quantified at the background monitoring location and therefore are not considered to be landfill derived.

No exceedances of nitrate (a health-related parameter) were quantified at BH6-III to be in exceedance of the Guideline B-7. Concentrations of nitrate observed at this location appear to be slightly decreasing over time since installation of this well in 2019 with a spike in fall 2022.

Monitoring well BH6-III is located near the creek flowing from the south of the Site and was therefore also compared to the applicable APV standards. All parameter concentrations at BH6-III satisfied the APV during 2025.

Monitoring Well BH7-II

In comparison to background water quality, groundwater observed east of the Site at BH7-II is generally observed to have generally similar concentrations of conductivity, alkalinity, TDS, chloride, sulphate, calcium, sodium and potassium indicating very minor impacts from the landfill which is consistent with historical observations at this location. During the 2025 monitoring period, pH (low, fall only), hardness (low), alkalinity (low), aluminum and turbidity concentrations were identified at BH7-II that exceeded the ODWQS. Guideline B-7 Criteria exceedances were quantified during 2025 for pH (low), aluminum and iron (fall only). These parameters are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site. Furthermore, elevated concentrations of pH (low), hardness (low), alkalinity (low), iron and turbidity are also quantified at the background monitoring location and therefore are not considered to be landfill derived.



Monitoring well BH7-II is located near the creek flowing from the south of the Site and was therefore also compared to the applicable APV standards. All parameter concentrations at BH7-II satisfied the APV during the 2025 sampling events.

Monitoring Well BH8-I

In comparison to background water quality, groundwater observed east of the Site at BH8-I is generally observed to have higher concentrations of conductivity, alkalinity, TDS, nitrate, chloride, sulphate, calcium, sodium and potassium indicating temperate impacts from the landfill. During the 2025 monitoring period, hardness (high), DOC, manganese and turbidity concentrations were identified at BH8-I that exceeded the ODWQS. Guideline B-7 criteria exceedances were quantified during 2025 for DOC and manganese. Hardness, DOC, manganese and turbidity parameters are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site. Furthermore, elevated concentrations of DOC and turbidity are also quantified at the background monitoring location and therefore are not considered to be landfill derived.

No exceedances of nitrate (health-related parameter) were quantified at BH8-I to be in exceedance of the Guideline B-7. Concentrations of nitrate observed at this location appear to be slightly decreasing over time since installation of this well in 2019 and stabilized in recent years.

Monitoring well BH8-I is located near the creek east of the Site and was therefore also compared to the applicable APV standards. All parameter concentrations at BH8-I satisfied the APV during the 2025 monitoring period.

Monitoring Well BH9-I

In comparison to background water quality, groundwater observed east of the Site at BH9-I is generally observed to have higher concentrations of conductivity, alkalinity, TDS, chloride, sulphate, calcium, sodium and potassium indicating temperate impacts from the landfill. It is interpreted that the groundwater at this location is impacted with minor amounts of landfill leachate. During the 2025 monitoring period, hardness (high), DOC, iron, manganese and turbidity concentrations were identified at BH9-I that exceeded the ODWQS. Guideline B-7 criteria exceedances were quantified during 2025 for TDS, DOC, iron, manganese and aluminum (fall only). Hardness, TDS, DOC, iron, manganese and turbidity parameters are either operational guidelines or aesthetic objectives for drinking water systems set by the ODWQS and are not considered to be a significant environmental concern originating from the Site. Furthermore, elevated concentrations of aluminum, DOC and turbidity are also quantified at the background monitoring location and therefore are not considered to be landfill derived.



Monitoring well BH9-I is located near the creek east of the Site and was therefore also compared to the applicable APV standards. All parameter concentrations at BH9-I satisfied the APV during the 2025 sampling events with the exception of marginal cobalt exceedances quantified during the spring and fall, consistent with previous events.

4.4 Groundwater Trend Analysis

A series of time versus concentration graphs were developed to evaluate the concentrations of several select landfill indicator parameters (including alkalinity, chloride, nitrate, pH and DOC) at each monitoring well for the Site. Current and historical groundwater quality data was utilized to identify any apparent trends or inconsistencies in the water quality within the monitoring well network. The time versus concentration graphs are provided in Appendix VII. It should be noted that the newly installed monitoring wells (BH3-II, BH4-II, BH6-III, BH8-I, BH9-I, BH10-I and BH11) currently only have data available for 2019-2025; therefore, further monitoring is required in order to interpret accurate trends at these locations.

In general, the landfill indicator parameters are demonstrating fairly stable trends with respect to time at all monitoring well locations with some exceptions. Concentrations of alkalinity are generally stable with the exception of wells BH1, BH2, BH4, BH5-II and BH10-I which are demonstrating increasing trends, although BH1 appears to be decreasing since 2019 and BH2 and BH4 appear to have stabilized. Chloride, nitrate and DOC concentrations at BH4 have generally been elevated but have been demonstrating a decreasing trend since 2013. At newly installed BH4-II, DOC and chloride concentrations appear stable while nitrate concentrations also follow a decreasing trend.

Further monitoring investigations are required in order to confirm the interpreted trends observed during this monitoring period.

4.5 Groundwater Field Measurement Results

During the spring and fall of 2025, Pinchin collected groundwater monitoring parameters from each of the well locations using a YSI-556 water quality meter for measurement of field parameters. The field parameter measurements are provided in Tables 3 through 16.

A review of the field parameters for the project identified no significant concerns in the water quality during the monitoring events. The water quality at the Site monitoring locations did not change significantly between each of the monitoring locations and the measured field parameters were within the normal variability associated with shallow groundwater monitoring systems. Pinchin notes that the field pH parameters obtained during the fall sampling event may not be representative due to an equipment probe malfunction identified at the time of sampling.

4.6 Surface Water Quality Monitoring

4.6.1 The Provincial Water Quality Objectives (PWQO)

The PWQO are numerical and narrative criteria which serve as chemical and physical indicators representing satisfactory levels for surface water and groundwater where it discharges to the surface. The PWQO are levels which are protective of the water quality for all forms of aquatic life during their indefinite exposures to the water. The PWQO levels include protection for anthropogenic recreational water uses where there is a high potential of exposure and are based on public health and aesthetic considerations.

In general, the PWQO stated that the surface water quality of a water body shall be “free from contaminating levels of substances and materials attributable to human activities which in themselves, or in combination with other factors can: settle to form objectionable deposits; float as debris or scum or oil or other matter to form nuisances; product objectionable colour, odour, taste, or turbidity; injure, are toxic to, or produce adverse physiological or behavioural responses in humans, animals, or plants; or enhance the production of undesirable aquatic life or result in the dominance of nuisance species”.

4.6.2 Canadian Water Quality Guidelines (CWQG)

The CWQG were developed by the Canadian Council of Resources and Environment to provide basic scientific information about the effects of water quality parameters on uses in order to assess water quality issues and concerns and to establish water quality objectives for specific sites. The guidelines contain recommendations for chemical, physical, radiological and biological parameters necessary to protect and enhance designated uses of water. They apply only to inland surface waters and groundwater and not to estuarine and marine waterbodies. The rationale for each parameter is included to assist in the development of water quality objectives to suit local water conditions.

4.7 Surface Water Results

Pinchin collected surface water samples from all surface water monitoring locations during the spring and fall monitoring events in 2025. A summary of water quality monitoring data relative to the regulatory standards is presented in the attached Tables 19 through 22. Copies of the laboratory analytical reports are presented in Appendix VI.

Surface water monitoring location SW1 located within the creek along the south side of the Site is considered representative of background water quality conditions and is characterized by naturally elevated concentrations of pH (low), phenols, iron, aluminum. Concentrations of pH (low) and aluminum exceeded the PWQO and/or CWQG during the 2025 sampling events which is consistent with the observations at this location throughout the historical monitoring record.



Samples collected at the observed leachate seep location (SEEP) during 2025 indicated elevated levels of most parameters when compared to the background surface water conditions at SW1. Concentrations of iron, boron, chromium (spring only) and cobalt (fall only) were identified to be in exceedance of the PWQO and/or CWQG during 2025.

Minor leachate impacts are observed at the downstream surface water monitoring location SW3 with exceedances quantified for iron, boron and cobalt (fall only) during 2025. These impacts are interpreted to improve with distance from the Site as lower concentrations are quantified at further downstream monitoring location SW2. Surface water samples collected further downstream at SW2 had exceedances quantified for aluminum (spring only) during 2025. The concentrations observed at this location are consistent with the observations at this location throughout the historical monitoring record.

Additionally, concentrations of nitrate (health-related parameter) quantified at several of the downgradient groundwater monitoring wells are not interpreted to be impacting the surface water quality at the Site as nitrate concentrations are observed to be at low levels at the seepage source area at SW3 and lower still at downstream monitoring location SW2. This interpretation should be confirmed during future monitoring.

4.8 Surface Water Trend Analysis

A series of time versus concentration graphs were developed to evaluate the concentrations of several select landfill indicator parameters (including alkalinity, chloride, nitrate, pH, and DOC) at each surface water monitoring location for the Site. Current and historical surface water quality data was utilized to identify any apparent trends or inconsistencies in the water quality at the Site. The time versus concentration graphs are provided in Appendix VIII. It should be noted that the SEEP location currently only has data available for 2021-2025; therefore, further monitoring is required in order to interpret accurate trends at this location.

In general, the landfill indicator parameters are demonstrating stable trends with respect to time at all surface water monitoring locations within a large range of fluctuation with the exception of SW3 which does not demonstrate an identifiable trend for alkalinity or nitrate. Chloride concentrations are noted to be higher at the SEEP location in comparison to the remainder of the surface water monitoring locations but appear to indicate a decreasing trend. Conversely, chloride concentrations appear to be increasing at the remainder of the monitoring locations, including at background location SW1. Nitrate concentrations are low at all locations and also indicate a decreasing trend at the SEEP location.

Further monitoring investigations are required to confirm the trends observed during this monitoring period.



4.9 Surface Water Field Measurement Results

During the spring and fall of 2025, Pinchin collected surface water monitoring parameters from each surface water monitoring location using a YSI-556 water quality meter for real-time in-situ measurement of field parameters. The field parameter measurements are provided in Tables 19 through 22.

A review of the field parameters for the project identified no significant concerns in the water quality during the monitoring event. The quality at the surface water monitoring locations did not change significantly between each of the monitoring locations. Pinchin notes that the field pH parameters obtained during the fall sampling event may not be representative due to an equipment probe malfunction identified at the time of sampling.

4.10 Surface Water Flow Measurement Results

Stream flow measurements were conducted on each of the surface water monitoring stations during the spring and fall 2025 monitoring events. Flow measurements are summarized below in the following table.

Sample Station	Flow (m ³ /s)	
	Spring 2025	Fall 2025
SW1	0.07	0.0011
SW2	0.0244	0.0092
SW3	0.0094	0.0016

4.11 Leachate Characterization

The Site is an operating landfill with minor operational or maintenance being overseen by the Municipality. The Site currently does not have a leachate collection system whereby leachate quality monitoring and characterization is being completed. Currently, there is no groundwater monitoring well included in the existing monitoring well network at the Site that is situated within the active landfill area, or which is considered representative of source leachate water quality. Therefore, leachate at the Site is characterized via monitoring wells BH4 and BH4-II which are considered near source monitors.

4.12 Contaminant Attenuation Zone

A Contaminant Attenuation Zone (CAZ) has not been established for the Site. However, it should be noted that based on the current observed water quality data, landfill derived leachate impacts appear to attenuate prior to the property boundary (although the current groundwater seep needs to be addressed). Future investigations should involve the development/formal approval of a CAZ for this Site.



4.13 Adequacy of the Monitoring Program

At this time, there is currently no formal monitoring program for the Site. Pinchin recommends continuation of sampling the groundwater and surface water two times per year (spring and fall) to establish any notable trends or impacts emanating from the landfill. The results of inspection and monitoring will continue to be reported annually to the MECP.

During these sampling and reporting events, it is recommended that the monitoring well network be evaluated for adequacy and determine if there is a need for additional monitoring locations.

4.13.1 Monitoring Well Network Efficiency

Pinchin concludes that the current groundwater monitoring well network is considered adequate for evaluating the Chapman Waste Disposal Site geological and hydrogeological characteristics immediately to the east of the landfill (for evaluating downgradient groundwater quality migrating from the Site).

Based on a review of the groundwater contaminant data from BH3 (Destroyed), BH3-II and BH11, the assumed groundwater flow direction and comments received by the MECP, monitoring well BH11 has been identified as a best-case background location. A review of the dataset (as provided on Table 16) from BH11 did not identify elevated levels of common landfill-related contaminant parameters with the exception of hardness and alkalinity which are naturally lower than the ODWQS range and turbidity which is naturally elevated. At this time, monitoring well BH11 is considered adequate for monitoring background groundwater quality. The groundwater quality observed in monitoring well BH11 have been used within this report for assessing the Site's water quality data to Guideline B-7 RUC (i.e., background well).

Based on a visual inspection of the monitoring well installations, Pinchin concludes that the monitoring wells are in satisfactory condition.

Borehole logs for several of the wells on-Site are currently not available. The borehole logs for the new monitoring wells installed in September 2018 are provided in Appendix III.

4.14 Supplemental Monitoring: Sediment, Benthic and/or Toxicity Monitoring

No supplemental monitoring was completed as part of the 2025 monitoring program completed by Pinchin.

4.15 Assessment of the Need for Implementation of Contingency Measures

As part of the 2019 Leachate Management Study Report completed by Pinchin in April 2019 and the Updated Trigger Plan report completed by Pinchin in September 2022 in accordance with MECP review comments, a trigger level monitoring program and contingency plan has been proposed for the Chapman



Waste Disposal Site. The proposed Trigger Level Monitoring Program for groundwater and surface water is a three-tiered program that includes routine monitoring (i.e. the semi-annual monitoring program), compliance monitoring and confirmation monitoring. It should be noted that the implementation of the trigger level monitoring program is only recommended once the proposed mitigation measures associated with the leachate seep are completed. Additionally, the updated trigger level program is currently being submitted to the MECP for approval under separate cover as a stand-alone document.

It is Pinchin's opinion that contingency measures are not required for the Site at the time of preparation of this report.

4.16 Waste Disposal Site Gas Impacts

At this time, no evidence has been documented to suggest that methane gas generation from the Site is a significant concern.

4.17 Effectiveness of Engineered Controls

With the exception of the intermittent landfill cover, there are no operational engineered controls in effect at the Site. The Client should continue to maintain the integrity of the landfill cover as per the CofA. Annual monitoring and inspections should continue to ensure regular maintenance is occurring as needed. At the time of the 2025 monitoring event, no significant damage or concerns were noted.

4.18 Control Systems Monitoring

Environmental control systems are designed, constructed and utilized at some waste disposal sites to reduce or increase an environmental variable to an acceptable level, or to maintain an environmental variable within an acceptable range in order to prevent a negative environmental outcome.

Certain environmental control systems such as a leachate collection system or a methane gas collection system can provide the basis for operator intervention to bring about or maintain a desired condition to operate the landfill. The Site does not currently operate any control systems; therefore, no control system monitoring was completed as part of the 2025 monitoring program.

4.19 QA/QC Results

In order to provide confidence in the data obtained, a comprehensive QA/QC component was included in the monitoring program. The QA/QC procedures developed for this monitoring program are prepared in accordance with MECP Sampling Document and in most cases, exceed the minimum requirements.



Water quality samples collected by Pinchin were generated in accordance with acceptable procedures. No analytical hold times were exceeded for samples submitted for analyses, and sample temperatures upon receipt at the project laboratory were below 10° Celsius.

Two groundwater duplicate sample pairs and one surface water duplicate sample pair were collected from the Site during the spring and fall sampling events and submitted for laboratory analysis of the full suite of analytical parameters. All duplicate data for 2025 are provided in Tables 23 and 24 for groundwater and surface water, respectively.

The following table summarizes the duplicate pairs for 2025:

Sampling Event	Duplicate Sample ID	Original Sample ID
Spring	GW DUP1	BH11
	GW DUP2	BH8-I
	SW DUP	SW1
Fall	GW DUP1	BH11
	GW DUP2	BH4-II
	SW DUP	SW1

The calculated RPDs for the original and field duplicate groundwater sample has been compared to the performance standards considered acceptable by Pinchin (i.e. 50%). Each of the calculated RPDs met the corresponding performance standard with the exception of the following:

- Cadmium, nickel, phosphorus and turbidity in GW DUP 1 during spring 2025;
- Turbidity in GW DUP 2 during spring 2025;
- Phosphorus in GW DUP 1 during fall 2025;
- Titanium in GW DUP 2 during fall 2025;
- Alkalinity and boron in SW DUP during the spring 2025; and
- Cadmium in SW DUP during the fall 2025.

The analytical laboratory employed to perform the laboratory analyses (SGS) is accredited by the Standards Council of Canada/Canadian Association for Laboratory Accreditation in accordance with ISO/IEC 17025:1999 – “General Requirements for the Competence of Testing and Calibration Laboratories” for the tested parameters and has met the standards for proficiency testing developed by



the Standards Council of Canada for parameters set out in the Soil, Ground Water and Sediment Standards.

Sample analysis dates provided on the laboratory analytical reports issued by SGS indicate that all sample analyses were performed within the required sample/extract hold times as indicated by the dates presented in columns for each sample parameter on the analytical report. The laboratory minimum detection limits were reported to be at or lower than the required MECP reporting detection limits for the parameters analyzed. A comparison of the internal laboratory duplicate samples indicates that all samples and the respective duplicates are within acceptable limits.

Upon review of the QA/QC results for spring and fall sampling programs, Pinchin has not identified any significant concerns that would warrant the invalidation of any of the field or laboratory data; and therefore, considers the data generated as part of this program to be reliable.

5.0 CONCLUSIONS

Based on the work completed, the following is a summary of the activities and findings of the 2025 water quality monitoring program:

- Groundwater samples were collected from all monitoring wells at the Site on May 7 and September 26, 2025, with the exception of BH6-II in the spring and fall due to dry conditions at the time of sampling, as well as BH4 in the fall due to insufficient volume at the time of sampling. All groundwater samples were submitted for laboratory analysis of parameters identified in the previous monitoring reports. Samples collected at monitoring well BH4-II were also submitted for analysis of mercury and VOCs. The groundwater quality was assessed based on the ODWQS, APV and Guideline B-7;
- Surface water samples were collected from all monitoring locations on May 7 and September 26, 2025, and were submitted for laboratory analysis of parameters identified in the previous monitoring reports. Surface water quality was assessed based on the PWQO and CWQG;
- Groundwater flow at the Site is interpreted to be directed towards the east;
- All reported concentrations in the groundwater samples submitted for analysis satisfied the respective ODWQS parameters with the exception the following:
 - pH (low) at BH3-II, BH7-II and BH11;
 - Hardness (high) at BH1, BH2, BH4, BH4-II, BH5-II, BH6-III, BH8-I, BH9-I and BH10-I;
 - Hardness (low) at BH1, BH3-II, BH7-II, BH10-I and BH11;



- Alkalinity (low) at BH1, BH3-II, BH7-II and BH11;
- DOC at BH2, BH4, BH4-II, BH5-II, BH6-III, BH8-I, BH9-I and BH10-I;
- Iron at BH2, BH9-I;
- Manganese at BH1, BH2, BH4-II, BH5-II, BH8-I, BH9-I;
- Turbidity at BH1, BH2, BH3-II, BH-4, BH4-II, BH5-II, BH6-III, BH7-II, BH8-I, BH9-I, BH10-I and BH11; and
- Aluminum at BH7-II.
- All reported concentrations in the groundwater samples near surface water bodies submitted for analysis satisfied the respective APV parameters with the exception of cobalt at BH9-I;
- All reported concentrations in the groundwater samples collected from the downgradient monitoring wells met the applicable Guideline B-7 criteria for all parameters analyzed with the exception of the following:
 - pH (low) at BH7-II;
 - TDS at BH6-III and BH9-I;
 - DOC at all locations except BH7-II;
 - Iron at BH7-II and BH9-I;
 - Manganese at all locations except BH7-II; and
 - Aluminum at BH7-II and BH9-I.
- All reported concentrations in the surface water samples submitted for analysis satisfied the respective PWQO and/or CWQG parameters with the exception of the following:
 - pH (low) at SW1;
 - Iron at SW2 and SEEP;
 - Aluminum at SW1 and SW2;
 - Chromium at SEEP;
 - Cobalt at SW2 and SEEP; and
 - Boron SW2 and SEEP.

Based on the results obtained from the existing groundwater monitoring wells and surface water monitoring locations, Pinchin has not identified any significant landfill related impacts at the Site aside from the SEEP. Concentrations of pH, TDS, iron, DOC, aluminum and manganese parameters within the groundwater samples analyzed at the furthest downgradient monitoring locations (BH5-II,



BH6-III, BH7-II, BH8-I and BH9-I) which exceeded the Guideline B-7 criteria are likely attributed to either naturally occurring conditions within the shallow unconfined aquifer on-site or from temperate impacts from leachate sourced from the waste deposits at the Site. All exceedances of the Guideline B-7 RUC are related to operational guidelines and/or aesthetic objectives associated with drinking water systems set by the ODWQS and are not considered to be an immediate significant human health or environmental concern originating from the Site. In addition, no exceedances of the APVs were quantified in any of the monitoring wells in the vicinity of the adjacent surface water features. The elevated concentrations of nitrate are only quantified in some downgradient wells; however, did not exceed the Guideline B-7 criteria in 2025 and often fluctuate throughout the historical record; seasonal fluctuations are also observed with higher concentrations quantified during the fall events. These concentrations are generally stable or decreasing but should be confirmed during the next monitoring period.

6.0 RECOMMENDATIONS

Based on a review of the existing dataset and regulatory requirements to date, Pinchin recommends the following:

- Continue with routine monitoring of all the available groundwater monitoring wells and surface water monitoring locations during the spring and fall. Groundwater and surface water monitoring shall be completed with analyses for the parameters identified in the historical monitoring record. Monitoring well BH4-II should also be analyzed for mercury and VOCs. Considering the dataset completed thus far, it is Pinchin's opinion that sampling should continue in 2026 before the adequacy of the monitoring program can be fully evaluated;
- Rehabilitation of the SEEP should be initiated in order to address the potential associated impacts to the adjacent surface water receptor; and
- The Client should continue to ensure that the requirements as specified in the CofA are complied with.

7.0 MONITORING AND SCREENING CHECKLIST

In accordance with the MECP Landfill Standards, the Monitoring and Screening Checklist for the Site completed by the Pinchin CEP is completed and provided in Appendix IX.



8.0 DISCLAIMER

This Water Quality Monitoring Program was performed for the Corporation of the Municipality of Magnetawan (Client) in order to investigate the environmental condition of the groundwater and surface water at the Chapman Waste Disposal Site (Site). The term recognized environmental condition means the presence or likely presence of any hazardous substance on a property under conditions that indicate an existing release, past release, or a material threat of a release of a hazardous substance into structures on the property or into the ground, groundwater, or surface water of the property.

This Water Quality Monitoring Program does not quantify the extent of the current and/or recognized environmental condition or the cost of any remediation.

Conclusions derived are specific to the immediate area of study and cannot be extrapolated extensively away from sample locations. Samples have been analyzed for a limited number of contaminants that are expected to be present at the Site, and the absence of information relating to a specific contaminant does not indicate that it is not present.

No environmental site assessment can wholly eliminate uncertainty regarding the potential for recognized environmental conditions on a property. Performance of this Water Quality Monitoring Program to the standards established by Pinchin is intended to reduce but not eliminate uncertainty regarding the potential for recognized environmental conditions on the Site and recognizes reasonable limits on time and cost.

This Water Quality Monitoring Program was performed in general compliance with currently acceptable practices for environmental site investigations and specific Client requests as applicable to this Site.

This report was prepared for the exclusive use of the Client subject to the conditions and limitations contained within the duly authorized work plan. Any use which a third party makes of this report, or any reliance on or decisions to be made based on it is the responsibility of the third parties. If additional parties require reliance on this report, written authorization from Pinchin will be required. Pinchin disclaims responsibility of consequential financial effects on transactions or property values, or requirements for follow up actions and costs. No other warranties are implied or expressed. Furthermore, this report should not be construed as legal advice.

Pinchin will not be responsible for any consequential or indirect damages. Pinchin will only be held liable for damages resulting from the negligence of Pinchin. Pinchin will not be liable for any losses or damage if the Client has failed within a period of two years following the date upon which the claim is discovered within the meaning of the Limitations Act, 2002 (Ontario) to commence legal proceedings against Pinchin to recover such losses or damage.



2025 Annual Monitoring Report

Chapman Waste Disposal Site, Magnetawan, Ontario
Municipality of Magnetawan

February 13, 2026


Pinchin File: 225335.010


Pinchin makes no other representations whatsoever, including those concerning the legal significance of its findings, or as to other legal matters touched on in this report, including, but not limited to ownership of any property, or the application of any law to the facts set forth herein. With respect to regulatory compliance issues, regulatory statutes are subject to interpretation, and these interpretations may change over time.

\\pin-sud-fs01\job\225000s\0225335.000 magnetawan, chapmansite, edr, landfill\0225335.010 magnetawan, chapmansite, edr, amr, 2025\deliverables\reports\chapman\225335.010 2025 amr chapman wds magnetawan.doc

Template: Groundwater Monitoring Report Template, EDR, May 28, 2019

APPENDIX I
Figures



	PROJECT NAME:		2025 ANNUAL MONITORING REPORT		
	CLIENT NAME:		MUNICIPALITY OF MAGNETAWAN		
	PROJECT LOCATION:		CHAPMAN WASTE DISPOSAL SITE, MAGNETAWAN, ONTARIO		
	FIGURE NAME:		KEY MAP		FIGURE NUMBER
	PROJECT NUMBER:	SCALE:	DRAWN BY:	REVIEWED BY:	DATE:
225335.010	AS SHOWN	NJ	JP	FEBRUARY2026	1




- LEGEND**
- - - SITE BOUNDARY
 - - - UAV IMAGE
 - - - PREVIOUSLY PROPOSED 1.2 Ha WASTE BOUNDARY
 - - - NEWLY PROPOSED 1.2 Ha WASTE BOUNDARY
 - - - TREE LINE

LEGEND IS COLOUR DEPENDENT. NON-COLOUR COPIES MAY ALTER INTERPRETATION.



PROJECT NAME:	
2025 ANNUAL MONITORING REPORT	
CLIENT NAME:	
MUNICIPALITY OF MAGNETAWAN	
PROJECT LOCATION:	
CHAPMAN WASTE DISPOSAL SITE, MAGNETAWAN, ONTARIO	
FIGURE NAME:	
SITE PLAN	
PROJECT NUMBER:	SCALE:
225335.010	AS SHOWN
DRAWN BY:	REVIEWED BY:
NJ	JP
DATE:	FIGURE NUMBER:
FEBRUARY 2026	2



606600.000

606800.000

607000.000

5063400.000

5063200.000

5063000.000

606600.000

606800.000

607000.000



LEGEND

- EXTENT OF SURVEY IMAGE
- EXISTING GROUND MAJOR CONTOUR LINES (5 m)
- EXISTING GROUND MINOR CONTOUR LINES (1 m)
- ACCESS ROAD
- PROPOSED WASTE BOUNDARY

LEGEND IS COLOUR DEPENDENT. NON-COLOUR COPIES MAY ALTER INTERPRETATION.



PROJECT NAME:

2025 ANNUAL MONITORING REPORT

CLIENT NAME:

MUNICIPALITY OF MAGNETAWAN

PROJECT LOCATION:

CHAPMAN WASTE DEPOSIT SITE
MAGNETAWAN, ONTARIO


FIGURE NAME:


TOPOGRAPHIC SURVEY

PROJECT NUMBER: 225335.010	SCALE: AS SHOWN
-------------------------------	--------------------

DRAWN BY: KL	REVIEWED BY: JP
-----------------	--------------------

DATE: FEBRUARY 2026	FIGURE NUMBER: 3
------------------------	---------------------





- LEGEND**
- - - SITE BOUNDARY
 - - - UAV IMAGE
 - PREVIOUSLY PROPOSED 1.2 Ha LANDFILL BOUNDARY
 - NEWLY PROPOSED 1.2 Ha LANDFILL BOUNDARY
 - CREEK
 - TREE LINE
 - MONITORING WELL
 - ▲ SURFACE WATER WELL

LEGEND IS COLOUR DEPENDENT.
NON-COLOUR COPIES MAY ALTER
INTERPRETATION.




PROJECT NAME:
**2025 ANNUAL MONITORING
REPORT**


CLIENT NAME:
**MUNICIPALITY OF
MAGNETAWAN**

PROJECT LOCATION:
**CHAPMAN WASTE DISPOSAL
SITE, MAGNETAWAN, ONTARIO**

FIGURE NAME:
MONITORING LOCATIONS

PROJECT NUMBER: 225335.010	SCALE: AS SHOWN
DRAWN BY: NJ	REVIEWED BY: JP
DATE: FEBRUARY 2026	FIGURE NUMBER: 4





SW2 (Culvert on Millers Road)



- LEGEND**
- - - SITE BOUNDARY
 - - - UAV IMAGE
 - - - PREVIOUSLY PROPOSED 1.2 Ha LANDFILL BOUNDARY
 - - - NEWLY PROPOSED 1.2 Ha LANDFILL BOUNDARY
 - CREEK
 - - - TREE LINE
 - MONITORING WELL
 - GROUNDWATER CONTOUR LINES
 - 100.0 MONITORING WELL ELEVATION (masl.)
 - 100.0 GROUNDWATER CONTOUR ELEVATION (masl.)
 - ➔ GROUNDWATER FLOW DIRECTION

LEGEND IS COLOUR DEPENDENT. NON-COLOUR COPIES MAY ALTER INTERPRETATION.




PROJECT NAME:
2025 ANNUAL MONITORING REPORT


CLIENT NAME:
MUNICIPALITY OF MAGNETAWAN

PROJECT LOCATION:
CHAPMAN WASTE DISPOSAL SITE, MAGNETAWAN, ONTARIO

FIGURE NAME:
INFERRED GROUNDWATER CONTOUR PLAN -SPRING 2025

PROJECT NUMBER: 225335.010	SCALE: AS SHOWN
DRAWN BY: NJ	REVIEWED BY: JP
DATE: FEBRUARY 2026	FIGURE NUMBER: 5





SW2 (Culvert on
Millers Road)



- LEGEND**
- - - SITE BOUNDARY
 - - - UAV IMAGE
 - - - PREVIOUSLY PROPOSED 1.2 Ha LANDFILL BOUNDARY
 - - - NEWLY PROPOSED 1.2 Ha LANDFILL BOUNDARY
 - CREEK
 - - - TREE LINE
 - MONITORING WELL
 - GROUNDWATER CONTOUR LINES
 - 100.0 BOREHOLE ELEVATION (masl.)
 - 100.0 GROUNDWATER CONTOUR ELEVATION (masl.)
 - ➔ GROUNDWATER FLOW DIRECTION

LEGEND IS COLOUR DEPENDENT.
NON-COLOUR COPIES MAY ALTER
INTERPRETATION.




PROJECT NAME:
2025 ANNUAL MONITORING
REPORT

CLIENT NAME:
MUNICIPALITY OF
MAGNETAWAN

PROJECT LOCATION:
CHAPMAN WASTE DISPOSAL
SITE, MAGNETAWAN, ONTARIO

FIGURE NAME:
INFERRED GROUNDWATER
CONTOUR PLAN -FALL 2025

PROJECT NUMBER: 225335.010	SCALE: AS SHOWN
DRAWN BY: NJ	REVIEWED BY: JP
DATE: FEBRUARY 2026	FIGURE NUMBER: 6



APPENDIX II
Certificate of Approval



Ministry
of the
Environment

Ontario

Provisional Certificate No. A 521202

PROVISIONAL CERTIFICATE OF APPROVAL WASTE DISPOSAL SITE

Under The Environmental Protection Act, 1971 and the regulations and subject to the limitations thereof, this Provisional Certificate of Approval is issued to:

Township of Chapman
Box 70, R.R. # 1
Magnetawan, Ontario
POA 1P0

for the use and operation of a 1.2 hectare dump site

all in accordance with the following plans and specifications:


Located: Lot 108, Concession A
Township of Chapman
District of Parry Sound

which includes the use of the site only for the receiving and disposal of the following categories of waste (NOTE: Use of the site for additional categories of wastes requires a new application and amendments to the Provisional Certificate of Approval) domestic and commercial wastes.

and subject to the following conditions:

1. No operation shall be carried out at the site after sixty days from this condition becoming enforceable unless this Certificate including the reasons for this condition has been registered by the applicant as an instrument in the appropriate Land Registry Office against title to the site and a duplicate registered copy thereof has been returned by the applicant to the Director.

Dated this 20th day of March, 1980.


Director, Section 39,
The Environmental Protection Act, 1971

APPENDIX III
Borehole Logs



Log of Borehole: BH3-II

Project #: 225335.001

Logged By: KM

Project: Hydrogeology Assessment

Client: Municipality of Magnetawan

Location: Chapman Waste Disposal Site, Magnetawan, Ontario

Drill Date: September 28, 2018

Project Manager: TM

SUBSURFACE PROFILE					SAMPLE	
Depth	Symbol	Description	Measured Depth (m)	Monitoring Well Details	Sample #	Recovery (%)
0		Ground Surface	0.00			
1		Sand Brown sand, some gravel, dry, no PHC odour or staining.				
2						
3						
4						
5						
6						
7						
8						
9						
10			3.05			
11		Sand and Silt Grey sand and silt, damp, no PHC odour or staining.	3.66		SS1	
12						
13		Sand and Silt Grey sand and silt, saturated, no PHC odour or staining.				
14						
15						
16					SS2	
17						
18						
19						
20			6.10			
21		End of Borehole				
22						
23						
24						
25						

Contractor: CCC

957 Cambrian Heights Drive

Grade Elevation: NA

Drilling Method: Hollow Auger

Suite 203

Top of Casing Elevation: NA

Well Casing Size: 5.08 cm

Sudbury, ON P3C 5S5

Sheet: 1 of 1



Log of Borehole: BH4-II

Project #: 225335.001

Logged By: KM

Project: Hydrogeology Assessment

Client: Municipality of Magnetawan

Location: Chapman Waste Disposal Site, Magnetawan, Ontario

Drill Date: September 27, 2018

Project Manager: TM

SUBSURFACE PROFILE					SAMPLE	
Depth	Symbol	Description	Measured Depth (m)	Monitoring Well Details	Sample #	Recovery (%)
0		Ground Surface	0.00			
1		Sand Coarse brown sand, some gravel, dry, no PHC odour or staining.				
2						
3						
4						
5						
6						
7						
8			3.05			
9						
10						
11		Sand and Gravel Coarse brown sand and gravel, trace cobbles, damp, no PHC odour or staining.			SS1	
12						
13			3.96			
14						
15		Bedrock Bedrock.				
16						
17		Auger refusal on assumed bedrock.				
18						
19						
20		Sandseam at 20'.				
21						
22						
23						
24						
25						
26						
27			8.44			
28		End of Borehole				
29						
30						

Contractor: CCC

957 Cambrian Heights Drive

Grade Elevation: NA

Drilling Method: Hollow Auger

Suite 203

Top of Casing Elevation: NA

Well Casing Size: 5.08 cm

Sudbury, ON P3C 5S5

Sheet: 1 of 1



Log of Borehole: BH6-III

Project #: 225335.001

Logged By: KM

Project: Hydrogeology Assessment

Client: Municipality of Magnetawan

Location: Chapman Waste Disposal Site, Magnetawan, Ontario

Drill Date: September 28, 2018

Project Manager: TM

SUBSURFACE PROFILE					SAMPLE		
Depth	Symbol	Description	Measured Depth (m)	Monitoring Well Details	Sample #	Recovery (%)	
0		Ground Surface	0.00				
1		Sand and Gravel Coarse sand and gravel, some cobbles, damp, no PHC odour or staining.					
2							
3							
4							
5							
6							
7							
8							
9							
10			3.05				
11		Sand and Gravel Coarse sand and gravel, large cobbles, damp, no PHC odour or staining.			SS1		
12							
13		Bedrock Bedrock.	3.96				
14							
15							
16							
17							
18							
19		Auger refusal on assumed bedrock.					
20							
21			6.30				
22		End of Borehole					
23							
24							
25							

Contractor: CCC

957 Cambrian Heights Drive

Grade Elevation: NA

Drilling Method: Hollow Auger

Suite 203

Top of Casing Elevation: NA

Well Casing Size: 5.08 cm

Sudbury, ON P3C 5S5

Sheet: 1 of 1



Log of Borehole: BH8-1

Project #: 225335.001

Logged By: KM

Project: Hydrogeology Assessment

Client: Municipality of Magnetawan

Location: Chapman Waste Disposal Site, Magnetawan, Ontario

Drill Date: September 27, 2018

Project Manager: TM

SUBSURFACE PROFILE					SAMPLE	
Depth	Symbol	Description	Measured Depth (m)	Monitoring Well Details	Sample #	Recovery (%)
0		Ground Surface	0.00			
1		Sand Coarse, brown sand with some gravel, no PHC odour or staining.				
2						
3						
4						
5						
6			4.27			
7		Sand and Gravel Coarse, brown sand and gravel, trace cobbles, no PHC odour or staining.				
8						
9						
10						
11					SS1	
12						
13						
14						
15						
16					SS2	
17						
18						
19						
20			6.05			
21		End of Borehole				
22						
23						
24						
25						

Contractor: CCC

957 Cambrian Heights Drive

Grade Elevation: NA

Drilling Method: Hollow Auger

Suite 203

Top of Casing Elevation: NA

Well Casing Size: 5.08 cm

Sudbury, ON P3C 5S5

Sheet: 1 of 1



Log of Borehole: BH9-I

Project #: 225335.001

Logged By: KM

Project: Hydrogeology Assessment

Client: Municipality of Magnetawan

Location: Chapman Waste Disposal Site, Magnetawan, Ontario

Drill Date: September 28, 2018

Project Manager: TM

SUBSURFACE PROFILE					SAMPLE	
Depth	Symbol	Description	Measured Depth (m)	Monitoring Well Details	Sample #	Recovery (%)
0		Ground Surface	0.00			
1		Sand Coarse brown sand, damp, no PHC odour or staining.				
2						
3						
4						
5						
6						
7						
8						
9						
10						
11					SS1	
12						
13						
14			4.27			
15		Sand and Silt Coarse brown sand and fine brown sand and silt, trace gravel, saturated, no PHC odour or staining.			AS1	
16						
17						
18						
19						
20						
21						
22						
23						
24		Refusal at 27' on assumed bedrock.			AS2	
25						
26						
27			8.23			
28		End of Borehole				
29						
30						

Contractor: CCC

957 Cambrian Heights Drive

Grade Elevation: NA

Drilling Method: Hollow Auger

Suite 203

Top of Casing Elevation: NA

Well Casing Size: 5.08 cm

Sudbury, ON P3C 5S5

Sheet: 1 of 1



Log of Borehole: BH10-I

Project #: 225335.001

Logged By: KM

Project: Hydrogeology Assessment

Client: Municipality of Magnetawan

Location: Chapman Waste Disposal Site, Magnetawan, Ontario

Drill Date: September 26, 2018

Project Manager: TM

SUBSURFACE PROFILE					SAMPLE	
Depth	Symbol	Description	Measured Depth (m)	Monitoring Well Details	Sample #	Recovery (%)
0		Ground Surface	0.00			
1		Sand Coarse, brown sand, some gravel, trace cobbles, damp, no PHC odour or staining.				
2						
3						
4			1.52			
5		Bedrock Refusal on assumed bedrock.				
6						
7						
8						
9						
10						
11						
12						
13						
14						
15						
16			4.88			
17		End of Borehole				
18						
19						
20						
21						
22						
23						
24						
25						

Contractor: CCC

957 Cambrian Heights Drive

Grade Elevation: NA

Drilling Method: Hollow Auger

Suite 203

Top of Casing Elevation: NA

Well Casing Size: 5.08 cm

Sudbury, ON P3C 5S5

Sheet: 1 of 1



Log of Borehole: BH11

Project #: 225335

Logged By: KM

Project: Hydrogeology Assessment

Client: Municipality of Magnetawan

Location: Chapman Waste Disposal Site, Magnetawan, Ontario

Drill Date: September 26, 2018

Project Manager: TM

SUBSURFACE PROFILE					SAMPLE	
Depth	Symbol	Description	Measured Depth (m)	Monitoring Well Details	Sample #	Recovery (%)
0		Ground Surface	0.00			
1		Sand and Silt Brown sand with silt, damp, no PHC odour or staining.			SS1	
2						
3						
4						
5			3.05			
6		Sand Coarse, brown sand, saturated, no PHC odour or staining.			SS2	
7						
8						
9						
10						
11						
12						
13						
14						
15						
16			4.88		AS1	
17		End of Borehole				
18						
19						
20						
21						
22						
23						
24						
25						

Contractor: CCC

957 Cambrian Heights Drive

Grade Elevation: NA

Drilling Method: Hollow Auger

Suite 203

Top of Casing Elevation: NA

Well Casing Size: 5.08 cm

Sudbury, ON P3C 5S5

Sheet: 1 of 1

APPENDIX IV
Summary Tables

TABLE 1
Groundwater Monitoring Well Data
Chapman Waste Disposal Site
Magnetawan , Ontario

Well ID	Date (dd/mm/yyyy)	Ground Surface Elevation (masl)	TOC Elevation (masl)	Height of TOC from Ground Surface (m)	Water Level Measurement from TOC (m)	Total Well Depth from TOC (m)	Depth to Groundwater (mbgs)	Calculated Water Level Elevation (masl)	UTM Coordinates			Comments					
									Zone	Northing (m)	Easting (m)						
BH1	13-May-15	313.01	314.06		6.31			308.18	17	606939	5063235						
	22-Oct-15				6.93		307.56										
	13-Oct-16				6.83		307.66										
	18-May-17				5.80		308.69										
	25-Oct-17				6.41		308.08										
	2-May-18				6.01		308.48										
	17-Oct-18				6.60		307.89										
	11-Jun-19				1.03	6.10	11.25	5.07				308.39					
	26-Sep-19				0.94	6.79	11.20	5.85				307.70					
	1-Jun-20				0.94	6.56	10.74	5.62				307.50					
	30-Sep-20				1.03	6.75	11.20	5.72				307.31	No well cap				
	12-May-21				1.14	6.45	11.34	5.31				307.61	No well cap				
	6-Oct-21				1.14	6.55	11.27	5.41				307.51					
	4-May-22				1.06	6.16	11.24	5.1				307.90					
	19-Oct-22				1.14	6.83	11.24	5.69				307.23					
	10-May-23				1.14	5.79	11.18	4.65				308.27					
	28-Sep-23				1.14	6.86	11.21	5.72				307.20	PVC too tall to close casing lid.				
	23-Apr-24				1.14	5.91	11.25	4.77				308.15	Cannot close lid				
	2-Oct-24				0.99	6.9	11.09	5.91				307.16	0.10 m cut off PVC (after water level measured)				
	7-May-25				0.96	5.97	11.28	5.01				308.09					
26-Sep-25		0.98	9.64	11.10	8.66	304.42											
BH2	8-May-14	313.22	313.68		4.73			308.95	17	606927	5063213						
	30-Oct-14				5.78		307.90										
	13-May-15				5.77		307.91										
	22-Oct-15				6.46		307.22										
	13-Oct-16				6.36		307.32										
	18-May-17				5.2		308.48										
	25-Oct-17				5.9		307.78										
	2-May-18				5.47		308.21										
	17-Oct-18				6.08		307.60										
	11-Jun-19				0.39	5.57	9.80	5.18				308.11					
	26-Sep-19				0.36	6.08	9.68	5.72				307.60					
	1-Jun-20				0.36	6.04	6.72	5.68				307.64					
	30-Sep-20				0.41	6.28	9.71	5.87				307.40	No well cap				
	12-May-21				0.42	5.91	9.73	5.49				307.77					
	6-Oct-21				0.42	5.82	9.78	5.40				307.86					
	4-May-22				0.41	5.6	9.76	5.19				308.08					
	19-Oct-22				0.43	6.34	9.80	5.91				307.34					
	10-May-23				0.43	5.19	9.68	4.76				308.49					
	28-Sep-23				0.43	6.39	9.78	5.96				307.29	Clear, no odour, well casing short				
	23-Apr-24				0.43	5.50	9.78	5.07				308.18					
2-Oct-24		0.41	6.42	9.87	6.01	307.26											
7-May-25		0.41	5.53	9.89	5.12	308.15	Culvert W= 0.61 D=0.3M flow 0.2m/s										
26-Sep-25		0.41	6.38	9.73	5.97	307.30	No well cap										
BH3	8-May-14	N/A	314.49		5.32			321.31	17	N/A	N/A						
	30-Oct-14				6.52		320.11										
	13-May-15				6.39		320.24										
	22-Oct-15				7.47		319.16										
	13-Oct-16				7.4		319.23										
	18-May-17				5.86		308.63										
	25-Oct-17				-		-										
	2-May-18				-		-										
	17-Oct-18				-		-										
	11-Jun-19												DESTROYED				
BH3-II	11-Jun-19	322.4	323.3	0.80	3.54	6.70	2.74	319.74	17	606650	5063158	Installed new tubing.					
	26-Sep-19			0.77	4.55	6.50	3.78	318.73									
	1-Jun-20			0.77	4.04	6.50	3.27	319.24									
	30-Sep-20			0.81	4.5	6.54	3.69	318.78									
	12-May-21			0.83	4.46	6.58	3.63	318.82									
	6-Oct-21			0.83	4.38	6.57	3.55	318.90									
	4-May-22			0.83	3.77	6.40	2.94	319.51									
	19-Oct-22			0.83	4.64	6.54	3.81	318.64									
	10-May-23			0.83	3.56	6.48	2.73	319.72									
	28-Sep-23			0.83	4.56	6.48	3.73	318.72				PVC too tall to close casing lid.					
	23-Apr-24			0.78	4.08	6.57	3.3	319.20				Tree fallen, no damage to well					
	2-Oct-24			0.65	4.48	6.47	3.83	318.80				0.12 m cut from PVC (after water level measured)					
	7-May-25			0.67	3.69	6.38	3.02	319.59				Silty					
	26-Sep-25			0.68	4.38	6.54	3.70	318.90				GW Dup 1					
BH4	13-May-15	314.00	314.38		5.63			309.15	17	606912	5063195						
	22-Oct-15				6.39		308.39										
	13-Oct-16				5.99		308.79										
	18-May-17				5.43		309.35										
	25-Oct-17				6.19		308.59										
	2-May-18				-		-										
	17-Oct-18				5.52		309.26										
	11-Jun-19				0.35	5.67	6.34	5.32				309.11					
	26-Sep-19				0.28	5.75	6.38	5.47				309.03					
	1-Jun-20												No sample				
	30-Sep-20				0.37	5.9	6.35	5.53				308.48	No well cap				
	12-May-21				0.36	5.77	6.42	5.41				308.61	No well cap				
	6-Oct-21				0.36	5.45	6.34	5.09				308.93					
	4-May-22				0.34	5.53	6.40	5.19				308.85					
	19-Oct-22				0.34	5.7	6.40	5.36				308.68					
	10-May-23				0.34	5.29	6.40	4.95				309.09					
	28-Sep-23				0.34	6.12	6.41	5.78				308.26	Clear, no odour, well casing short				
	23-Apr-24				0.35	5.29	6.49	4.94				309.09					
	2-Oct-24				0.33	6.33	6.54	6.00				308.05	Insufficient volume - no sample.				
	7-May-25				0.34	5.55	6.11	5.21				308.83					
26-Sep-25		0.35	6.36	6.41	6.01	308.02	Insufficient volume - no sample. No well cap										

TABLE 1
Groundwater Monitoring Well Data
Chapman Waste Disposal Site
Magnetawan , Ontario

Well ID	Date (dd/mm/yyyy)	Ground Surface Elevation (masl)	TOC Elevation (masl)	Height of TOC from Ground Surface (m)	Water Level Measurement from TOC (m)	Total Well Depth from TOC (m)	Depth to Groundwater (mbgs)	Calculated Water Level Elevation (masl)	UTM Coordinates			Comments
									Zone	Northing (m)	Easting (m)	
BH4-II	11-Jun-19	313.67	314.61	0.73	5.87	8.51	5.14	-	17	606910	5063197	Needs new tubing.
	26-Sep-19			0.63	8.42	5.87	7.79	-				Installed new tubing.
	1-Jun-20			0.63	6.07	8.58	5.44	308.54				
	30-Sep-20			0.74	6.05	8.39	5.31	308.56				
	12-May-21			0.74	5.94	8.50	5.20	308.67				
	6-Oct-21			0.74	5.72	8.60	4.98	308.89				
	4-May-22			0.71	5.82	8.46	5.11	308.79				
	19-Oct-22			0.74	5.96	8.46	5.22	308.65				
	10-May-23			0.72	5.57	8.47	4.85	309.04				
	28-Sep-23			0.72	6.26	8.45	5.54	308.35				Clear, no odour, good well condition
	23-Apr-24			0.72	5.58	8.42	4.86	309.03				
	2-Oct-24			0.68	7.38	8.40	6.70	307.23				
	7-May-25			0.70	5.79	8.47	5.09	308.82				
	26-Sep-25			0.69	6.44	8.43	5.75	308.17				GW Dup 2
	BH5-II			13-May-15	291.00	291.84	-	4.37				-
22-Oct-15		-	4.71	-			-	287.13				
13-Oct-16		-	4.67	-			-	287.17				
18-May-17		-	4.32	-			-	287.52				
25-Oct-17		-	4.47	-			-	287.37				
2-May-18		-	4.21	-			-	287.63				
17-Oct-18		-	4.52	-			-	287.32				
11-Jun-19		0.94	4.43	6.93			3.49	287.41				
26-Sep-19		0.84	4.64	6.84			3.80	287.20				
1-Jun-20		0.84	4.5	6.84			3.66	287.34				
30-Sep-20		0.96	4.62	6.95			3.66	287.22				
12-May-21		0.96	4.47	6.93			3.51	287.37				
6-Oct-21		0.96	4.47	6.92			3.51	287.37				
4-May-22		0.96	4.36	6.90			3.40	287.48				
19-Oct-22		0.96	4.61	6.93			3.65	287.23				
10-May-23		0.96	4.28	6.91			3.32	287.56				
28-Sep-23		0.96	4.64	6.91			3.68	287.20	Brown, no odour, good well condition			
23-Apr-24		0.94	4.30	6.87			3.36	287.54				
2-Oct-24		0.91	4.69	6.92			3.78	287.15				
7-May-25		0.88	4.31	7.05			3.43	287.53				
26-Sep-25	0.96	4.64	6.95	3.68	287.20							
BH6-II	13-May-15	N/A	N/A	-	-	-	-	-	17	606993	5063185	
	22-Oct-15			-	-	-	-	-				
	13-Oct-16			-	-	-	-	-				
	18-May-17			-	-	-	-	-				
	25-Oct-17			-	-	-	-	-				
	2-May-18			-	-	-	-	-				
	17-Oct-18			-	-	-	-	-				
	11-Jun-19			1.00	DRY	2.99	DRY	DRY				
	26-Sep-19			1.05	DRY	2.90	DRY	DRY				
	1-Jun-20			-	-	DRY	-	-				
	30-Sep-20			1.17	DRY	2.98	DRY	DRY				No cap, no tubing.
	12-May-21			2.98	DRY	1.17	DRY	DRY				Water level inconsistent
	6-Oct-21			2.97	DRY	-	DRY	DRY				Water level inconsistent
	4-May-22			-	DRY	-	DRY	DRY				
	19-Oct-22			-	DRY	2.97	DRY	DRY				
	10-May-23			1.18	DRY	2.97	DRY	DRY				
	28-Sep-23			1.18	DRY	2.98	DRY	DRY				Good well condition
	23-Apr-24			1.18	DRY	2.98	DRY	DRY				
	2-Oct-24			1.08	DRY	2.96	DRY	DRY				
	7-May-25			1.10	DRY	2.97	DRY	DRY				
26-Sep-25	1.10	DRY	2.98	DRY	DRY							
BH6-III	11-Jun-19	292.76	293.47	0.88	4.02	6.10	3.14	-	17	607006	5063197	Installed new tubing.
	26-Sep-19			0.62	5.11	6.51	4.49	-				
	1-Jun-20			0.62	4.36	6.51	3.74	289.11				
	30-Sep-20			0.67	4.83	6.57	4.16	288.64				
	12-May-21			0.67	4.21	6.52	3.54	289.26				
	6-Oct-21			0.67	4.65	6.63	3.98	288.82				
	4-May-22			0.67	3.76	6.67	3.09	289.71				
	19-Oct-22			0.67	5.18	6.57	4.51	288.29				
	10-May-23			0.67	3.58	6.48	2.91	289.89				
	28-Sep-23			0.67	5.11	6.50	4.44	288.36				Clear, no odour, good well condition
	23-Apr-24			0.70	4.10	6.52	3.4	289.37				
	2-Oct-24			0.74	5.17	6.57	4.43	288.30				
	7-May-25			0.77	3.70	6.57	2.93	289.77				
	26-Sep-25			0.78	5.04	6.57	4.26	288.43				
	BH7-II			13-May-15	309.12	310.02	-	1.63				-
22-Oct-15		-	2.15	-			-	307.87				
13-Oct-16		-	-	-			-	-				
18-May-17		-	1.64	-			-	308.38				
25-Oct-17		-	1.72	-			-	308.30				
2-May-18		-	1.29	-			-	308.73				
17-Oct-18		-	1.88	-			-	308.14				
11-Jun-19		0.94	1.67	2.78			0.73	308.35				
26-Sep-19		0.87	1.92	2.73			1.05	308.10				
1-Jun-20		0.87	1.91	2.73			1.04	308.11				
30-Sep-20		0.99	2.00	2.81			1.01	308.02				
12-May-21		1.00	1.84	2.79			0.84	308.18				
6-Oct-21		1.00	1.00	2.80			0.00	309.02				
4-May-22		1.00	1.63	2.78			0.63	308.39				
19-Oct-22		1.00	DRY	2.78			DRY	DRY				
10-May-23		1.00	1.61	2.78			0.61	308.41				
28-Sep-23		1.00	2.21	2.80			1.21	307.81	Brown, no odour, good well condition			
23-Apr-24		0.96	1.78	2.80			0.82	308.24				
2-Oct-24		0.96	2.21	2.81			1.25	307.81				
7-May-25		0.97	1.68	2.79			0.71	308.34				
26-Sep-25	0.97	2.31	2.80	1.34	307.71							
BH8-I	11-Jun-19	290.86	291.72	0.83	4.17	6.71	3.34	-	17	607052	5063239	Red/orange in colour. Needs new tubing.
	26-Sep-19			0.76	6.58	4.30	5.82	-				Installed new tubing.
	1-Jun-20			0.76	4.20	6.58	3.44	287.52				
	30-Sep-20			0.85	4.24	6.69	3.39	287.48				
	12-May-21			0.85	4.15	6.65	3.30	287.57				
	6-Oct-21			0.85	4.16	6.70	3.31	287.56				
	4-May-22			0.85	4.70	5.62	3.85	287.02				
	19-Oct-22			0.85	4.26	6.70	3.41	287.46				
	10-May-23			0.82	4.08	6.68	3.26	287.64				
	28-Sep-23			0.82	4.3	6.67	3.48	287.42				Orange, no odour, good well condition
	23-Apr-24			0.83	4.04	6.66	3.21	287.68				DUP2
	2-Oct-24			0.83	4.28	6.65	3.45	287.44				
	7-May-25			0.81	4.03	6.76	3.22	287.69				
	26-Sep-25			0.84	4.28	6.70	3.44	287.44				

TABLE 1
Groundwater Monitoring Well Data
Chapman Waste Disposal Site
Magnetawan , Ontario

Well ID	Date (dd/mm/yyyy)	Ground Surface Elevation (masl)	TOC Elevation (masl)	Height of TOC from Ground Surface (m)	Water Level Measurement from TOC (m)	Total Well Depth from TOC (m)	Depth to Groundwater (mbgs)	Calculated Water Level Elevation (masl)	UTM Coordinates			Comments
									Zone	Northing (m)	Easting (m)	
BH9-I	11-Jun-19	292.05	292.76	0.67	2.33	8.21	1.66	-	17	606985	5063240	Installed new tubing.
	26-Sep-19			0.62	2.40	8.09	1.78	-				
	1-Jun-20			0.62	2.49	8.02	1.87	290.27				
	30-Sep-20			0.65	2.65	8.11	2.00	290.11				
	12-May-21			0.65	2.45	8.14	1.80	290.31				
	6-Oct-21			0.65	2.46	8.13	1.81	290.30				
	4-May-22			0.65	2.30	8.10	1.65	290.46				
	19-Oct-22			0.65	2.81	8.16	2.16	289.95				
	10-May-23			0.65	2.19	8.07	1.54	290.57				
	28-Sep-23			0.65	2.85	8.08	2.20	289.91				
	23-Apr-24			0.68	2.26	8.11	1.58	290.50				
	2-Oct-24			0.67	2.89	8.11	2.22	289.87				
	7-May-25			0.70	2.32	8.26	1.62	290.44				
	26-Sep-25			0.70	2.86	8.11	2.16	289.90				
BH10-I	11-Jun-19	314.62	315.17	0.71	2.07	5.27	1.36	-	17	606825	5063079	
	26-Sep-19			0.64	2.13	5.11	1.49	-				
	1-Jun-20			0.64	2.22	5.11	1.58	312.95				
	30-Sep-20			0.70	2.24	5.32	1.54	312.93				
	12-May-21			0.70	2.30	5.30	1.60	312.87				
	6-Oct-21			0.70	2.06	5.32	1.36	313.11				
	4-May-22			0.73	2.20	5.33	1.47	312.97				
	19-Oct-22			0.74	2.13	6.26	1.39	313.04				
	10-May-23			0.70	2.09	5.23	1.39	313.08				
	28-Sep-23			0.70	2.55	5.33	1.85	312.62				
	23-Apr-24			0.75	2.1	5.28	1.35	313.07				
	2-Oct-24			0.69	2.51	5.42	1.82	312.66				
	7-May-25			0.73	2.2	5.23	1.47	312.97				
	26-Sep-25			0.71	2.58	5.26	1.87	312.59				
BH11	11-Jun-19	319.34	320.12	0.79	1.24	5.18	0.45	318.88	17	606694	5063095	Needs new tubing.
	26-Sep-19			0.70	1.73	5.13	1.03	318.39				
	1-Jun-20			0.70	1.5	5.13	0.80	318.62				
	30-Sep-20			0.82	1.72	5.14	0.9	318.40				
	12-May-21			0.79	1.42	5.13	0.63	318.70				
	6-Oct-21			0.79	1.66	5.20	0.87	318.46				
	4-May-22			0.80	1.30	5.18	0.50	318.82				
	19-Oct-22			0.80	1.82	5.19	1.02	318.30				
	10-May-23			0.79	1.2	5.20	0.41	318.92				
	28-Sep-23			0.79	1.92	5.20	1.13	318.20				
	23-Apr-24			0.80	2.91	5.21	2.11	317.21				
	2-Oct-24			0.77	1.8	5.26	1.03	318.32				
	7-May-25			0.76	1.33	5.24	0.57	318.79				
	26-Sep-25			0.81	2.25	5.18	1.44	317.87				

Notes:

- mbgs Meters below ground surface
- masl Meters above sea level
- TOC Top of casing
- NA No data available

TABLE 2
Surface Water Monitoring Location Data
Chapman Waste Disposal Site
Magnetawan, Ontario

Surface Water Monitoring Location	UTM Coordinates			Comments
	Zone	Easting (m)	Northing (m)	
SW1	17	606740	5063072	Spring - flow is 0.0.07 m/s
				Fall - flow is 0.0011 m ³ /s
SW2	17	607482	5063373	Spring - flow is 0.0244 m/s
				Fall - flow is 0.0092 m ³ /s
SW3	17	606914	5063195	Spring - 0.0094 m/s
				Fall - flow is 0.0016 m ³ /s
SEEP	17	606978	5063242	Spring - no flow
				Fall - no flow

TABLE 3
Groundwater Quality Results - BH-1
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation Sample Collection Date (07/05/2025) BH-1																				ODWQS	
		13-May-15	22-Oct-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25		26-Sep-25
pH Lab	pH Units	7.27	7.05	7.2	6.8	6.7	6.7	7	7.44	7.49	6.93	6.81	7.17	6.74	7.31	7.69	7.51	7.61	6.88	6.98	7.01	6.65	6.5-8.5
Conductivity	µS/cm	320	280	372	716	538	498	434	653	581	483	335	407	286	464	242	423	381	438	265	371	53	-
Hardness	mg/L	74	73	118	238	157	125	122	230	140	131	113	125	104	143	60	120	149	132	76.2	108	13.6	80-100
Total Dissolved Solids	mg/L	638	150	204	440	304	212	206	310	250	262	188	243	146	260	97	234	231	243	149	223	< 30	500
Alkalinity	mg/L	110	85	111	277	210	179	167	260	153	159	153	143	108	181	86	147	133	158	83	113	22	30-500
Chloride	mg/L	20	13	17	44	31	39	26	30.6	22.5	27.1	18.3	31.0	12	42	6	38	24	31	8	25	< 1	250
Sodium	mg/L	14	13	20.2	36	20	23.2	16.5	31.3	20.7	23.8	18.0	23.0	17	24.6	11	23.5	17	26.0	12	15.5	4.04	200
Calcium	mg/L	23	23	40.5	71.5	50.1	38.7	37.4	78.6	48.7	42.0	34.8	39.1	33	46.1	18	36.7	47	42.1	23	35.3	4.23	-
Magnesium	mg/L	4.2	3.9	4.13	14.5	7.7	6.84	6.88	8.27	4.36	6.34	6.27	6.55	5.53	6.69	3.39	6.84	7.75	6.56	4.46	4.87	0.726	-
Potassium	mg/L	13	7	10.1	21.2	14.4	11.6	7.14	12.5	20.8	10.2	9.1	9.2	9.14	14.2	6.10	9.25	3.65	12.3	6.74	10.3	2.00	-
Sulphate	mg/L	7	10	11	61	36	17	12	32.1	13.8	23.0	11.4	6.0	5	10	5	15	10	10	7	14	< 2	500
Ammonia	mg/L	8.4	2.6	1.44	7.19	8.55	7.51	2.87	7.2	7.18	3.76	3.53	2.77	0.96	3.97	2.75	3.25	0.29	4.29	3.10	3.80	< 0.1	-
Nitrate as N	mg/L	0.93	4.34	7.7	1.1	0.3	0.6	5	<0.10	10.8	0.6	4.2	1.0	4.42	0.07	4.92	1.32	6.85	< 0.06	8.99	3.77	0.82	10
Nitrite as N	mg/L	0.02	0.111	<0.05	<0.05	<0.05	<0.05	0.12	<0.10	0.16	<0.05	<0.05	< 0.03	< 0.03	< 0.03	0.04	< 0.03	< 0.03	< 0.03	< 0.03	0.03	< 0.03	1
Total Kjeldahl Nitrogen	mg/L	8.6	3.1	1.6	8.8	10.7	7.6	3.6	7.46	7.74	4.81	3.80	3.38	0.35	4.33	3.74	3.94	0.84	4.30	2.80	3.50	< 0.5	-
Phenolics	mg/L	<0.001	<0.001	<0.001	<0.001	0.002	<0.001	<0.001	0.001	<0.001	<0.001	0.001	< 0.002	< 0.002	< 0.002	0.00	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	-
Dissolved Organic Carbon	mg/L	4.4	4	4.6	10.4	9.3	4.3	8.9	6.3	6.9	6.7	7.0	6.0	9	5	6	4	6	4	4	3	5	5
Chemical Oxygen Demand	mg/L	6.2	<4	26	36	28	25	21	26	20	25	<5	15	10.0	26	8.0	16	27.0	14	12.0	< 8	< 8	-
Iron	mg/L	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.0001	<0.010	<0.010	0.016	0.032	< 0.007	0.01	0.01	0.01	< 0.007	0.02	0.024	< 0.007	< 0.007	< 0.007	0.3
Manganese	mg/L	1.8	12.5	4.26	7.81	4.26	3.6	2.47	1.00	7.81	4.26	4.41	6.19	0.67	4.69	2.75	6.1	0.33	3.46	2.86	2.47	0.0271	0.05
Phosphorus	mg/L	0.041	<0.02	<0.01	<0.00001	0.02	<0.01	0.02	0.02	<0.02	<0.02	<0.02	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	-
Orthophosphate	mg/L	<0.01	-	-	-	-	-	-	-	<0.10	<0.10	<0.10	< 0.03	-	< 0.03	-	< 0.03	< 0.03	< 0.03	< 0.03	-	< 0.03	-
Turbidity	NTU	1	0.7	1.0	1.5	1.8	2.1	6.4	1.9	7.0	3.4	2.2	1.0	0.79	0.13	8.20	1.3	2.10	2.0	0.90	0.4	5.2	5
Total Suspended Solids	mg/L	14	13	5	<2	6	<2	12	<10	72	<10	11	4	17	12	16	2	8	5	13	< 2	6	-
BOD	mg/L	<2	<2	3	<2	<2	<2	<2	<5	<5	<5	-	< 4	< 4	< 4	19.00	< 4	< 4	< 4	< 4	4	< 4	-
Anion Sum	-	3.05	2.6	3.50	8.13	5.84	5.08	4.67	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	3.04	2.38	3.50	6.87	4.37	3.8	3.34	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	0.1	NC	0.1	-8.4	-14.3	-14.3	-16.6	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	0.00019	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.002	<0.002	<0.0001	<0.0001	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	-
Aluminum	mg/L	0.023	0.017	0.012	0.026	0.029	0.027	0.016	0.022	0.026	0.045	0.026	0.027	0.01	0.032	0.01	0.027	0.01	0.024	0.01	0.016	0.009	0.1
Antimony	mg/L	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.003	<0.003	<0.001	<0.001	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.006
Arsenic	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.001	<0.003	<0.003	0.002	0.002	0.0007	0.0004	0.0006	0.0007	0.0004	0.0003	0.0007	0.0003	0.0004	< 0.0002	0.010
Barium	mg/L	0.14	0.071	0.105	0.301	0.177	0.088	0.163	0.103	0.078	0.093	0.165	0.177	0.103	0.16	0.05	0.11	0.04	0.130	0.05	0.107	0.00493	1
Beryllium	mg/L	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.001	<0.001	<0.0005	<0.0005	0.000015	0.000008	0.000019	0.000007	0.000023	0.000010	0.000012	0.000013	0.000021	0.000007	-
Bismuth	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002	<0.002	<0.002	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	-
Boron	mg/L	0.2	0.19	0.266	0.628	0.351	0.256	0.551	0.329	0.277	0.329	0.277	0.277	0.307	0.284	0.277	0.301	0.284	0.199	0.208	0.208	0.062	5
Cadmium	mg/L	<0.0001	<0.0001	0.0002	0.0002	0.0001	<0.0001	0.0001	<0.001	<0.001	<0.0001	<0.0001	0.000069	0.00004	0.000095	0.00003	0.000107	0.00002	0.000123	0.00003	0.000068	< 0.000003	0.005
Chromium	mg/L	<0.005	<0.005	<0.001	0.001	<0.001	0.005	<0.001	<0.003	<0.003	<0.002	0.003	0.00051	0.00036	0.00063	0.00037	0.00052	0.00038	0.00064	0.00036	0.000236	0.00029	0.05
Cobalt	mg/L	0.0035	0.0034	0.003	0.008	0.0072	0.008	0.0044	0.008	0.005	0.0076	0.0053	0.0061	0.00071	0.00634	0.00256	0.00686	0.00118	0.00367	0.00228	0.00040	0.000216	-
Copper	mg/L	0.006	0.0051	0.0058	0.0104	0.009	0.0067	0.0061	0.010	0.009	0.008	0.007	0.007	0.0049	0.0095	0.0065	0.0055	0.0062	0.008	0.0050	0.003	0.002	1
Molybdenum	mg/L	0.00061	0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.002	<0.002	<0.002	<0.002	0.00039	0.0002	0.00042	0.0006	0.00027	0.0002	< 0.0004	< 0.0004	< 0.0004	< 0.0004	-
Nickel	mg/L	0.0014	<0.001	0.002	0.004	0.002	0.002	0.001	<0.003	<0.003	<0.003	<0.003	0.0013	0.0008	0.0018	0.0007	0.0013	0.0011	0.0015	0.0008	0.0007	0.0002	-
Phosphate	mg/L	-	-	<0.0002	<0.0002	<0.0002	<0.2	<0.2	<0.20	-	-	-	-	-	-	-	-	-	-	< 0.03	-	-	-
Lead	mg/L	<0.0005	<0.0005	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.001	<0.001	<0.0005	<0.0005	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	0.01
Selenium	mg/L	<0.002	<0.002	<0.001	<0.001	0.001	<0.001	0.001	<0.004	<0.004	0.002	<0.001	0.00008	0.00009	0.0001	0.00007	0.00019	0.00008	0.00030	0.00007	0.00009	0.00007	0.05
Silicon	mg/L	4.6	3.6	3.63	3.46	5.56	5.35	3.15	-	-	-	0.18	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.001	<0.001	<0.005	<0.005	<0.005	<0.005	-	<0.002	<0.002	<0.002	<0.002	0.0001	< 0.00006	0.00008	< 0.00006	0.00009	0.00010	< 0.00006	< 0.00006	< 0.00006	< 0.00006	-
Strontium	mg/L	0.15	0.13	0.187	0.534	0.299	0.262	0.198	0.419	0.379	0.245	<0.0003	0.234	0.21	0.309	0.14	0.271	0.18	0.306	0.15	0.264	0.0206	-
Titanium	mg/L	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.002	<0.002	<0.002	<0.010	0.00011	0.00011	0.00019	0.00014	0.00036	0.00016	0.0002	0.00010	0.0001	< 0.0001	-
Uranium	mg/L	0.0006	0.00049	0.0007	0.0034	0.0015	0.001	0.001	0.004	<0.002	0.0006	<0.002	0.0006	0.00043	0.00077	0.00034	0.000545	0.00110	0.000654	0.00039	0.000343	0.000083	0.02
Vanadium	mg/L	<0.0005	<0.0005	0.0023	<0.0005	<0.0005	0.0082	<0.0005	<0.002	<0.002	<0.002	<0.005	0.00017	0.00006	0.00039	0.00011	0.0002	0.00009	0.00021	0.00012	0.00012	0.00006	-
Zinc	mg/L	0.013	<0.005	<0.005	<0.005	0.006	<0.005	<0.005	<0.005	<0.005	<0.005	-	0.002										

TABLE 4
Groundwater Quality Results - BH-2
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation																				ODWQS	
		Sample Collection Date (07/05/2025)																					
		BH-2																					
		13-May-15	22-Oct-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25	
pH Lab	pH Units	7.22	7.06	7.0	6.9	7.3	6.9	7.0	7.48	7.40	7.08	7.44	7.46	7.79	7.71	7.43	7.43	6.89	7.37	7.40	6.5-8.5	-	
Conductivity	µS/cm	1000	960	954	740	778	820	820	596	923	798	690	659	717	654	775	722	764	675	745	626	719	-
Hardness	mg/L	430	350	380	222	305	389	298	239	349	299	493	244	318	249	335	271	352	228	340	239	325	80-100
Total Dissolved Solids	mg/L	136	574	608	450	498	488	468	312	452	411	456	400	411	346	500	400	409	383	457	366	426	500
Alkalinity	mg/L	320	310	263	274	292	338	346	230	311	290	331	269	332	282	319	294	313	278	340	252	313	30-500
Chloride	mg/L	49	42	21	43	19	14	24	26.2	24.1	25.0	24.6	26.0	22.0	35	30.0	32	25.0	25	20.0	24	20	250
Sodium	mg/L	78	57	69.8	33.1	42.4	23.2	34.6	27.4	33.0	28.2	43.3	24.7	25.7	28.2	22.4	28.1	24.4	26.8	21.3	21.1	21.6	200
Calcium	mg/L	110	98	107	72.5	87.3	86.5	81.7	72.7	98.8	87.9	141.0	75.0	94.0	77.2	97.3	82.6	102.0	70.0	101.0	75.0	94.6	-
Magnesium	mg/L	34	25	27.4	9.9	21	41.9	22.9	13.9	24.9	19.3	34.3	13.8	20.3	13.6	22.2	15.6	23.7	12.9	21.4	12.5	21.6	-
Potassium	mg/L	7.5	6.4	5.93	19.1	5.69	5.36	7.1	11.9	6.7	9.29	10.00	11.00	7.63	12.5	6.43	12.3	7.29	12.5	7.23	11.1	7.43	-
Sulphate	mg/L	140	120	198	70	118	104	104	46.7	78.0	76.5	88.9	32.0	72.0	37	64.0	56	78.0	43	72.0	43	58	500
Ammonia	mg/L	0.7	0.6	0.18	14.4	1.61	0.04	0.73	5.86	0.51	1.60	0.19	5.33	0.06	6.18	1.64	4.85	0.52	4.97	0.40	6.70	0.8	-
Nitrate as N	mg/L	2.17	0.52	8.4	0.7	2.8	2.6	1.1	<0.20	<0.25	<0.1	0.2	0.09	0.4	<0.06	0.11	<0.06	<0.06	<0.06	<0.06	0.26	<0.06	10
Nitrite as N	mg/L	0.044	0.015	0.32	<0.05	0.13	<0.1	0.14	<0.20	<0.25	<0.1	<0.05	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	1
Total Kjeldahl Nitrogen	mg/L	1.8	1.5	1.0	14.4	2.1	0.7	1.3	6.63	1.11	3.05	0.80	5.93	0.41	6.26	2.02	5.17	0.90	5.36	0.70	6.40	1.3	-
Phenolics	mg/L	0.0013	<0.001	0.005	<0.001	<0.001	<0.001	<0.001	0.002	0.002	0.002	0.005	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-
Dissolved Organic Carbon	mg/L	18	14	12.8	10.2	10.2	10.7	8.4	11.0	10.0	11.1	11.1	11.0	11.0	12	9.0	12	8.0	10	8.0	8	10	5
Chemical Oxygen Demand	mg/L	36	33	55	45	30	31	34	25	26	34	<5	32	13	30	27	27	26	38	24	26	24	-
Iron	mg/L	<0.1	<0.1	<0.1	4.9	0.455	<0.1	0.585	9.71	0.53	1.93	0.705	7.12	0.704	10.8	1.89	8.9	1.44	10.6	1.92	5.4	2.21	0.3
Manganese	mg/L	1.2	1.1	1.4	6.14	0.975	1.16	1.38	4.06	1.51	4.84	3.05	1.78	4.17	2.22	4.84	2.11	2.32	5.28	2.31	3.65	2.40	0.05
Phosphorus	mg/L	0.071	0.18	0.57	<0.01	0.02	0.05	0.1	0.46	0.57	0.09	0.08	0.20	0.07	<0.03	0.04	0.07	0.04	0.09	0.25	<0.03	0.04	-
Orthophosphate	mg/L	<0.01	-	-	-	-	-	-	<0.50	<0.2	<0.10	<0.03	-	<0.03	-	<0.03	<0.03	0.04	-	<0.03	<0.03	-	
Turbidity	NTU	15	22	90.3	34.5	33.3	64.4	204	52.0	81.1	44.2	255	35	10	0.17	4	55	65	40	34	40	20	5
Total Suspended Solids	mg/L	66	62	222	24	47	50	152	289	230	152	841	15	117	53	53	215	72	160	260	30	23	-
BOD	mg/L	<2	<2	4	3	<2	<2	<2	<5	<5	<5	-	14	<4	<4	<4	<4	<4	<4	<4	<4	<4	-
Anion Sum	-	11	9.95	10.6	8.18	9.04	9.71	9.85	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	12.1	9.63	10.8	6.36	8.08	9.5	7.64	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	5.09	1.59	0.9	-12.5	-5.6	1	-12.6	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.002	<0.002	<0.0001	<0.0001	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	-
Aluminum	mg/L	0.1	0.0093	0.001	0.016	0.062	0.004	0.007	0.024	0.016	0.004	0.013	0.021	0.006	0.028	0.008	0.023	0.010	0.024	0.008	0.016	0.009	0.1
Antimony	mg/L	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.003	<0.003	<0.001	<0.001	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	0.006
Arsenic	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.003	<0.003	0.001	<0.001	0.0007	0.0004	0.0006	0.0006	0.0007	0.0004	0.0006	0.0004	0.0004	0.0005	0.010
Barium	mg/L	0.27	0.24	0.212	0.257	0.033	0.179	0.168	0.216	0.186	0.182	0.187	0.216	0.163	0.233	0.186	0.219	0.186	0.218	0.171	0.224	0.178	1.00
Beryllium	mg/L	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.001	<0.001	<0.0005	<0.0005	0.00001	<0.000007	0.000014	<0.000007	0.00003	0.000008	0.000015	0.000008	0.000008	0.000010	-
Bismuth	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002	<0.002	<0.002	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	-
Boron	mg/L	0.84	0.81	0.638	0.47	0.083	0.542	0.643	0.542	0.643	0.542	0.511	0.542	0.606	0.526	0.511	0.544	0.541	0.433	0.513	0.448	0.488	5
Cadmium	mg/L	0.00019	0.00013	<0.0001	0.0003	<0.0001	<0.0001	<0.0001	<0.001	<0.001	<0.0001	<0.0001	0.000079	0.000081	0.000064	0.000052	0.000088	0.00007	0.000076	0.000069	0.000079	0.000061	0.005
Chromium	mg/L	<0.005	<0.005	0.002	0.002	<0.001	0.006	<0.001	<0.003	<0.003	<0.002	<0.002	0.00091	0.00047	0.00094	0.00054	0.00107	0.00057	0.00100	0.00053	0.000524	0.00035	0.05
Cobalt	mg/L	0.0057	0.0048	0.0037	0.0101	0.003	0.0029	0.004	0.0038	0.004	0.0038	0.0030	0.0061	0.0036	0.00702	0.0032	0.00676	0.0033	0.00689	0.0038	0.00080	0.00318	-
Copper	mg/L	0.0097	0.0085	0.0076	0.0038	0.0005	0.006	0.0066	<0.003	0.004	0.003	0.005	0.003	0.003	0.0045	0.002	0.0028	0.004	0.002	0.003	0.003	0.003	1
Molybdenum	mg/L	0.00088	0.001	<0.0005	<0.0005	<0.0005	0.0006	0.0008	<0.002	<0.002	<0.002	0.01	0.00077	0.00074	0.00076	0.00094	0.0008	0.00083	0.0008	0.0008	0.0007	0.0008	-
Nickel	mg/L	0.0052	0.0032	0.004	0.004	<0.001	0.003	0.003	<0.003	0.003	<0.003	<0.003	0.0018	0.002	0.0021	0.0017	0.0022	0.0021	0.0021	0.0021	0.0022	0.0017	-
Phosphate	mg/L	-	-	<0.0002	<0.2	<0.0002	-	<0.0002	<0.40	-	-	-	-	-	-	-	-	-	-	<0.03	-	-	-
Lead	mg/L	<0.0005	<0.0005	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.001	<0.001	<0.0005	<0.0005	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	0.01
Selenium	mg/L	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	0.002	<0.004	<0.004	0.007	0.001	0.00014	0.00012	0.00014	0.00013	0.00018	0.0002	0.00032	0.00012	0.00012	0.00012	0.05
Silicon	mg/L	4.8	3.8	3.55	4.59	2.11	3.87	2.71	-	-	-	0.513	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.001	<0.001	<0.005	<0.005	<0.005	<0.005	<0.005	<0.002	<0.002	<0.002	<0.002	0.00011	0.00008	0.00018	0.00009	0.00013	0.00017	0.00006	0.00009	0.00007	0.00007	-
Strontium	mg/L	0.76	0.67	0.505	0.257	0.075																	

TABLE 5
Groundwater Quality Results - BH-3
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation																												ODWQS
		Sample Collection Date (dd/mm/yyyy)																												
		BH-3																												
		24-Sep-03	12-May-04	27-Oct-04	15-May-05	26-Oct-05	8-May-06	2-Nov-06	8-May-07	24-Oct-07	7-May-08	29-Oct-08	11-May-09	15-Oct-09	2-Jun-10	21-Oct-10	23-Jun-11	27-Oct-11	9-May-12	4-Oct-12	30-May-13	24-Oct-13	8-May-14	30-Oct-14	13-May-15	22-Oct-15	13-Oct-16	18-May-17		
pH Lab	pH Units	4.49	6.16	6.01	6.65	7.09	6.9	6.7	6	6.9	6.7	6.8	5.9	6.2	6.4	6.15	6.24	6.46	6.25	5.72	6.45	5.01	6.1	6.42	6.12	6.18	6.1	6.1	6.5-8.5	
Conductivity	µS/cm	560	41	46	31.9	37	34	39	134	41	89	44	54	40	60	69	70	40	46	41	61	63	33	38	70	37	64	85	-	
Hardness	mg/L	242	12	13	11.5	12	12	13	27	11	17	16	18	14	19	17	22	12	17	17	20	15	11	11	18	11	19	22	80-100	
Total Dissolved Solids	mg/L	395	92	36	480	130	34	27	66	25	60	30	37	30	40	42	40	22	30	<10	68	56	32	58	58	44	46	120	500	
Alkalinity	mg/L	-	6.6	3	11.1	8	8	7	2	5	3	5	7	10	6	7	6	6	6.1	4.1	3.8	<1	4.5	8.5	5.3	8.2	7	14	30-500	
Chloride	mg/L	4.6	1.4	0.9	1.63	2	2	1	30	3	17	4	5	2	6	12	7	2	2	2	3	3	1	1	14	2.1	3	5	250	
Sodium	mg/L	11.4	0.8	0.9	1.2	1.3	1.1	1.3	2.2	2.4	4.4	2.2	1.7	1.6	1.7	1.6	2.4	1.1	1.3	1.1	1.3	1.2	1	1.1	1.4	2	3.31	3.13	200	
Calcium	mg/L	87	4.3	4.4	5	4.3	4.2	4.4	9.2	3.6	5.8	5.1	6.1	4.8	6.3	5.7	7.3	4.1	5.5	5.7	6.7	5	3.8	3.8	6	3.7	6.51	7.55	-	
Magnesium	mg/L	6	0.41	0.51	0.71	0.67	0.44	0.62	1.1	0.45	0.68	0.68	0.73	0.6	0.82	0.76	0.8	0.49	0.65	0.78	0.83	0.59	0.37	0.39	0.76	0.42	0.546	0.647	-	
Potassium	mg/L	2	0.9	0.7	1.1	0.78	0.85	0.87	1	0.69	0.95	0.69	0.8	0.67	0.62	0.8	1.1	0.8	0.82	0.73	0.62	0.44	0.41	0.79	0.55	0.54	0.858	1.01	-	
Sulphate	mg/L	272	6.4	10.4	6.4	6	6	6	3	6	6	5	5	4	3	4	4	4	4	4	5	12	3	4	2	3.1	10	7	500.0	
Ammonia	mg/L	0.28	0.03	-	0.07	-	-	-	-	-	-	-	<0.05	<0.05	-	<0.05	<0.005	<0.05	<0.05	<0.05	0.18	<0.05	<0.05	<0.05	<0.05	<0.05	0.04	0.01	-	
Nitrate as N	mg/L	0.4	0.2	0.2	0.2	0.2	0.2	0.7	1.1	0.2	2	0.5	2.4	0.3	2	0.6	1.9	0.8	1.4	1	3.2	1.2	0.68	0.48	0.28	<0.1	1.6	2.8	10	
Nitrite as N	mg/L	-	-	-	-	-	-	-	-	-	-	-	0.01	<0.01	-	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	1	
Total Kjeldahl Nitrogen	mg/L	-	1.36	0.68	2.6	2.7	1	1.6	2.4	2.7	1.7	1.1	1.8	2.3	1.6	<1	1.5	2	0.76	<0.23	0.43	0.78	0.42	0.34	0.24	0.23	0.2	0.2	-	
Phenolics	mg/L	-	-	-	-	0.002	-	-	-	-	-	-	-	<0.001	-	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	-	
Dissolved Organic Carbon	mg/L	68.7	95.8	26.2	4	32.1	18.4	12.8	18.1	26.1	12.5	7.7	1.9	2.7	1.7	1.7	1.8	1.7	1.5	1.9	2.1	2.4	2.6	2.6	2.7	2.7	3.9	3.4	5	
Chemical Oxygen Demand	mg/L	-	254	64	110	110	56	36	60	96	47	21	51	67	15	17	32	61	14	13	13	4.9	7.4	13	4.2	7.8	29	20	-	
Iron	mg/L	56.2	0.09	0.4	1.9	2.1	0.055	1.6	0.073	0.25	-	0.64	<0.1	<0.1	-	<0.1	<0.1	<0.1	<0.1	0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	0.3	
Manganese	mg/L	3.01	0.02	0.028	0.045	0.092	0.015	0.087	0.028	0.011	0.026	0.053	0.046	0.045	0.018	0.056	0.011	0.016	0.0058	0.0052	0.0092	0.018	0.0068	0.0034	0.019	0.013	<0.005	0.011	0.05	
Phosphorus	mg/L	9.9	4.8	5.4	3.7	4	2.5	3.8	2.8	2.9	2.6	3	3	2.8	2.9	3	3	3	0.13	0.48	0.13	0.18	0.099	0.29	0.39	0.1	0.13	0.08	-	
Orthophosphate	mg/L	-	-	-	-	0.013	-	-	-	-	-	-	<0.01	<0.01	0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	0.014	<0.01	0.01	<0.01	-	-	-	-	
Turbidity	NTU	-	24	8.8	627	636	792	3170	1880	159	910	150	1900	770	660	500	290	120	120	320	34	81	45	63	37	51	40.4	35.1	5	
Total Suspended Solids	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	74	140	270	550	62	73	-	
BOD	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	<2	<2	<2	<2	<2	<2	-	
Anion Sum	-	-	-	-	-	-	-	-	-	0.331	0.796	0.362	0.56	0.384	-	0.598	0.534	0.314	0.362	0.278	0.488	0.399	0.252	0.321	0.583	0.288	0.54	0.78	-	
Cation Sum	-	-	-	-	-	-	-	-	-	0.385	0.576	0.524	0.472	0.389	-	0.447	0.568	0.319	0.414	0.426	0.498	0.386	0.288	0.303	0.456	0.332	0.54	0.59	-	
Ion Balance	%	-	-	-	-	-	-	-	-	NC	NC	NC	NC	NC	-	NC	NC	NC	NC	NC	NC	NC	NC	-	NC	NC	-0.2	-	-	
Silver	mg/L	-	-	-	0.0007	-	-	-	-	-	-	0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	0.00013	<0.0001	<0.0001	<0.0001	<0.0001	-	
Aluminum	mg/L	6.93	0.103	0.648	1.2	2.1	0.1	1.9	0.18	0.32	0.1	0.69	0.11	0.13	0.045	0.11	0.055	0.068	0.073	0.076	0.1	0.13	0.11	0.11	0.16	0.12	0.097	0.093	-	
Antimony	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	-	
Arsenic	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.010	
Barium	mg/L	0.121	0.013	0.014	0.022	0.021	0.012	0.022	0.026	0.011	0.021	0.018	0.017	0.011	0.017	0.018	0.027	0.013	0.018	0.018	0.021	0.021	0.017	0.018	0.022	0.013	0.029	0.059	1.00	
Beryllium	mg/L	0.0013	-	-	-	-	-	-	-	-	-	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	-	
Bismuth	mg/L	-	-	-	-	-	-	-	-	-	-	-	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	-	
Boron	mg/L	0.01	0.006	-	-	-	-	-	-	-	-	-	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	0.015	0.019	<0.01	0.023	0.017	<0.01	0.023	0.024	5	
Cadmium	mg/L	-	-	-	-	-	-	-	-	-	-	-	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	0.00018	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	0.005	
Chromium	mg/L	-	-	-	-	-	-	-	-	-	-	-	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.05	
Cobalt	mg/L	0.124	0.0002	0.0005	0.001	0.002	-	0.0018	-	-	0.011	0.0016	0.01	0.023	0.0009	0.01	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	0.0006	
Copper	mg/L	0.015	0.001	0.0017	0.006	0.005	-	0.004	-	0.001	-	0.003	0.001	<0.001	0.002	0.001	<0.001	<0.001	0.0011	0.0015	0.0012	0.0011	0.0011	0.0026	0.0014	0.0011	0.0024	0.0017	1	
Molybdenum	mg/L	-	-	-	-	-	-	-	-	-	-	-	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	-	
Nickel	mg/L	0.13	-	-	0.001	0.001	0.001	0.001	-	-	0.001	-	0.001	0.004	<0.001	0.002	<0.001	<0.001	<0.001	<0.001	<0.001	0.001	<0.001	<0.001	<0.001	<0.001				

TABLE 6
Groundwater Quality Results - BH-3-II
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation														ODWQS
		Sample Collection Date (07/05/2025)														
		BH3-II														
		11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25	
pH Lab	pH Units	6.58	6.37	6.57	6.17	6.55	6.16	6.58	6.95	6.58	7.02	6.44	6.28	6.37	6.41	6.5-8.5
Conductivity	µS/cm	56	65	49	70	39	42	29	46	35	44	32	44	30	37	-
Hardness	mg/L	4.9	4.1	6.7	22.4	5.8	5.6	5	6.8	6.8	5.4	7.0	4.7	5.0	3.9	80-100
Total Dissolved Solids	mg/L	84	42	42	48	< 30	110	< 30	51	37	43	37	43	51	< 30	500
Alkalinity	mg/L	18	20	17	16	11	13	9	15	10	12	7	11	8	10	30-500
Chloride	mg/L	1.54	0.85	1.44	12.7	2.0	4.0	3	1.0	5	2.0	< 1	2.0	4	2	250
Sodium	mg/L	11.7	10.6	5.27	3.98	3.90	7.74	3.66	5.96	3.83	5.98	3.48	4.41	3.41	4.59	200
Calcium	mg/L	1.53	1.29	2.12	7.43	1.86	1.76	1.54	2.24	2.11	1.60	2.20	1.46	1.58	1.20	-
Magnesium	mg/L	0.26	0.22	0.35	0.93	0.28	0.29	0.279	0.29	0.36	0.33	0.359	0.25	0.249	0.228	-
Potassium	mg/L	0.54	0.44	0.71	1.27	0.50	0.32	0.55	0.51	0.637	0.57	0.866	0.49	0.408	0.483	-
Sulphate	mg/L	5.64	6.33	4.94	5.38	10.00	15.00	18	7.00	10	8.00	8	15.00	15	12	500
Ammonia	mg/L	<0.02	0.12	<0.02	<0.02	< 0.04	0.04	< 0.04	0.04	< 0.04	< 0.04	< 0.04	< 0.1	< 0.1	< 0.1	-
Nitrate as N	mg/L	0.10	0.12	0.11	0.16	0.12	0.22	0.12	0.22	0.07	0.20	< 0.06	0.07	0.13	< 0.06	10
Nitrite as N	mg/L	<0.05	<0.05	<0.05	<0.05	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	1
Total Kjeldahl Nitrogen	mg/L	0.57	0.24	0.21	0.16	0.07	0.13	0.12	< 0.05	0.05	0.09	< 0.05	< 0.5	< 0.5	< 0.5	-
Phenolics	mg/L	0.001	<0.001	<0.001	<0.001	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	-
Dissolved Organic Carbon	mg/L	5.6	3.8	8.4	2.2	2	9	1	1	2	2	2	2	3	5	5
Chemical Oxygen Demand	mg/L	29	11	<5	<5	9	10	11	14	< 8	< 8	13	< 8	< 8	< 8	-
Iron	mg/L	<0.010	<0.010	0.018	0.028	0.031	0.043	0.023	0.017	0.149	0.017	0.281	0.02	0.021	0.024	0.3
Manganese	mg/L	0.022	0.008	0.018	0.05	0.01	0.01	0.00683	0.01	0.0242	0.01	0.0176	0.01	0.0077	0.00914	0.05
Phosphorus	mg/L	12.2	4.90	3.36	0.42	2.48	1.97	1.5	0.50	0.77	1.17	0.55	1.40	0.50	0.89	-
Orthophosphate	mg/L	-	<0.10	<0.10	<0.10	0.08	-	0.12	-	0.09	0.18	0.29	-	0.17	0.43	-
Turbidity	NTU	1140	1460	899	201	90.6	443	2230	190	400	110	400	100	170	300	5
Total Suspended Solids	mg/L	7390	4650	4490	954	3590	2580	9720	1320	5540	4450	4290	22100	1280	1240	-
BOD	mg/L	<5	<5	<5	-	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.002	<0.002	<0.0001	<0.0001	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	-
Aluminum	mg/L	0.078	0.112	0.053	0.070	0.071	0.094	0.048	0.056	0.238	0.052	0.469	0.057	0.056	0.062	0.1
Antimony	mg/L	<0.003	<0.003	<0.001	<0.001	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.006
Arsenic	mg/L	<0.003	<0.003	0.001	<0.001	0.0007	0.0016	0.0006	0.0011	0.0006	0.0005	0.0006	0.0005	0.0004	0.0007	0.010
Barium	mg/L	0.006	0.003	0.003	0.018	0.005	0.002	0.0052	0.005	0.00792	0.003	0.0114	0.00379	0.0036	0.00250	1.00
Beryllium	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000026	0.000038	0.000023	0.000023	0.000047	0.000032	0.000054	0.000029	0.000027	0.000030	-
Bismuth	mg/L	<0.002	<0.002	<0.002	<0.002	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	0.00002	< 0.00001	< 0.00001	< 0.00001	-
Boron	mg/L	0.020	0.051	0.019	<0.010	0.013	0.036	0.024	0.018	0.012	0.016	0.011	0.016	0.009	0.014	5
Cadmium	mg/L	<0.001	<0.001	<0.0001	<0.0001	0.000016	0.000007	0.000007	0.000009	0.00003	0.000011	0.000029	0.000015	0.000009	0.000008	0.005
Chromium	mg/L	<0.003	<0.003	<0.002	<0.002	0.00023	0.00024	0.00014	0.00021	0.00033	0.00019	0.00044	0.00019	0.00012	0.00020	0.05
Cobalt	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000175	0.000149	0.000135	0.00018	0.000241	0.000207	0.000329	0.000091	0.000280	0.000080	-
Copper	mg/L	<0.003	0.006	<0.001	0.003	0.0004	0.0025	0.0015	0.0007	0.0008	0.0028	0.001	0.0010	< 0.001	0.001	1
Molybdenum	mg/L	0.006	0.006	<0.002	<0.002	0.001	0.001	0.00048	0.001	0.0004	0.001	< 0.0004	< 0.0004	< 0.0004	< 0.0004	-
Nickel	mg/L	<0.003	<0.003	<0.003	<0.003	0.0002	0.0002	0.0003	0.0001	0.0002	0.0006	0.0003	0.0001	0.0001	0.0001	-
Phosphate	mg/L	<0.10	-	-	-	-	-	-	-	-	-	-	0.10	-	-	-
Lead	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.0001	< 0.00009	< 0.00009	< 0.00009	0.00015	< 0.00009	0.00066	< 0.00009	< 0.00009	< 0.00009	0.01
Selenium	mg/L	<0.004	<0.004	<0.001	<0.001	< 0.00004	< 0.00004	< 0.00004	< 0.00004	0.00013	< 0.00004	0.00008	< 0.00004	< 0.00004	< 0.00004	0.05
Silicon	mg/L	-	-	-	0.063	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.002	<0.002	<0.002	0.006	< 0.00006	< 0.00006	0.00008	0.00006	0.0001	0.00018	0.00006	< 0.00006	0.00011	< 0.00006	-
Strontium	mg/L	0.014	0.007	0.020	<0.0003	0.022	0.018	0.0175	0.024	0.0244	0.015	0.0225	0.017	0.0169	0.0131	-
Titanium	mg/L	<0.002	0.002	<0.002	<0.010	0.001	0.00165	0.00072	0.00061	0.00451	0.00053	0.0147	0.00040	0.0007	0.0005	-
Uranium	mg/L	<0.002	<0.002	0.0012	<0.002	0.000574	0.000958	0.000381	0.000669	0.000516	0.000478	0.000539	0.000335	0.000239	0.000207	0.02
Vanadium	mg/L	<0.002	<0.002	<0.002	<0.005	0.00012	0.00021	0.00023	0.00018	0.00022	0.00012	0.00050	0.00011	0.00013	0.00011	-
Zinc	mg/L	<0.005	0.019	<0.005	-	< 0.002	0.004	0.003	< 0.002	0.002	0.004	< 0.002	0.002	0.002	0.010	5
Field Measurements																
Temperature	oC	8.4	10.5	6.8	9.49	6.98	10.5	6.4	7.4	8.3	8.6	6.5	7.4	6.4	8.7	-
pH	pH Units	6.48	5.68	5.86	5.8	4.4	5.3	16.2	5.8	5.4	5.1	5.9	6.5	8.4	6.14	-
Coductivity	uS/cm	63.4	48.4	45.8	30.00	22.00	37.00	19.50	29.30	23.30	27.00	20.30	29.60	29.70	35.80	-
Oxidation Reduction Potential	mV	105.1	179.4	304.7	385.4	262.9	270.9	125	131.2	185.4	200.1	157.1	95.8	118.1	262.3	-
Dissolved Oxygen	mg/L	4.34	4.84	5.36	9.2	5.9	4.41	6.81	4.31	8.13	4.39	5.87	22.35	3.36	0.61	-

Notes:

ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act, dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.

BOLD Exceeds ODWQS

Units All Units in mg/L Unless Otherwise Noted.

- No data available

TABLE 7
Groundwater Quality Results - BH-4
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation																				ODWQS
		Sample Collection Date (07/05/2025)																				
		BH-4																				
		13-May-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25	
pH Lab	pH Units	7.12	INSUFFICIENT	INSUFFICIENT	INSUFFICIENT	DRY	7.2	7.56	INSUFFICIENT	INSUFFICIENT	7.03	7.87	6.82	7.9	7.83	7.85	7.8	7.69	INSUFFICIENT	7.80	INSUFFICIENT	6.5-8.5
Conductivity	µS/cm	970	VOLUME	VOLUME	VOLUME	-	603	730	VOLUME	VOLUME	499	572	468	584	540	631	527	542	VOLUME	579	VOLUME	-
Hardness	mg/L	420	-	-	-	-	228	350	-	-	247	259	222	297	243	295	261	266	-	272	-	80-100
Total Dissolved Solids	mg/L	672	-	-	-	-	370	484	-	-	342	391	285	423	363	391	331	371	-	403	-	500
Alkalinity	mg/L	130	-	-	-	-	227	184	-	-	203	161	191	211	187	213	173	204	-	184	-	30-500
Chloride	mg/L	21	-	-	-	-	5	5.67	-	-	2.7	4	3	4	3	7	4	2	-	3	-	250
Sodium	mg/L	37	-	-	-	-	11.5	11.6	-	-	8.57	6.48	8.01	7.36	7.55	9.24	8.16	7.19	-	5.55	-	200
Calcium	mg/L	140	-	-	-	-	79.7	123	-	-	86.8	91.7	79	107	85.3	105	89.8	95.1	-	97.9	-	-
Magnesium	mg/L	19	-	-	-	-	6.99	10.3	-	-	7.37	7.4	6.02	7.46	7.19	8.02	8.84	6.98	-	6.72	-	-
Potassium	mg/L	22	-	-	-	-	16.5	12.4	-	-	10.6	8.8	11	9.74	8.24	9.98	8.34	8.20	-	6.80	-	-
Sulphate	mg/L	290	-	-	-	-	63	137	-	-	69.7	79	49	77	54	72	91	51	-	91	-	500
Ammonia	mg/L	<0.05	-	-	-	-	0.06	0.09	-	-	0.04	0.13	0.06	< 0.04	< 0.04	< 0.04	0.05	< 0.04	-	< 0.1	-	-
Nitrate as N	mg/L	19	-	-	-	-	11.1	15.2	-	-	6.71	11.1	5.24	8.34	10	11	5.92	6.58	-	6.81	-	10
Nitrite as N	mg/L	<0.01	-	-	-	-	<0.05	<0.10	-	-	<0.05	0.04	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	-	< 0.03	-	1
Total Kjeldahl Nitrogen	mg/L	1.7	-	-	-	-	0.9	1.1	-	-	1.12	0.64	0.51	0.09	0.23	< 0.05	0.48	0.08	-	< 0.5	-	-
Phenolics	mg/L	<0.001	-	-	-	-	<0.001	<0.001	-	-	<0.001	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	-	< 0.002	-	-
Dissolved Organic Carbon	mg/L	17	-	-	-	-	11	8.7	-	-	10.8	11	3	13	6	12	7	10	-	10	-	5
Chemical Oxygen Demand	mg/L	41	-	-	-	-	40	22	-	-	<5	41	< 8	33	32	31	22	36	-	26	-	-
Iron	mg/L	<0.1	-	-	-	-	<0.1	<0.010	-	-	0.141	0.054	0.012	0.016	0.021	0.024	0.012	0.017	-	0.043	-	0.3
Manganese	mg/L	0.048	-	-	-	-	<0.005	<0.002	-	-	0.028	0.0039	0.0037	0.00148	0.00261	0.00544	0.0184	0.00100	-	0.00728	-	0.05
Phosphorus	mg/L	0.15	-	-	-	-	0.05	0.12	-	-	0.37	2.68	0.5	0.22	0.2	0.08	0.06	< 0.03	-	0.12	-	-
Orthophosphate	mg/L	<0.01	-	-	-	-	-	-	-	-	<0.10	< 0.03	-	< 0.03	-	< 0.03	< 0.03	< 0.03	-	< 0.03	-	-
Turbidity	NTU	52	-	-	-	-	55.3	30.5	-	-	149	49.6	15	72.7	38	45	16	17	-	50	-	5
Total Suspended Solids	mg/L	290	-	-	-	-	97	172	-	-	250	2110	1160	556	289	81	383	79	-	177	-	-
BOD	mg/L	<2	-	-	-	-	<2	<5	-	-	-	< 4	< 4	< 4	< 4	< 4	< 4	< 4	-	< 4	-	-
Anion Sum	-	10.6	-	-	-	-	6.77	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	10.6	-	-	-	-	5.48	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	0.1	-	-	-	-	-10.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.0001	-	-	-	-	<0.0001	<0.002	-	-	<0.0001	< 0.00005	<0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	-	< 0.00005	-	-
Aluminum	mg/L	0.039	-	-	-	-	0.028	0.018	-	-	0.085	0.037	0.021	0.017	0.019	0.021	0.014	0.017	-	0.036	-	0.1
Antimony	mg/L	<0.0005	-	-	-	-	<0.0005	<0.003	-	-	<0.001	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	-	< 0.0009	-	0.006
Arsenic	mg/L	<0.001	-	-	-	-	0.001	<0.003	-	-	0.001	0.0004	0.0005	0.0004	0.0005	0.0006	0.0003	0.0005	-	0.0004	-	0.010
Barium	mg/L	0.25	-	-	-	-	0.128	0.126	-	-	0.088	0.0789	0.0958	0.0908	0.092	0.111	0.0859	0.0741	-	0.0784	-	1.00
Beryllium	mg/L	<0.0005	-	-	-	-	<0.0005	<0.001	-	-	<0.0005	0.00001	0.00001	0.00007	0.000011	0.000015	0.000007	0.000045	-	< 0.000007	-	-
Bismuth	mg/L	<0.001	-	-	-	-	<0.001	<0.002	-	-	<0.002	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	0.00005	-	< 0.00001	-	-
Boron	mg/L	0.56	-	-	-	-	0.504	0.397	-	-	0.421	0.335	0.491	0.358	0.334	0.457	0.346	0.351	-	0.324	-	5
Cadmium	mg/L	<0.0001	-	-	-	-	<0.0001	<0.001	-	-	<0.0001	0.000017	0.000017	0.000008	0.000007	0.000025	0.000016	0.000025	-	0.000006	-	0.005
Chromium	mg/L	<0.005	-	-	-	-	<0.001	<0.003	-	-	<0.002	0.0006	0.00062	0.00072	0.0005	0.00096	0.00049	0.00077	-	0.00024	-	0.05
Cobalt	mg/L	0.00068	-	-	-	-	0.0007	<0.001	-	-	<0.0005	0.000297	0.000402	0.00028	0.000303	0.000371	0.000245	0.000289	-	0.000550	-	-
Copper	mg/L	0.0079	-	-	-	-	0.0077	0.005	-	-	0.01	0.0035	0.0052	0.0068	0.0037	0.0065	0.0064	0.005	-	0.004	-	1
Molybdenum	mg/L	<0.0005	-	-	-	-	<0.0005	<0.002	-	-	<0.002	0.00072	0.00046	0.00076	0.00058	0.00052	0.00066	0.0004	-	0.0008	-	-
Nickel	mg/L	0.0026	-	-	-	-	0.002	<0.003	-	-	<0.003	0.0006	0.0008	0.0008	0.0005	0.001	0.0011	0.0007	-	0.0005	-	-
Phosphate	mg/L	-	-	-	-	-	<0.0002	<0.20	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Lead	mg/L	<0.0005	-	-	-	-	0.0001	<0.001	-	-	0.0008	0.00026	<0.00009	0.00058	0.00032	< 0.00009	0.0003	< 0.00009	-	< 0.00009	-	0.01
Selenium	mg/L	<0.002	-	-	-	-	0.002	<0.004	-	-	<0.001	0.0001	0.00019	0.00014	0.0001	0.00027	0.00017	0.00023	-	0.00012	-	0.05
Sillicon	mg/L	2.5	-	-	-	-	2.38	-	-	-	0.272	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.001	-	-	-	-	<0.005	<0.002	-	-	0.003	0.0001	<0.00006	0.00021	0.00011	0.00017	0.00014	0.00008	-	0.00010	-	-
Strontium	mg/L	0.42	-	-	-	-	0.276	0.395	-	-	<0.0003	0.305	0.265	0.341	0.384	0.389	0.332	0.312	-	0.336	-	-
Titanium	mg/L	<0.005	-	-	-	-	<0.005	<0.002	-	-	<0.010	0.00307	0.00033	0.00034	0.00081	0.00045	0.00061	0.0002	-	0.0022	-	-
Uranium	mg/L	0.003	-	-	-	-	<0.0016	0.003	-	-	<0.002	0.00282	0.00139	0.0026	0.00237	0.0026	0.00283	0.00180	-	0.00273	-	0.02
Vanadium	mg/L	<0.0005	-	-	-	-	<0.0005	<0.002	-	-	<0.005	0.00034	0.00034	0.00048	0.00027	0.00025	0.00029	0.00030	-	0.00035	-	-
Zinc	mg/L	0.0062	-	-	-	-	0.006	<0.005	-	-	-	< 0.002	0.003	0.005	< 0.002	< 0.002	0.005	< 0.002	-	< 0.002	-	5
Field Measurements																						
Temperature	oC	-	-	-	-	-	-	-	-	-	13.16	11.52	11.6	6.7	10.1	7.9	12.7	7.8	-	7.6	-	-
pH	pH Units	7.27	5.65	6.49	-	-	6.62	-	-	-	6.52	7.23	5.88	16.21	6.65	6.21	6.55	7.48	-	7.82	-	-
Coductivity	uS/cm	711	795	6.57	-	-	0.63	-	-	-	413.0	381.0	375.0	384.5	386.0	434.5	429.3	351.5	-	457.0	-	-
Oxidation Reduction Potential	mV	-	-	-	-	-	-	-	-	-	309.3	146.8	239	126.4	97.2	96.8	104.1	94.4	-	82	-	-
Dissolved Oxygen	mg/L	-	-	-	-	-	-	-	-	-	12.03	9.02	6.13	9.17	5.1	11.9	1.57	7.01	-	7	-	-

Notes:
ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act, dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.
BOLD Exceeds ODWQS
Units All Units in mg/L Unless Otherwise Noted.
- No data available

TABLE 8
Groundwater Quality Results - BH4-II
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation														ODWQS
		Sample Collection Date (07/05/2025)														
		BH4-II														
		11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25	
pH Lab	pH Units	7.46	7.16	7.07	6.96	7.30	6.93	7.68	7.59	7.61	7.62	7.19	6.88	7.58	7.29	6.5-8.5
Conductivity	µS/cm	768	826	779	507	731	590	710	562	690	594	599	526	701	706	-
Hardness	mg/L	342	323	308	227	356	260	352	253	319	248	274	265	328	330	80-100
Total Dissolved Solids	mg/L	570	450	494	332	563	351	486	403	426	397	380	343	491	440	500
Alkalinity	mg/L	191	240	230	235	231	229	259	214	229	215	210	243	227	280	30-500
Chloride	mg/L	7.09	4.78	6.77	4.83	7	5	7	4	12	4	4	3	6	6	250
Sodium	mg/L	16.0	12.9	13.3	10.4	12.8	10.1	12.6	8.2	11.3	10.4	8.77	9.9	10.1	12.1	200
Calcium	mg/L	117	109	104	78.2	124	89.5	122	87.6	111	84	95.5	88.9	114.0	108	-
Magnesium	mg/L	12.0	12.3	11.8	7.8	11.5	8.8	11.2	8.2	10.3	9.4	8.58	10.4	10.6	14.7	-
Potassium	mg/L	16.3	15.5	14.0	12.5	12.8	12.4	13.8	10.8	12	11.5	8.72	10.4	9.69	11.0	-
Sulphate	mg/L	91.9	67.3	78.6	59.6	60.0	67.0	67	41.0	72	55.0	55	56.0	83	85	500
Ammonia	mg/L	0.54	0.11	<0.02	0.19	<0.04	0.14	<0.04	0.16	<0.04	0.08	0.04	0.20	<0.1	0.4	-
Nitrate as N	mg/L	28.7	16.7	17.3	6.7	21.1	5.3	15.8	10.2	14.8	8.8	8.67	6.64	14.3	4.17	10
Nitrite as N	mg/L	<0.10	<0.25	<0.10	<0.05	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	1
Total Kjeldahl Nitrogen	mg/L	<0.10	0.17	0.86	1.05	<0.05	0.61	<0.05	0.34	<0.05	<0.05	1.10	<0.5	<0.5	0.7	-
Phenolics	mg/L	<0.001	0.001	<0.001	<0.001	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-
Dissolved Organic Carbon	mg/L	10.7	8.6	9.9	13.2	11.0	15.0	13	8.0	13	7.0	10	7.0	12	10	5
Chemical Oxygen Demand	mg/L	16	21	22	12	32	36	30	34	27	24	33	18	29	27	-
Iron	mg/L	<0.010	<0.010	0.013	0.015	0.02	0.046	0.019	0.013	0.035	0.045	0.020	0.011	0.009	0.020	0.3
Manganese	mg/L	0.292	0.386	0.328	0.263	0.252	0.322	0.225	0.180	0.139	0.142	0.0624	0.233	0.1470	0.289	0.05
Phosphorus	mg/L	0.12	0.07	<0.02	<0.02	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	-
Orthophosphate	mg/L	-	<0.50	<0.20	<0.10	<0.03	-	<0.03	-	<0.03	<0.03	<0.03	-	<0.03	<0.03	-
Turbidity	NTU	79.7	74.6	28.0	2.1	4.7	14.8	0.93	2.8	8.2	1.4	3.7	1.5	0.9	8.8	5
Total Suspended Solids	mg/L	242	44	46	11	5	9	9	15	15	6	13	6	19	8	-
BOD	mg/L	<5	<5	<5	-	<4	<4	<4	<4	<4	<4	<4	<4	<4	<4	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.002	<0.002	<0.0001	<0.0001	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	-
Aluminum	mg/L	0.025	0.035	0.017	0.069	0.021	0.021	0.022	0.019	0.018	0.063	0.014	0.017	0.015	0.020	0.1
Antimony	mg/L	<0.003	<0.003	<0.001	<0.001	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	0.006
Arsenic	mg/L	<0.003	<0.003	0.001	0.002	0.0005	0.0007	0.0005	0.0006	0.0006	0.0004	0.0005	0.0003	0.0005	0.0005	0.010
Barium	mg/L	0.130	0.119	0.091	0.079	0.102	0.083	0.103	0.103	0.111	0.085	0.0732	0.080	0.0944	0.105	1.00
Beryllium	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000011	0.000017	0.000017	0.000018	0.000023	0.000014	0.000012	0.000014	0.000010	0.000018	-
Bismuth	mg/L	<0.002	<0.002	<0.002	<0.002	0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	-
Boron	mg/L	0.519	0.473	0.488	0.495	0.514	0.523	0.384	0.569	0.415	0.294	0.400	0.495	0.511	5	
Cadmium	mg/L	<0.001	<0.001	<0.0001	<0.0001	0.000039	0.000039	0.00003	0.000033	0.000042	0.000026	0.000028	0.000029	0.000016	0.000026	0.005
Chromium	mg/L	<0.003	<0.003	<0.002	<0.002	0.00073	0.00067	0.00084	0.00056	0.00104	0.00062	0.00078	0.00055	0.00095	0.00061	0.05
Cobalt	mg/L	0.002	0.002	0.002	0.002	0.001	0.002	0.0012	0.001	0.00105	0.001	0.000663	0.001	0.000750	0.00125	-
Copper	mg/L	0.009	0.010	0.008	0.008	0.008	0.009	0.0093	0.008	0.0095	0.010	0.008	0.008	0.007	0.008	1
Mercury	mg/L	-	-	-	-	<0.00001	<0.00001	0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	0.001
Molybdenum	mg/L	<0.002	<0.002	<0.002	<0.002	0.00096	0.00089	0.00102	0.00075	0.00074	0.00063	0.0008	0.0007	0.0009	0.0011	-
Nickel	mg/L	<0.003	0.004	0.010	<0.003	0.002	0.0023	0.0019	0.0017	0.0029	0.0018	0.0018	0.0016	0.0016	0.0019	-
Phosphate	mg/L	<0.20	-	-	-	-	-	-	-	-	-	-	<0.03	-	-	-
Lead	mg/L	<0.001	<0.001	<0.0005	<0.0005	<0.00009	<0.00009	<0.00009	<0.00009	0.00028	0.0001	<0.00009	<0.00009	<0.00009	<0.00009	0.01
Selenium	mg/L	<0.004	<0.004	<0.001	<0.0014	0.00014	0.0002	0.00017	0.00015	0.0002	0.00021	0.00021	0.0002	0.00016	0.00016	0.05
Silicon	mg/L	-	-	-	0.263	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.002	<0.002	<0.002	0.002	0.00014	0.00007	0.00014	0.00009	0.00019	0.00013	<0.00006	0.00007	0.00012	0.00007	-
Strontium	mg/L	0.384	0.392	<0.002	<0.0003	0.406	0.311	0.425	0.394	0.421	0.311	0.323	0.331	0.408	0.412	-
Titanium	mg/L	<0.002	0.002	<0.002	<0.010	0.001	0.000	0.00035	0.000	0.00042	0.00213	0.0003	0.0003	0.0002	0.0014	-
Uranium	mg/L	<0.002	0.005	0.0062	<0.002	0.0050	0.005	0.00469	0.004	0.00431	0.004	0.00373	0.00638	0.00654	0.00660	0.02
Vanadium	mg/L	<0.002	<0.002	<0.002	<0.005	0.0003	0.0004	0.00041	0.0003	0.00032	0.000	0.00027	0.00038	0.00031	0.00037	-
Zinc	mg/L	<0.005	<0.005	<0.005	-	<0.002	0.003	0.004	<0.002	<0.002	0.0030	<0.002	<0.002	<0.002	0.009	5
Benzene	mg/L	-	-	-	-	<0.0005	<0.0005	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	0.001
1,4-Dichlorobenzene	mg/L	-	-	-	-	<0.0005	<0.0005	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	0.005
Dichloromethane	mg/L	-	-	-	-	<0.0005	<0.0005	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	0.05
Toluene	mg/L	-	-	-	-	<0.0005	<0.0005	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	0.06
Vinyl Chloride	mg/L	-	-	-	-	<0.0002	<0.0002	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	0.001
Field Measurements																
Temperature	oC	10.1	10.5	9.9	12.7	10.47	13.1	8	10	8.5	16.6	8	11.1	8.6	11.3	-
pH	-	-	-	-	-	-	-	-	-	-	-	6.80	5.96	6.53	7.12	-
Conductivity	uS/cm	847.0	586.0	719.0	387.0	491.0	489.0	471.8	413.5	488.8	477.0	392.6	399.9	591.0	706.0	-
Oxidation Reduction Potential	mV	165.5	142.1	398.2	335.4	160.1	226.4	143	89.3	135	114.7	126.4	266.2	112.5	320.4	-
Dissolved Oxygen	mg/L	5.23	2.14	3.79	10.77	4.25	1.1	5.33	1.48	7.62	4.48	3.65	2.2	3.79	0.65	-

Notes:

ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act, dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.

BOLD	Exceeds ODWQS
Units	All Units in mg/L Unless Otherwise Noted.
-	No data available

TABLE 9
Groundwater Quality Results - BH5-II
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation Sample Collection Date (07/05/2025) BH5-II																				ODWQS	
		13-May-15	22-Oct-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25		26-Sep-25
pH Lab	pH Units	6.7	6.77	6.6	6.5	7.1	6.5	6.7	6.94	6.84	6.83	6.64	7.24	6.56	7.62	7.73	7.38	7.51	6.90	6.78	6.83	6.90	6.5-8.5
Conductivity	µS/cm	230	350	456	355	351	276	377	245	421	352	352	337	366	350	445	341	388	334	422	285	406	-
Hardness	mg/L	70	110	181	122	119	47	127	96.0	142	136	226	132	158	133	177	123	168	112	180	115	176	80-100
Total Dissolved Solids	mg/L	132	212	284	288	230	142	214	176	230	214	226	203	206	249	214	340	197	277	220	274	194	500
Alkalinity	mg/L	49	48	66	57	58	59	85	57	83	90	115	89	114	100	116	91	108	89	117	74	98	30-500
Chloride	mg/L	12	15	14	9	7	7	15	6.9	10.9	10.3	13.0	10.0	17.0	16	14.0	17	13.0	9	8.0	6	7	250
Sodium	mg/L	11	16	22.2	14.9	13.1	8.48	13.4	9.07	13.10	12.3	19.2	10.9	12.9	11.2	12.6	10.3	13.2	9.17	12.0	8.03	10.2	200
Calcium	mg/L	19	34	58.9	29.8	31.7	18.9	34.6	26.7	43.0	37.0	68.9	36.9	49.7	37.7	58.4	34.6	54.4	32.0	59.4	33.9	56.1	-
Magnesium	mg/L	5.7	6.1	8.32	11.6	9.64	<0.2	9.87	7.13	8.43	10.70	13.10	9.64	8.36	9.45	7.52	8.89	7.91	7.84	7.79	7.44	8.67	-
Potassium	mg/L	3.4	6.7	8.43	4.63	4.17	<0.001	4.57	3.94	5.10	4.77	8.10	4.27	5.60	4.59	5.18	4.42	5.62	3.70	5.46	3.65	5.36	-
Sulphate	mg/L	29	50	112	97	93	56	75	45.5	68.4	60.3	62.6	49.0	56.0	67	76.0	58	70.0	53	83.0	56	81	500
Ammonia	mg/L	0.17	0.12	0.22	0.23	0.14	0.16	0.33	0.31	0.17	0.22	0.27	0.25	0.16	0.31	0.11	0.32	0.12	0.37	0.10	0.30	0.2	-
Nitrate as N	mg/L	3.31	9.18	6.0	3.9	3	2	3.5	1.68	4.13	2.30	3.68	2.07	3.62	1.77	5.62	1.75	3.52	1.48	3.97	1.43	2.24	10
Nitrite as N	mg/L	<0.001	0.016	<0.05	<0.05	<0.05	<0.05	0.05	0.15	<0.05	<0.05	<0.05	0.09	<0.03	0.15	<0.03	0.29	0.03	0.06	0.03	0.06	0.04	1
Total Kjeldahl Nitrogen	mg/L	0.85	0.82	0.9	1	0.8	0.8	0.9	0.72	0.63	0.74	0.68	0.44	0.28	0.53	0.45	0.5	0.35	0.41	<0.5	<0.5	<0.5	-
Phenolics	mg/L	<0.001	<0.001	0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002	<0.002	0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-
Dissolved Organic Carbon	mg/L	3.1	3.8	7.4	5.5	7.6	5.8	4.1	2.8	5.4	3.9	5.5	4.0	2.8	14	5	6	4	5.0	4	6	4	5
Chemical Oxygen Demand	mg/L	24	12	64	66	34	53	33	<5	14	13	<5	16	8	15	9	13	11	16	13	26	16	-
Iron	mg/L	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.010	<0.010	<0.010	0.012	0.182	0.123	0.01	0.012	<0.007	0.008	0.012	0.008	0.008	0.007	0.3
Manganese	mg/L	0.067	0.075	0.193	0.124	0.123	0.074	0.158	0.124	0.067	0.171	0.144	0.174	0.139	0.098	0.178	0.021	0.211	0.055	0.192	0.035	0.170	0.05
Phosphorus	mg/L	7.5	2.9	1.72	2.46	0.62	1.23	0.62	1.05	0.29	1.14	3.32	0.55	0.18	0.76	0.39	0.39	0.18	0.40	0.19	18.80	0.37	-
Orthophosphate	mg/L	<0.01	-	-	-	-	-	-	<0.10	<0.10	<0.10	<0.10	<0.03	-	<0.03	-	<0.03	<0.03	0.03	-	<0.03	0.10	-
Turbidity	NTU	210	400	778	860	595	471	424	258	273	95.9	225	21.9	14.5	134	70	170	60	190	45	45	190	5
Total Suspended Solids	mg/L	4200	3800	2020	6690	1720	1830	870	1730	2380	2000	761	1400	612	730	398	1810	287	1060	6720	1040	558	-
BOD	mg/L	<2	<2	9	<2	2	7	<2	<5	<5	<5	-	<4	<4	<4	<4	<4	4	<4	<4	<4	<4	-
Anion Sum	-	2.17	3.06	4.46	3.68	3.5	2.69	3.92	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	1.99	3.08	4.81	3.21	3.05	3.08	3.24	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	NC	0.31	3.8	-6.9	-6.8	-	-9.6	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.002	<0.002	<0.0001	<0.0001	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	-
Aluminum	mg/L	0.031	0.025	0.019	0.015	0.014	0.026	0.012	0.017	0.015	0.010	0.034	0.117	0.078	0.021	0.016	0.023	0.018	0.029	0.016	0.023	0.017	0.1
Antimony	mg/L	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.003	<0.003	<0.001	<0.001	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	0.006
Arsenic	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.003	<0.003	<0.001	<0.001	0.0002	0.0003	<0.0002	0.0004	<0.0002	0.0003	<0.0002	0.0003	<0.0002	0.0004	0.010
Barium	mg/L	0.064	0.019	0.276	0.095	0.071	0.121	0.095	0.121	0.092	0.125	0.095	0.107	0.126	0.142	0.150	0.0965	0.127	0.0740	0.124	0.0811	0.122	1.00
Beryllium	mg/L	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.001	<0.001	<0.0005	<0.0005	0.000019	0.000015	0.000013	0.000007	0.000017	0.00001	0.000010	0.000007	0.000011	0.000007	-
Bismuth	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002	<0.002	<0.002	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	-
Boron	mg/L	0.13	0.26	0.391	0.21	0.257	0.176	0.310	0.289	0.215	0.326	0.279	0.295	0.331	0.263	0.299	0.331	0.145	0.298	0.193	0.286	0.291	5
Cadmium	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.001	<0.001	<0.0001	0.0003	0.000036	0.000019	0.000023	0.000008	0.000042	0.000007	0.000021	0.000005	0.000023	0.000014	0.005
Chromium	mg/L	<0.005	<0.005	<0.001	<0.001	<0.001	0.003	<0.001	<0.003	<0.003	<0.002	<0.002	0.00044	0.00047	0.00029	0.00046	0.00039	0.0005	0.00032	0.00058	0.00025	0.00038	0.05
Cobalt	mg/L	<0.0005	0.00074	0.0007	0.0005	0.0005	<0.0005	0.0007	<0.001	<0.001	<0.0005	<0.0005	0.00066	0.000395	0.000388	0.000278	0.000339	0.000263	0.000288	0.00022	0.000280	0.000217	-
Copper	mg/L	0.002	0.0033	0.0033	0.0021	0.0019	0.0012	0.003	<0.003	0.003	0.002	0.003	0.002	0.003	0.0032	0.004	0.0025	0.005	0.002	0.004	0.002	0.003	1
Molybdenum	mg/L	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	<0.002	<0.002	<0.002	<0.002	0.00022	0.00023	0.00024	0.0003	0.00031	0.00024	<0.0004	<0.0004	<0.0004	<0.0004	-
Nickel	mg/L	0.0016	<0.001	0.002	0.003	0.002	0.002	0.003	<0.003	<0.003	<0.003	<0.003	0.0021	0.0011	0.0022	0.0006	0.0016	0.0009	0.0015	0.0007	0.0011	0.0010	-
Phosphate	mg/L	-	-	<0.0002	<0.0002	<0.0002	<0.0002	<0.0002	<0.10	-	-	-	-	-	-	-	-	-	-	<0.03	-	-	-
Lead	mg/L	<0.0005	<0.0005	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.001	<0.001	<0.0005	<0.0005	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	0.01
Selenium	mg/L	<0.002	<0.002	<0.001	<0.001	<0.001	<0.001	<0.001	<0.004	<0.004	0.001	<0.001	0.00006	0.00008	0.00005	0.00008	0.00016	0.00009	0.00015	0.0001	0.00007	0.00008	0.05
Silicon	mg/L	4.4	3.5	3.36	3.73	4.29	3.47	3.1	-	-	-	0.22	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.001	<0.001	<0.005	<0.005	<0.005	<0.005	<0.005	<0.002	<0.002	<0.002	0.002	<0.00006	<0.00006	0.0001	0.00009	0.00012	0.00007	<0.00006	<0.00006	<0.00006	<0.00006	-

TABLE 10
Groundwater Quality Results - BH6-II
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation																				ODWQS		
		Sample Collection Date (07/05/2025)																						
		BH6-II																						
		13-May-15	22-Oct-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25		
pH Lab	pH Units	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	DRY	6.5-8.5
Conductivity	µS/cm	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Hardness	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	80-100
Total Dissolved Solids	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	500
Alkalinity	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	30-500
Chloride	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	250
Sodium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	200
Calcium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Magnesium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Potassium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Sulphate	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	500.0
Ammonia	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Nitrate as N	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	10
Nitrite as N	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1
Total Kjeldahl Nitrogen	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Phenolics	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Dissolved Organic Carbon	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	5
Chemical Oxygen Demand	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Iron	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.3
Manganese	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.05
Phosphorus	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Orthophosphate	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Turbidity	NTU	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	5
Total Suspended Solids	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
BOD	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Aluminum	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.1
Antimony	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.006
Arsenic	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.010
Barium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.00
Beryllium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Bismuth	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Boron	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	5
Cadmium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.005
Chromium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.05
Cobalt	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Copper	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1
Molybdenum	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Nickel	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Phosphate	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Lead	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.01
Selenium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.05
Silicon	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Strontium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Titanium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Uranium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.02
Vanadium	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Zinc	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	5
Field Measurements																								
Temperature	oC	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
pH	pH Units	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Conductivity	uS/cm	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Oxidation Reduction Potential	mV	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Dissolved Oxygen	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Notes:
 ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act", dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.
BOLD Exceeds ODWQS
 Units All Units in mg/L Unless Otherwise Noted.
 - No data available

TABLE 11
Groundwater Quality Results - BH6-III
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation														ODWQS	APV
		Sample Collection Date (07/05/2025)															
		BH6-III															
		11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25		
pH Lab	pH Units	7.04	6.99	6.85	6.70	7.16	7.09	7.41	7.77	7.47	7.39	7.13	6.82	6.82	6.93	6.5-8.5	-
Conductivity	µS/cm	309	465	381	352	324	379	358	456	276	411	301	420	402	406	-	-
Hardness	mg/L	123	158	140	142	134	159	158	169	106	172	132	167	169	185	80-100	-
Total Dissolved Solids	mg/L	184	232	216	206	189	246	257	306	163	< 30	186	257	277	246	500	-
Alkalinity	mg/L	72	101	97	130	82	115	86	127	60	116	73	119	77	159	30-500	-
Chloride	mg/L	6.03	12.9	7.79	11.9	7	16	8	15	6	17	3	9	4	6	250	180
Sodium	mg/L	11.0	13.2	10.9	17.2	9.0	14.2	9.3	12.3	7.97	12.7	7.49	11.6	7.30	9.52	200	180
Calcium	mg/L	35.9	47.5	41.1	42.6	39.5	49.0	48.2	50.5	31.7	51.9	40.2	50.7	52.8	56.5	-	-
Magnesium	mg/L	7.98	9.60	8.99	8.73	8.47	8.89	9.06	10.40	6.38	10.20	7.74	9.94	9.11	10.6	-	-
Potassium	mg/L	5.49	7.47	6.09	7.86	6.06	8.53	6.26	7.11	4.28	6.96	4.19	6.74	4.62	5.85	-	-
Sulphate	mg/L	65.7	66.8	68.1	57.5	56	57	84	74	67	69	58	80	120	86	500	-
Ammonia	mg/L	0.30	0.79	<0.02	0.65	0.23	0.47	0.1	0.75	< 0.04	0.43	< 0.04	0.40	< 0.1	< 0.1	-	-
Nitrate as N	mg/L	1.60	3.36	2.23	2.48	2.41	3.31	2.23	4.26	1.45	2.23	1.47	2.77	1.47	1.56	10	-
Nitrite as N	mg/L	<0.05	<0.05	<0.05	<0.05	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	1	-
Total Kjeldahl Nitrogen	mg/L	0.52	1.30	0.70	1.13	0.30	0.30	0.28	0.97	0.09	0.69	0.10	0.60	< 0.5	< 0.5	-	-
Phenolics	mg/L	<0.001	<0.001	<0.001	<0.001	< 0.002	< 0.002	0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	-	0.961
Dissolved Organic Carbon	mg/L	2.9	5.3	4.6	4.8	4	5	4	5	3	4	4	5	4	6	5	-
Chemical Oxygen Demand	mg/L	<5	12	16	<5	11	13	< 8	9	< 8	18	< 8	18	12	9	-	-
Iron	mg/L	<0.010	<0.010	0.019	<0.010	0.01	0.03	0.024	0.039	< 0.007	0.009	0.013	0.007	0.012	< 0.007	0.3	-
Manganese	mg/L	0.404	0.615	0.450	0.898	0.469	0.541	0.34	0.913	0.0519	0.343	0.0379	0.605	0.0271	0.0318	0.05	-
Phosphorus	mg/L	0.25	0.12	0.16	0.70	0.05	0.03	0.04	0.07	0.04	0.07	< 0.03	0.04	< 0.03	0.03	-	-
Orthophosphate	mg/L	-	<0.10	<0.10	<0.10	< 0.03	-	< 0.03	-	< 0.03	< 0.03	< 0.03	-	< 0.03	< 0.03	-	-
Turbidity	NTU	36.7	24.5	60.4	213	3.8	3.4	77.5	40	12	11	4.1	4.8	2.2	8.4	5	-
Total Suspended Solids	mg/L	42	66	107	190	158	228	134	420	58	359	81	198	161	215	-	-
BOD	mg/L	<5	<5	<5	-	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	-	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.002	<0.002	<0.0001	<0.0001	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	-	0.00012
Aluminum	mg/L	0.013	0.015	0.011	0.030	0.009	0.017	0.011	0.020	0.007	0.007	0.011	0.004	0.011	0.005	0.1	-
Antimony	mg/L	<0.003	<0.003	<0.001	<0.001	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.006	1.6
Arsenic	mg/L	<0.003	<0.003	<0.001	<0.001	0.0002	0.0002	< 0.0002	0.0004	< 0.0002	0.0003	< 0.0002	< 0.0002	< 0.0002	0.0003	0.01	0.15
Barium	mg/L	0.096	0.124	0.093	0.116	0.100	0.123	0.128	0.142	0.0749	0.120	0.0765	0.115	0.1170	0.116	1.00	2.3
Beryllium	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000013	0.000011	0.000009	0.000008	0.000024	0.000016	< 0.000007	0.000011	0.000013	0.000013	-	0.0053
Bismuth	mg/L	<0.002	<0.002	<0.002	<0.002	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	-	-
Boron	mg/L	0.207	0.341	0.265	0.287	0.256	0.287	0.265	0.293	0.176	0.301	0.148	0.287	0.243	0.291	5	3.55
Cadmium	mg/L	<0.001	<0.001	<0.0001	<0.0001	0.000021	0.000048	0.00003	0.000045	0.000032	0.000049	0.000012	0.000057	0.000011	0.000006	0.005	0.00021
Chromium	mg/L	<0.003	<0.003	<0.002	<0.002	0.00041	0.00025	0.00027	0.00028	0.00039	0.00037	0.00036	0.00033	0.00030	0.00021	0.05	0.064
Cobalt	mg/L	<0.001	<0.001	0.0007	0.001	0.00223	0.000876	0.00103	0.000582	0.000684	0.000277	0.000287	0.000328	0.000300	0.000148	-	0.0052
Copper	mg/L	0.006	0.007	0.005	0.007	0.005	0.007	0.0058	0.0069	0.004	0.0060	0.003	0.0060	0.003	0.003	1	0.0069
Molybdenum	mg/L	<0.002	<0.002	<0.002	<0.002	0.00039	0.00042	0.00033	0.00058	0.00024	0.00037	< 0.0004	0.0004	< 0.0004	< 0.0004	-	0.73
Nickel	mg/L	<0.003	0.005	0.004	0.005	0.004	0.004	0.0037	0.004	0.0025	0.003	0.0015	0.004	0.0013	0.0009	-	0.039
Phosphate	mg/L	< 0.10	-	-	-	-	-	-	-	-	-	-	< 0.03	-	-	-	-
Lead	mg/L	<0.001	<0.001	<0.0005	<0.0005	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	0.01	0.002
Selenium	mg/L	<0.004	<0.004	0.002	<0.001	< 0.00004	0.00009	0.00005	0.0001	0.00017	0.00013	0.00010	0.00012	0.00007	0.00008	0.05	0.005
Silicon	mg/L	-	-	-	0.325	-	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.002	<0.002	<0.002	0.002	0.00011	< 0.00006	0.00009	0.00008	0.00015	0.0001	< 0.00006	< 0.00006	0.00007	< 0.00006	-	-
Strontium	mg/L	0.225	0.292	0.280	<0.0003	0.342	0.436	0.382	0.440	0.218	0.312	0.237	0.321	0.320	0.327	-	-
Titanium	mg/L	<0.002	<0.002	<0.002	<0.010	0.00007	0.00116	0.00019	0.00239	0.00029	0.00015	0.0008	0.0001	0.0010	0.0002	-	-
Uranium	mg/L	<0.002	<0.002	<0.0005	<0.002	0.000278	0.000395	0.000256	0.000445	0.000156	0.000548	0.000244	0.000427	0.000230	0.000337	0.02	0.033
Vanadium	mg/L	<0.002	<0.002	<0.002	<0.005	0.00011	0.00018	0.00023	0.00015	0.00012	0.0001	0.00012	0.00008	0.00012	0.00010	-	0.02
Zinc	mg/L	0.005	0.005	<0.005	-	0.013	0.006	0.008	0.004	0.009	0.003	0.003	0.003	0.004	0.011	5	0.089
Field Measurements																	
Temperature	oC	8.3	9.8	7.2	10.24	6.76	9.4	6.7	8.2	7.2	9.3	7	9.1	7	9.3	-	-
pH	pH Units	6.4	5.8	6.1	6.2	12.7	5.6	16.2	6.4	5.7	6.1	6.7	6.3	6.7	10.9	-	-
Conductivity	uS/cm	338.8	321.1	371.1	27.1	198.0	285.0	239.0	311.6	191.4	295.7	201.8	301.0	201.8	413.1	-	-
Oxidation Reduction Potential	mV	209.4	427.5	250.2	279.6	145.7	232.3	90.3	92.1	134	106.8	120.9	142.9	120.9	315.7	-	-
Dissolved Oxygen	mg/L	2.48	1.7	4.06	12.15	3.28	1.51	3.01	3.72	4.43	0.61	3.29	5.61	3.29	0.97	-	-

Notes:

ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act", dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.

APV	Aquatic Protection Values
BOLD	Exceeds ODWQS
<u>UNDERLINED</u>	Exceeds APV
Units	All Units in mg/L Unless Otherwise Noted.
-	No data available

TABLE 12
Groundwater Quality Results - BH7-II
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation																				ODWQS	APV		
		Sample Collection Date (07/05/2025)																							
		BH7-II																							
		13-May-15	22-Oct-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25			
pH Lab	pH Units	6.05	6.44	DRY	5.9	6.4	6.1	6.1	6.34	5.92	6.43	5.95	6.93	5.91	6.69	DRY	6.67	6.69	6.83	6.42	6.55	6.37	6.5-8.5	-	
Conductivity	µS/cm	26	31	-	78	51	22	14	34	32	50	18	50	14	31	-	46	24	57	26	40	46	-	-	
Hardness	mg/L	7.5	7.6	-	22	12	1.0	5.0	9.2	7.2	10.7	6.0	15.2	5.7	7.5	-	12.4	7	0.49	4.3	7.60	10.5	80-100	-	
Total Dissolved Solids	mg/L	336	192	-	90	56	22	14	28	36	36	<20	49	31	89	-	40	< 30	54	< 30	34	37	500	-	
Alkalinity	mg/L	4.8	4.9	-	10	11	8.0	6.0	7.0	<5	15	7	15	3	8	-	12	4	10	6	10	11	30-500	-	
Chloride	mg/L	2	<1	-	1	1	<1	<1	0.49	0.22	0.58	0.58	1.00	1.00	3	-	6	< 1	1	2	6	2	250	180	
Sodium	mg/L	1.5	1.3	-	2.89	1.7	3.07	0.674	2.35	1.42	3.13	0.97	2.16	1.09	3.19	-	3.41	1.51	9.53	2.34	4.18	4.02	200	180	
Calcium	mg/L	2	2.1	-	1.48	2.79	0.466	1.2	2.07	1.58	2.30	1.35	3.35	1.25	1.63	-	2.76	1.57	0.11	0.94	1.70	2.23	-	-	
Magnesium	mg/L	0.62	0.58	-	0.543	1.34	<0.2	0.468	0.97	0.80	1.20	0.63	1.65	0.63	0.829	-	1.34	0.745	0.052	0.475	0.801	1.20	-	-	
Potassium	mg/L	1.4	1	-	1.03	1.48	0.874	0.471	1.42	0.58	1.48	0.55	1.33	0.92	1.2	-	1.38	0.819	0.408	0.803	1.040	1.73	-	-	
Sulphate	mg/L	7	5.8	-	8	9	1	2	5.68	1.98	7.70	1.98	10.00	8.00	19	-	38	8	30	20	48	14	500	-	
Ammonia	mg/L	<0.05	<0.05	-	0.03	0.06	0.04	0.02	0.11	0.13	<0.02	0.17	< 0.04	< 0.04	< 0.04	-	< 0.04	0.04	< 0.04	< 0.1	< 0.1	< 0.1	-	-	
Nitrate as N	mg/L	<0.1	<0.1	-	<0.1	<0.1	0.3	0.4	0.06	1.64	0.08	0.49	0.18	0.22	0.19	-	0.11	< 0.06	0.08	< 0.06	0.07	< 0.06	10	-	
Nitrite as N	mg/L	<0.01	<0.01	-	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	< 0.03	< 0.03	< 0.03	-	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	1	-	
Total Kjeldahl Nitrogen	mg/L	0.32	<0.1	-	0.3	0.3	0.6	0.4	0.16	0.56	0.17	0.19	0.06	0.11	0.08	-	0.05	0.26	0.12	< 0.5	< 0.5	< 0.5	-	-	
Phenolics	mg/L	<0.001	<0.001	-	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.009	< 0.002	< 0.002	< 0.002	-	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	-	0.961	
Dissolved Organic Carbon	mg/L	2.5	1.5	-	3.7	2.7	5.4	1.6	3.1	4.2	5.7	3.7	3.0	4.0	2	-	2	2	4	12	2	2	5	-	
Chemical Oxygen Demand	mg/L	4.5	<4	-	51	35	46	45	<5	<5	<5	<5	< 8	< 8	< 8	-	< 8	10	11	8	12	< 8	-	-	
Iron	mg/L	<0.1	<0.1	-	<0.1	<0.1	0.125	<0.1	<0.010	0.054	0.036	0.052	0.378	0.311	0.074	-	0.023	0.037	0.056	0.038	0.129	0.172	0.3	-	
Manganese	mg/L	0.0079	0.0036	-	0.012	0.006	<0.005	0.009	0.010	0.022	0.010	0.005	0.013	0.007	0.0119	-	0.00521	0.0049	0.00165	0.00353	0.00606	0.0185	0.05	-	
Phosphorus	mg/L	0.46	0.31	-	0.4	0.47	0.83	0.34	0.78	0.62	1.88	0.56	0.26	0.31	0.79	-	0.33	1.31	0.67	0.57	0.69	0.34	-	-	
Orthophosphate	mg/L	<0.01	-	-	-	-	-	-	-	<0.10	<0.10	<0.10	0.03	-	0.05	-	0.04	0.23	0.58	-	0.25	0.04	-	-	
Turbidity	NTU	330	380	-	1710	1580	2420	1720	2300	2470	3850	2640	74.2	105	510	-	1800	900	600	2000	180	850	5	-	
Total Suspended Solids	mg/L	1400	910	-	2530	1920	3550	1820	4160	2290	4180	3510	1330	921	1750	-	1510	3000	4260	2710	400	1040	-	-	
BOD	mg/L	<2	<2	-	<2	<2	<2	<2	<5	<5	<5	-	< 4	< 4	< 4	-	< 4	< 4	< 4	< 4	< 4	< 4	< 4	-	-
Anion Sum	-	0.292	0.238	-	0.4	0.44	0.23	0.22	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Cation Sum	-	0.265	0.239	-	0.27	0.36	0.19	0.14	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Ion Balance	%	-	NC	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Silver	mg/L	<0.0001	<0.0001	-	<0.0001	<0.0001	<0.0001	<0.0001	<0.002	<0.002	<0.0001	<0.0001	< 0.00005	< 0.00005	< 0.00005	-	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	0.00012	
Aluminum	mg/L	0.12	0.029	-	0.203	0.024	0.245	0.061	0.046	0.151	0.036	0.042	0.260	0.334	0.077	-	0.041	0.039	0.117	0.044	0.114	0.131	0.1	-	
Antimony	mg/L	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.003	<0.003	<0.001	<0.001	< 0.0009	< 0.0009	< 0.0009	-	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.006	1.6	
Arsenic	mg/L	<0.001	<0.001	-	<0.001	<0.001	<0.001	<0.001	<0.003	<0.003	<0.001	<0.001	< 0.0002	0.0002	< 0.0002	-	< 0.0002	< 0.0002	0.0004	< 0.0002	< 0.0002	< 0.0002	0.01	0.15	
Barium	mg/L	0.017	0.0086	-	0.014	0.018	0.004	0.007	0.014	0.014	0.012	0.005	0.024	0.012	0.0195	-	0.0143	0.00648	0.0013	0.00481	0.0100	0.0142	1.00	2.3	
Beryllium	mg/L	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.001	<0.001	<0.0005	<0.0005	0.00009	0.000084	0.000024	-	0.000032	0.00002	0.000029	0.000018	0.000049	0.000068	-	0.0053	
Bismuth	mg/L	<0.001	<0.001	-	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002	<0.002	<0.002	0.00002	< 0.00001	< 0.00001	-	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	-	-	
Boron	mg/L	0.01	0.011	-	0.014	0.023	0.02	<0.01	0.010	0.029	<0.010	<0.010	0.009	0.012	0.008	-	0.004	0.012	0.007	0.009	0.010	0.013	5	3.55	
Cadmium	mg/L	<0.0001	<0.0001	-	<0.0001	<0.0001	<0.0001	<0.0001	<0.001	<0.001	<0.001	<0.001	0.000013	0.000006	0.000024	-	0.000026	0.000009	0.000003	0.000005	0.000014	0.000018	0.005	0.00021	
Chromium	mg/L	<0.005	<0.005	-	<0.001	<0.001	<0.001	<0.001	<0.003	<0.003	<0.002	<0.002	0.00042	0.00063	0.00029	-	0.00044	0.00057	0.00053	0.00044	0.00026	0.00033	0.05	0.064	
Cobalt	mg/L	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	0.0006	<0.001	<0.001	<0.0005	<0.0005	0.00055	0.00045	0.000342	-	0.000302	0.000209	0.000083	0.000149	0.000360	0.000579	-	0.0052	
Copper	mg/L	0.002	0.001	-	0.0018	0.001	0.0021	0.0021	<0.003	<0.003	<0.001	<0.001	0.0014	0.0026	0.0047	-	0.0015	0.0028	0.002	0.002	0.001	0.002	1	0.0069	
Molybdenum	mg/L	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.002	<0.002	<0.002	<0.002	0.00008	0.00007	0.0001	-	0.00012	0.0001	< 0.0004	< 0.0004	< 0.0004	< 0.0004	-	0.73	
Nickel	mg/L	<0.001	<0.001	-	0.001	<0.001	<0.001	<0.001	<0.003	<0.003	<0.003	<0.003	0.0009	0.0006	0.0011	-	0.0007	0.0006	0.0002	0.0003	0.0005	0.0007	-	0.039	
Phosphate	mg/L	-	-	-	<0.2	<0.2	<0.2	<0.0002	< 0.10	-	-	-	-	-	-	-	-	-	-	0.24	-	-	-	-	
Lead	mg/L	<0.0005	<0.0005	-	<0.0001	<0.0001	0.0002	0.0001	<0.001	<0.001	<0.0005	<0.0005	0.00075	0.00024	0.00012	-	< 0.00009	0.00016	0.00027	< 0.00009	0.00024	0.00034	0.01	0.002	
Selenium	mg/L	<0.002	<0.002	-	<0.001	<0.001	<0.001	<0.001	<0.004	<0.004	<0.001	<0.001	0.0001	0.00005	0.00005	-	0.00018	0.00006	0.00009	< 0.00004	0.00007	0.00008	0.05	0.005	
Silicon	mg/L	4.3	4.6	-	5.17	6.09	2.3	2.41	-	-	-	0.013	-	-	-	-	-	-	-	-	-	-	-	-	
Tin	mg/L	<0.001	<0.001	-	<0.005	<0.005	<0.005	<0.005	<0.002	<0.002	<0.002	0													

TABLE 13
Groundwater Quality Results - BH8-1
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation														ODWQS	APV
		Sample Collection Date (07/05/2025)															
		BH8-1															
		11-Jun-19	23-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25		
pH Lab	pH Units	7.16	7.13	7.01	6.73	7.26	6.76	7.63	7.65	7.27	7.57	7.09	6.82	7.16	7.01	6.5-8.5	-
Conductivity	µS/cm	376	459	427	352	366	395	450	379	414	391	443	351	423	374	-	-
Hardness	mg/L	135	131	130	126	118	111	162	105	141	127	151	112	132	122	80-100	-
Total Dissolved Solids	mg/L	200	224	194	206	211	237	294	243	240	214	260	200	254	194	500	-
Alkalinity	mg/L	98	103	131	140	119	147	158	114	151	121	150	120	145	117	30-500	-
Chloride	mg/L	16.8	30.6	20.3	27.2	21.0	34.0	28	35.0	29	33.0	21	25.0	18	24	250	180
Sodium	mg/L	14.3	19.7	16.5	19.6	15.5	18.5	19.4	18.9	16.8	22.8	19.6	19.6	14.4	18.3	200	180
Calcium	mg/L	42.3	41.3	40.7	40.0	37.4	35.6	51.7	33.1	44.7	39.2	47.5	35.0	42.0	37.7	-	-
Magnesium	mg/L	7.06	6.87	6.91	6.30	6.03	5.38	7.96	5.50	7.22	7.12	7.92	6.03	6.53	6.82	-	-
Potassium	mg/L	10.0	9.4	10.40	10.40	10.00	9.16	11.2	7.80	9.9	8.94	9.45	8.11	8.68	8.72	-	-
Sulphate	mg/L	55.2	26.1	35.7	18.6	20.0	19.0	39	16.0	39	21.0	36	18.0	35	30	500	-
Ammonia	mg/L	0.26	1.71	2.70	1.29	1.97	2.13	2.35	1.33	2.53	1.46	2.19	1.40	2.20	1.4	-	-
Nitrate as N	mg/L	1.98	4.63	2.43	3.58	1.84	1.91	1.19	3.07	1.01	2.52	1.07	2.72	1.16	2.46	10	-
Nitrite as N	mg/L	0.25	0.12	0.06	<0.05	0.24	< 0.03	< 0.03	0.05	0.55	0.10	< 0.03	0.12	0.38	0.20	1	-
Total Kjeldahl Nitrogen	mg/L	6.10	4.10	4.96	2.27	2.71	2.52	2.95	1.68	3.08	1.61	2.27	1.60	2.10	1.6	-	-
Phenolics	mg/L	0.003	0.002	<0.001	<0.001	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	-	0.961
Dissolved Organic Carbon	mg/L	4.9	6	6.4	5.8	5.0	6	7	6	7	5	5	5	5	6	5	-
Chemical Oxygen Demand	mg/L	154	130	221	19	41	29	18	24	36	21	32	26	26	17	-	-
Iron	mg/L	<0.010	<0.010	0.039	0.014	0.214	0.031	0.012	0.017	0.1	0.017	0.042	0.073	0.013	0.008	0.3	-
Manganese	mg/L	1.39	0.94	1.56	1.22	1.26	0.96	2.13	1.45	2.05	1.53	2.85	1.65	1.53	1.57	0.05	-
Phosphorus	mg/L	2.98	3.36	1.22	0.80	0.71	0.70	0.55	0.56	0.88	0.26	0.46	0.38	0.41	0.91	-	-
Orthophosphate	mg/L	-	<0.10	<0.10	<0.10	0.2	-	0.03	-	< 0.03	0.03	< 0.03	-	< 0.03	0.04	-	-
Turbidity	NTU	7380	1450	629	473	29.8	20.9	153	120	230	70	50	55	8	37	5	-
Total Suspended Solids	mg/L	6680	3300	2180	1550	931	873	1180	662	2980	1110	380	1280	158	236	-	-
BOD	mg/L	9	<5	10	-	< 4	< 4	< 4	7	< 4	9	< 4	< 4	9	4	-	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.002	<0.002	<0.0001	<0.0001	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	-	0.00012
Aluminum	mg/L	0.033	0.035	0.031	0.067	0.124	0.024	0.026	0.020	0.043	0.022	0.040	0.050	0.021	0.019	0.1	-
Antimony	mg/L	<0.003	<0.003	<0.001	<0.001	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.006	1.6
Arsenic	mg/L	<0.003	<0.003	<0.001	<0.001	0.0004	0.0003	0.0003	0.0004	0.0003	0.0003	0.0004	0.0003	0.0003	0.0003	0.001	0.15
Barium	mg/L	0.183	0.147	0.162	0.146	0.160	0.121	0.206	0.128	0.161	0.130	0.142	0.106	0.144	0.120	1.00	2.3
Beryllium	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000023	0.000011	0.000011	0.000008	0.000019	0.00001	0.000015	0.000019	0.000011	0.000011	-	0.0053
Bismuth	mg/L	<0.002	<0.002	<0.002	<0.002	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	-	-
Boron	mg/L	0.230	0.343	0.286	0.271	0.281	0.297	0.443	0.224	0.264	0.287	0.244	0.256	0.218	0.266	5	3.55
Cadmium	mg/L	<0.001	<0.001	<0.0001	<0.0001	0.000061	0.000044	0.000065	0.000041	0.000073	0.000052	0.000089	0.000046	0.000050	0.000048	0.005	0.00021
Chromium	mg/L	<0.003	<0.003	<0.002	<0.002	0.00073	0.00041	0.00049	0.00032	0.00053	0.00041	0.00046	0.00048	0.00046	0.00026	0.05	0.064
Cobalt	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.00065	0.000532	0.000594	0.000616	0.00119	0.000645	0.000704	0.000672	0.000320	0.000470	-	0.0052
Copper	mg/L	0.004	0.004	0.003	0.004	0.004	0.003	0.0071	0.005	0.0039	0.004	0.004	0.004	0.003	0.004	1	0.0069
Molybdenum	mg/L	<0.002	<0.002	<0.002	<0.002	0.00017	0.00014	0.00027	0.00017	0.00021	0.00014	< 0.0004	< 0.0004	< 0.0004	< 0.0004	-	0.73
Nickel	mg/L	<0.003	<0.003	<0.003	<0.003	0.0007	0.0006	0.0011	0.0007	0.0009	0.001	0.0010	0.0009	0.0006	0.0007	-	0.039
Phosphate	mg/L	< 0.10	-	-	-	-	-	-	-	-	-	-	0.04	-	-	-	-
Lead	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.00022	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	0.01	0.002
Selenium	mg/L	<0.004	<0.004	0.002	<0.001	0.00006	0.00009	0.00009	0.00012	0.0002	0.00016	0.00022	0.0001	0.00011	0.00010	0.05	0.005
Silicon	mg/L	-	-	-	0.205	-	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.002	<0.002	<0.002	0.006	< 0.00006	0.00007	0.00021	0.00006	0.00014	0.00006	< 0.00006	< 0.00006	< 0.00006	< 0.00006	-	-
Strontium	mg/L	0.233	0.235	0.234	<0.0003	0.228	0.204	0.308	0.240	0.296	0.242	0.291	0.217	0.265	0.241	-	-
Titanium	mg/L	<0.002	<0.002	<0.002	<0.010	0.00641	0.00077	0.00036	0.00051	0.00184	0.00051	0.0011	0.0026	0.0005	0.0003	-	-
Uranium	mg/L	<0.002	<0.002	<0.0005	<0.002	0.000433	0.000227	0.000346	0.000271	0.000491	0.000342	0.000576	0.000407	0.000384	0.000262	0.02	0.033
Vanadium	mg/L	<0.002	<0.002	<0.002	<0.005	0.00048	0.00016	0.0004	0.00015	0.0003	0.00017	0.00024	0.00028	0.00016	0.00015	-	0.02
Zinc	mg/L	<0.005	<0.005	<0.005	-	0.002	0.003	0.008	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	0.009	5	0.089
Field Measurements																	
Temperature	oC	7.7	9.5	6.7	10.24	7.28	10.8	6.2	9	11.4	11.2	6.7	8.8	7	10.4	-	-
pH	pH Units	6.5	6.0	6.1	6.3	12.3	6.0	16.2	6.4	5.7	6.2	6.4	6.3	8.0	10.5	-	-
Conductivity	uS/cm	423.2	321.3	414.5	268	227	296	288	248	303	293	266	253	325	383	-	-
Oxidation Reduction Potential	mV	204.8	440.6	238.2	230.4	114.7	239.3	21.3	68.5	119.9	106.5	112.8	143.4	146.7	279.7	-	-
Dissolved Oxygen	mg/L	0.8	2.01	1.31	10.8	2.6	1.34	2.47	1.34	5.8	0.59	1.71	7.87	0.66	0.67	-	-

Notes:

ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act", dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.

APV Aquatic Protection Values

BOLD Exceeds ODWQS

UNDERLINED Exceeds APV

Units All Units in mg/L Unless Otherwise Noted.

- No data available

TABLE 14
Groundwater Quality Results - BH9-I
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation														ODWQS	APV
		Sample Collection Date (07/05/2025)															
		BH9-I															
		11-Jun-19	23-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25		
pH Lab	pH Units	7.40	7.17	6.99	6.85	7.25	6.75	7.74	7.75	7.15	7.61	7.06	6.72	6.86	7.21	6.5-8.5	-
Conductivity	µS/cm	479	574	608	441	534	485	551	503	548	521	516	485	598	544	-	-
Hardness	mg/L	197	143	155	140	176	153	178	136	180	161	168	155	173	198	80-100	-
Total Dissolved Solids	mg/L	260	240	300	240	294	520	351	291	309	277	329	263	394	274	500	-
Alkalinity	mg/L	152	168	192	201	174	189	157	182	148	197	184	196	106	207	30-500	-
Chloride	mg/L	15.5	38.6	26.2	33.5	23.0	42.0	28	37.0	18	37.0	23	30.0	9	28	250	180
Sodium	mg/L	11.4	22.5	21.6	22.8	22.0	25.0	23.4	21.3	17.2	25.8	24.7	20.7	14.9	18.8	200	180
Calcium	mg/L	63.9	45.6	48.1	44.6	54.3	48.6	56	42.7	55.3	50.7	52.0	49.4	53.5	64.6	-	-
Magnesium	mg/L	9.19	7.16	8.40	7.02	9.67	7.68	9.38	7.25	10.3	8.38	9.19	7.80	9.65	8.86	-	-
Potassium	mg/L	8.04	12.30	10.9	11.1	11.5	11.5	12.3	9.4	10.1	11.8	11.0	10.5	9.8	9.95	-	-
Sulphate	mg/L	65.9	20.0	58.4	16.9	57.0	19.0	79	15.0	97	21.0	54	22.0	180	42	500	-
Ammonia	mg/L	3.58	6.60	6.18	6.83	6.50	7.07	7.14	6.38	5.98	6.68	6.57	6.70	6.70	3.7	-	-
Nitrate as N	mg/L	0.92	<0.05	<0.05	<0.05	0.08	0.06	0.22	9.25	<0.06	<0.06	<0.06	<0.06	<0.06	<0.06	10	-
Nitrite as N	mg/L	<0.05	<0.05	0.06	<0.05	0.04	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	1	-
Total Kjeldahl Nitrogen	mg/L	4.00	7.46	7.96	7.40	7.15	6.66	6.84	7.62	6.64	6.94	6.41	6.50	6.40	3.9	-	-
Phenolics	mg/L	0.002	0.001	0.002	<0.001	<0.002	<0.002	<0.002	0.004	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-	0.961
Dissolved Organic Carbon	mg/L	6.8	9.2	9.8	10.4	9	12	9	9	10	9	8	8	7	8	5	-
Chemical Oxygen Demand	mg/L	35	33	45	16	43	27	34	45	39	40	45	28	30	28	-	-
Iron	mg/L	0.133	3.76	8.08	8.71	14.3	10.1	17	15.7	22.1	14.9	21.0	15.0	19.4	9.52	0.3	-
Manganese	mg/L	2.06	4.48	5.28	4.79	6.20	5.43	6.67	5.26	7.14	5.32	6.51	4.37	5.59	3.37	0.05	-
Phosphorus	mg/L	2.09	0.70	1.61	3.29	0.76	0.26	0.24	0.47	0.28	0.42	0.70	0.44	1.61	0.55	-	-
Orthophosphate	mg/L	-	<0.10	<0.10	<0.10	0.08	-	<0.03	-	<0.03	0.08	0.12	-	<0.03	0.18	-	-
Turbidity	NTU	4050	777	1120	777	182	138	251	260	380	320	650	500	310	600	5	-
Total Suspended Solids	mg/L	2090	1980	3320	1160	1350	325	715	677	798	1650	1520	3940	441	714	-	-
BOD	mg/L	<5	<5	<5	-	<4	<4	<4	<4	<4	<4	5	<4	<4	<4	-	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.002	<0.002	<0.0001	<0.0001	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	-	0.00012
Aluminum	mg/L	0.017	0.213	0.032	0.042	0.067	0.025	0.038	0.043	0.038	0.046	0.049	0.043	0.029	0.080	0.1	-
Antimony	mg/L	<0.003	<0.003	<0.001	<0.001	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	0.006	1.6
Arsenic	mg/L	<0.003	<0.003	0.001	0.002	0.0007	0.0005	0.0007	0.0011	0.001	0.0009	0.0011	0.001	0.0010	0.0011	0.01	0.15
Barium	mg/L	0.103	0.134	0.137	0.110	0.144	0.127	0.145	0.127	0.135	0.124	0.118	0.111	0.148	0.105	1.00	2.3
Beryllium	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000028	0.000017	0.000025	0.00002	0.000039	0.000026	0.000025	0.000021	0.000021	0.000027	-	0.0053
Bismuth	mg/L	<0.002	<0.002	<0.002	<0.002	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	-	-
Boron	mg/L	0.344	0.320	0.419	0.237	0.435	0.309	0.432	0.224	0.404	0.269	0.287	0.247	0.350	0.319	5	3.55
Cadmium	mg/L	<0.001	<0.001	<0.0001	<0.0001	0.000018	0.000024	0.000015	0.000017	0.000044	0.000018	0.000022	0.000008	0.000014	0.000009	0.005	0.00021
Chromium	mg/L	<0.003	<0.003	<0.002	<0.002	0.00091	0.00092	0.00095	0.00086	0.00079	0.00094	0.00111	0.00093	0.00210	0.00086	0.05	0.064
Cobalt	mg/L	0.006	0.016	0.022	0.019	0.026	0.021	0.025	0.018	0.0263	0.017	0.0224	0.0159	0.0008	0.00971	-	0.0052
Copper	mg/L	0.004	0.008	0.004	0.003	0.003	0.004	0.0036	0.003	0.0025	0.003	0.003	0.002	0.001	0.002	1	0.0069
Molybdenum	mg/L	<0.002	<0.002	<0.002	<0.002	0.0006	0.00059	0.00075	0.00075	0.00066	0.00077	0.0008	0.0007	0.0005	0.0006	-	0.73
Nickel	mg/L	<0.003	<0.003	<0.003	<0.003	0.0025	0.0024	0.0029	0.0024	0.003	0.0028	0.0030	0.0024	0.0023	0.0021	-	0.039
Phosphate	mg/L	<0.10	-	-	-	-	-	-	-	-	-	-	<0.03	-	-	-	-
Lead	mg/L	<0.001	<0.001	<0.0005	<0.0005	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	0.00016	<0.00009	<0.00009	<0.00009	<0.00009	0.01	0.002
Selenium	mg/L	<0.004	<0.004	0.003	<0.001	0.00016	0.00012	0.00011	0.00014	0.00021	0.00018	0.00028	0.00011	0.00013	0.00012	0.05	0.005
Silicon	mg/L	-	-	-	0.246	-	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.002	<0.002	<0.002	0.006	0.00007	0.00006	0.00016	<0.00006	0.00012	0.00008	0.00008	0.00022	<0.00006	<0.00006	-	-
Strontium	mg/L	0.275	0.300	0.318	<0.0003	0.349	0.296	0.351	0.348	0.355	0.307	0.313	0.283	0.349	0.312	-	-
Titanium	mg/L	0.002	0.013	<0.002	<0.010	0.003	0.001	0.00088	0.001	0.0012	0.001	0.0018	0.002	0.0009	0.0044	-	-
Uranium	mg/L	<0.002	<0.002	0.0015	<0.002	0.00157	0.00112	0.00152	0.00148	0.00169	0.0018	0.00178	0.00157	0.00113	0.00150	0.02	0.033
Vanadium	mg/L	<0.002	<0.002	<0.002	<0.005	0.00107	0.00087	0.00153	0.00207	0.00149	0.00217	0.00232	0.00212	0.00130	0.00170	-	0.02
Zinc	mg/L	<0.005	<0.005	<0.005	-	0.004	0.006	0.003	0.003	0.003	0.003	<0.002	0.002	<0.002	0.010	5	0.089
Field Measurements																	
Temperature	oC	8.1	9.2	8.4	9.89	7.38	9.9	7.2	8.6	8.2	9.1	8.5	8.4	6.5	10.9	-	-
pH	pH Units	6.5	6.1	6.2	6.3	11.9	6.1	16.2	6.7	5.7	6.2	6.6	6.3	8.2	8.3	-	-
Conductivity	µS/cm	532.2	4.0	599.1	353	359	405	391	377	419	393	398	375	501	575.9	-	-
Oxidation Reduction Potential	mV	203.8	318.4	230.4	287.2	60	52.2	-15.2	1	79	11.9	29	13.8	165.1	245.4	-	-
Dissolved Oxygen	mg/L	1.19	1.54	2.07	12.85	2.36	1.43	4.31	1.01	1.65	0.92	1.61	5.06	0.75	0.32	-	-

Notes:

ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act, dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.

APV Aquatic Protection Values

BOLD Exceeds ODWQS

UNDERLINED Exceeds APV

Units All Units in mg/L Unless Otherwise Noted.

- No data available

TABLE 15
Groundwater Quality Results - BH10-I
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation														ODWQS	APV
		Sample Collection Date (07/05/2025)															
		BH10-I															
		11-Jun-19	23-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25		
pH Lab	pH Units	7.08	7.11	6.49	6.69	7.32	6.59	7.22	7.85	7.58	7.77	7.12	7.14	6.85	7.34	6.5-8.5	-
Conductivity	µS/cm	289	601	86	465	186	224	167	451	215	568	157	611	168	571	-	-
Hardness	mg/L	115	214	90.9	215	61.3	69.7	63.9	174	87.7	260	58.0	282	60.6	270	80-100	-
Total Dissolved Solids	mg/L	188	338	150	328	114	137	97	286	129	383	109	434	149	337	500	-
Alkalinity	mg/L	47	76	7	106	38	60	40	107	52	142	38	147	36	161	30-500	-
Chloride	mg/L	4.10	10.30	3.54	9.84	2	4	3	11	2	8	< 1	7	1	6	250	180
Sodium	mg/L	9.14	18.10	8.09	15.60	5.26	7.30	4.57	11.80	5.82	17.30	4.76	16.30	3.71	13.0	200	180
Calcium	mg/L	30.2	56.7	23.8	57.9	15.8	18.9	17.1	46.8	23.2	68.1	15.1	77.2	16.5	71.9	-	-
Magnesium	mg/L	9.60	17.50	7.6	17.0	5.3	5.5	5.17	13.9	7.2	21.8	4.91	21.8	4.71	22.0	-	-
Potassium	mg/L	5.52	7.64	4.35	7.17	3.16	4.32	3.69	6.24	4.71	8.65	3.42	8.61	3.60	8.77	-	-
Sulphate	mg/L	84.2	165.0	58	152	32	51	28	98	43	130	24	170	31	120	500	-
Ammonia	mg/L	0.11	0.15	<0.02	<0.02	<0.04	<0.04	<0.04	0.06	<0.04	0.04	0.07	<0.1	<0.1	<0.1	-	-
Nitrate as N	mg/L	1.24	2.22	1.10	2.57	3.18	1.85	3.47	2.44	2.51	3.08	2.39	2.58	3.51	2.29	10	-
Nitrite as N	mg/L	<0.05	<0.05	<0.05	<0.05	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	1	-
Total Kjeldahl Nitrogen	mg/L	0.44	0.68	0.41	0.09	0.11	0.42	0.17	0.35	0.26	0.20	<0.5	<0.5	<0.5	<0.5	-	-
Phenolics	mg/L	<0.001	0.001	<0.001	<0.001	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	-	0.961
Dissolved Organic Carbon	mg/L	5.6	5.9	6.6	7.8	5.0	6	4	5.0	6	7	3	8	4	10	5	-
Chemical Oxygen Demand	mg/L	11	21	20	<5	8	12	<8	<8	8	20	12	22	14	22	-	-
Iron	mg/L	<0.010	<0.010	0.024	0.032	0.024	0.019	0.031	0.025	0.02	0.012	0.022	0.014	0.062	0.027	0.3	-
Manganese	mg/L	0.067	0.016	0.005	0.006	0.003	0.001	0.00265	0.005	0.00723	0.005	0.00199	0.003	0.00189	0.00815	0.05	-
Phosphorus	mg/L	1.73	1.58	1.20	0.73	0.43	0.14	0.06	0.04	0.07	0.05	0.25	0.07	0.07	0.09	-	-
Orthophosphate	mg/L	-	<0.10	<0.10	<0.10	<0.03	-	<0.03	-	<0.03	<0.03	0.07	-	<0.03	0.04	-	-
Turbidity	NTU	982	1940	583	187	50	5.91	32.8	39	46	17	140	60	50	100	5	-
Total Suspended Solids	mg/L	1130	2060	1320	796	776	166	93	243	830	63	1240	223	207	354	-	-
BOD	mg/L	<5	<5	<5	-	5	<4	<4	<4	<4	<4	<4	<4	<4	<4	-	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.002	<0.002	<0.0001	<0.0001	0.00008	<0.00005	0.00006	<0.00005	<0.00005	<0.00005	0.00006	<0.00005	0.00008	<0.00005	-	0.00012
Aluminum	mg/L	0.049	0.045	0.069	0.045	0.053	0.059	0.057	0.023	0.064	0.028	0.065	0.031	0.071	0.029	0.1	-
Antimony	mg/L	<0.003	<0.003	<0.001	<0.001	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	0.006	1.6
Arsenic	mg/L	<0.003	<0.003	<0.001	<0.001	<0.0002	<0.0002	<0.0002	<0.0002	0.0004	0.0004	<0.0002	0.0007	0.0008	0.0008	0.01	0.15
Barium	mg/L	0.111	0.148	0.079	0.190	0.063	0.082	0.0767	0.213	0.0941	0.285	0.0496	0.277	0.0548	0.253	1	2.3
Beryllium	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000008	0.00001	<0.000007	<0.000007	0.000014	<0.000007	0.000007	0.000009	<0.000007	0.000007	-	0.0053
Bismuth	mg/L	<0.002	<0.002	<0.002	<0.002	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	-
Boron	mg/L	0.446	0.790	0.367	0.807	0.218	0.460	0.233	0.645	0.100	0.551	0.106	0.564	0.564	5	3.55	
Cadmium	mg/L	<0.001	<0.001	<0.0001	<0.0001	0.000003	0.000004	0.000146	0.000009	0.000011	0.000013	<0.000003	0.000012	0.000007	0.000011	0.005	0.00021
Chromium	mg/L	<0.003	<0.003	<0.002	<0.002	0.00049	0.00045	0.00042	0.00038	0.00053	0.00042	0.00053	0.00051	0.00013	0.00039	0.05	0.064
Cobalt	mg/L	0.001	<0.001	<0.0005	<0.0005	0.000191	0.000107	0.000136	0.000293	0.000169	0.000574	0.000132	0.000458	0.000520	0.000378	-	0.0052
Copper	mg/L	0.008	0.008	0.005	0.007	0.004	0.004	0.0038	0.004	0.0038	0.006	0.003	0.005	0.002	0.005	1	0.0069
Molybdenum	mg/L	<0.002	<0.002	<0.002	<0.002	0.00011	0.00021	0.00013	0.0003	0.00013	0.00025	<0.0004	<0.0004	<0.0004	<0.0004	-	0.73
Nickel	mg/L	0.004	0.003	<0.003	<0.003	0.001	0.0006	0.0006	0.0011	0.001	0.0023	0.0006	0.0021	0.0006	0.0018	-	0.039
Phosphate	mg/L	<0.10	-	-	-	-	-	-	-	-	-	-	<0.03	-	-	-	-
Lead	mg/L	<0.001	<0.001	<0.0005	<0.0005	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	<0.00009	0.01	0.002
Selenium	mg/L	<0.004	<0.004	0.002	<0.001	0.00005	0.00009	0.00005	0.00009	0.00012	0.00011	0.00009	0.00011	0.00004	0.00011	0.05	0.005
Sillicon	mg/L	-	-	-	0.321	-	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.002	<0.002	<0.002	0.003	0.00007	0.00007	0.00016	0.0001	0.00017	0.00009	<0.00006	0.0002	0.0002	<0.00006	-	-
Strontium	mg/L	0.187	0.343	0.149	<0.0003	0.100	0.110	0.106	0.372	0.148	0.490	0.100	0.601	0.108	0.498	-	-
Titanium	mg/L	<0.002	0.003	<0.002	<0.010	0.000	0.00049	0.00041	0.00027	0.00043	0.00018	0.0005	0.00040	0.0021	0.0003	-	-
Uranium	mg/L	<0.002	<0.002	0.0007	<0.002	0.00068	0.000637	0.000592	0.00247	0.000832	0.0043	0.000830	0.00472	0.000536	0.00357	0.02	0.033
Vanadium	mg/L	<0.002	<0.002	<0.002	<0.005	0.00036	0.00055	0.00052	0.0005	0.00046	0.00054	0.00049	0.0006	0.00047	0.00059	-	0.02
Zinc	mg/L	0.007	0.009	<0.005	-	<0.002	0.003	0.005	0.003	0.004	0.002	<0.002	0.002	0.002	0.010	5	0.089
Field Measurements																	
Temperature	oC	10.1	11.4	7.2	11.09	7.62	10.9	8.5	9.6	8.4	11	7.1	10.7	8.1	11.2	-	-
pH	pH Units	6.5	6.1	6.0	6.4	13.5	5.8	16.2	6.8	5.9	6.6	7.0	5.2	7.0	12.8	-	-
Conductivity	uS/cm	311.4	416.3	252.1	369	120	201	107	320	87	442	102	468.5	140	586.3	-	-
Oxidation Reduction Potential	mV	158.2	179.3	292	358.7	153.9	209.3	118.1	142.1	136.4	110.6	119.5	253.3	15.5	-49.4	-	-
Dissolved Oxygen	mg/L	9.19	8.14	8.07	10.91	12.58	6.62	80.5	10.42	9.4	1.89	9.25	12.09	6.89	0.37	-	-

Notes:

ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act", dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.

APV Aquatic Protection Values

BOLD Exceeds ODWQS

UNDERLINED Exceeds APV

Units All Units in mg/L Unless Otherwise Noted.

- No data available

TABLE 16
Groundwater Quality Results - BH11
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation														ODWQS
		Sample Collection Date (07/05/2025)														
		BH11														
		11-Jun-19	23-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25	
pH Lab	pH Units	6.38	6.33	6.77	6.12	6.81	6.21	7.22	6.91	6.71	7.10	6.46	6.20	6.40	6.26	6.5-8.5
Conductivity	µS/cm	82	94	248	37	92	107	120	99	89	83	85	90	83	100	-
Hardness	mg/L	25.1	23.5	25.6	7.5	24.6	36.3	32.2	26.0	28.2	26.7	29.8	25.2	27.4	31.3	80-100
Total Dissolved Solids	mg/L	60	66	66	34	60	49	60	51	66	< 30	63	43	91	77	500
Alkalinity	mg/L	7	10	49	15	11	12	26	12	8	7	9	8	8	9	30-500
Chloride	mg/L	13.5	12.6	13.5	2.3	15	20	22	21	19	20	17	20	15	22	250
Sodium	mg/L	3.52	3.89	4.01	5.12	3.75	4.71	4.71	4.19	4.21	4.47	4.75	4.11	4.04	4.95	200
Calcium	mg/L	8.18	7.76	8.45	2.42	8.24	11.60	10.6	8.82	9.47	8.90	9.85	8.32	9.13	10.2	-
Magnesium	mg/L	1.14	0.99	1.09	0.36	0.98	1.76	1.41	0.98	1.11	1.08	1.26	1.07	1.12	1.43	-
Potassium	mg/L	1.38	1.34	1.28	0.70	1.16	1.51	1.32	1.17	1.34	1.32	1.29	1.39	1.24	1.54	-
Sulphate	mg/L	4.93	5.64	5.63	4.20	4.00	4.00	4	5.00	4	5.00	4	5.00	3	4	500
Ammonia	mg/L	0.07	0.12	<0.02	<0.02	< 0.04	< 0.04	0.04	< 0.04	< 0.04	0.04	< 0.04	< 0.1	< 0.1	< 0.1	-
Nitrate as N	mg/L	0.40	0.20	0.15	0.09	0.21	0.21	0.19	0.76	0.21	0.16	0.28	0.17	0.26	0.17	10
Nitrite as N	mg/L	<0.05	<0.05	<0.05	<0.05	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	1
Total Kjeldahl Nitrogen	mg/L	0.18	0.19	0.21	0.20	0.34	< 0.05	0.09	0.09	< 0.05	0.15	0.06	< 0.5	< 0.5	< 0.5	-
Phenolics	mg/L	<0.001	<0.001	<0.001	<0.001	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	-
Dissolved Organic Carbon	mg/L	1.8	2	2.5	4.3	< 1	< 1	2	1	2	1	1	1	1	2	5
Chemical Oxygen Demand	mg/L	<5	<5	<5	<5	< 8	< 8	14	< 8	11	< 8	11	8	11	< 8	-
Iron	mg/L	<0.010	<0.010	0.011	0.08	0.018	0.017	0.054	0.041	0.065	0.031	0.084	0.446	0.121	0.024	0.3
Manganese	mg/L	0.021	0.016	0.012	0.017	0.024	0.021	0.0265	0.057	0.0335	0.025	0.0350	0.042	0.0306	0.0210	0.05
Phosphorus	mg/L	0.87	0.90	1.84	2.42	0.63	0.47	0.15	0.42	0.12	0.24	0.25	1.56	0.34	0.60	-
Orthophosphate	mg/L	-	<0.10	<0.10	<0.10	0.08	-	0.04	-	< 0.03	0.03	0.07	-	< 0.03	< 0.03	-
Turbidity	NTU	368	216	320	771	23.9	12.4	27.6	50	60	90	100	100	29	18	5
Total Suspended Solids	mg/L	1760	1110	430	3210	820	1330	230	422	449	728	763	1930	373	183	-
BOD	mg/L	<5	<5	<5	-	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.0002	<0.002	<0.0001	<0.0001	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	-
Aluminum	mg/L	0.030	0.034	0.033	0.239	0.027	0.013	0.034	0.035	0.035	0.024	0.034	0.340	0.094	0.025	0.1
Antimony	mg/L	<0.003	<0.003	<0.001	<0.001	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.006
Arsenic	mg/L	<0.003	<0.003	<0.001	0.001	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	0.010
Barium	mg/L	0.019	0.019	0.017	0.007	0.021	0.021	0.0224	0.027	0.0244	0.024	0.0211	0.0276	0.0233	0.0244	1.00
Beryllium	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000042	0.000036	0.000046	0.000043	0.00006	0.000055	0.000053	0.000065	0.000052	0.000055	-
Bismuth	mg/L	<0.002	<0.002	<0.002	<0.002	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	-
Boron	mg/L	<0.010	<0.010	<0.010	0.018	0.027	0.026	0.027	0.018	0.018	0.01	0.009	0.008	0.006	0.005	5
Cadmium	mg/L	<0.001	<0.001	<0.0001	<0.0001	0.000008	0.000018	0.000033	0.000016	0.000031	0.000022	0.000018	0.000018	0.000015	0.000029	0.005
Chromium	mg/L	<0.003	<0.003	<0.002	<0.002	0.00029	0.00016	0.00025	0.00022	0.00036	0.00019	0.00021	0.00059	0.00025	0.00009	0.05
Cobalt	mg/L	<0.001	<0.001	<0.0005	<0.0005	0.000115	0.000063	0.000135	0.000538	0.00021	0.000089	0.000210	0.000324	0.000330	0.000047	-
Copper	mg/L	<0.003	<0.003	<0.001	0.002	0.0009	0.0003	0.0019	0.0018	0.0005	0.002	< 0.001	0.002	< 0.001	< 0.001	1
Molybdenum	mg/L	<0.002	<0.002	<0.002	<0.002	0.00041	0.00006	0.00008	0.00012	0.00006	0.00007	< 0.0004	< 0.0004	< 0.0004	< 0.0004	-
Nickel	mg/L	<0.003	<0.003	<0.003	<0.003	0.0002	0.0003	0.0003	< 0.0001	0.0002	0.0003	0.0002	0.0004	0.0001	0.0002	-
Phosphate	mg/L	<0.10	-	-	-	-	-	-	-	-	-	-	< 0.03	-	-	-
Lead	mg/L	<0.001	<0.001	<0.0005	<0.0005	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	0.00045	< 0.00009	< 0.00009	0.01
Selenium	mg/L	<0.004	<0.004	<0.001	0.011	0.00005	< 0.00004	< 0.00004	0.00005	0.00006	< 0.00004	0.00007	0.00004	< 0.00004	< 0.00004	0.05
Silicon	mg/L	-	-	-	0.024	-	-	-	-	-	-	-	-	-	-	-
Tin	mg/L	<0.002	<0.002	<0.002	0.003	< 0.00006	< 0.00006	0.00006	< 0.00006	0.00007	< 0.00006	< 0.00006	< 0.00006	< 0.00006	< 0.00006	-
Strontium	mg/L	0.081	0.075	0.077	<0.0003	0.090	0.094	0.0968	0.108	0.103	0.091	0.0973	0.090	0.0967	0.106	-
Titanium	mg/L	<0.002	<0.002	<0.002	<0.010	0.00045	0.00027	0.00046	0.00057	0.00059	0.00021	0.0007	0.0196	0.0041	0.0002	-
Uranium	mg/L	<0.002	<0.002	<0.0005	<0.002	0.000067	0.000049	0.000086	0.000075	0.000061	0.000054	0.000064	0.000124	0.000054	0.000051	0.02
Vanadium	mg/L	<0.002	<0.002	<0.002	<0.005	0.00007	0.00005	0.00019	0.00009	0.00012	0.00006	0.00012	0.00077	0.00017	0.00008	-
Zinc	mg/L	<0.005	<0.005	<0.005	-	0.002	< 0.002	0.003	< 0.002	< 0.002	0.002	< 0.002	0.004	< 0.002	0.010	5
Field Measurements																
Temperature	oC	12.3	11.3	7.8	10.61	7.99	10.5	8	8.6	7.7	10.4	6.9	9	6.8	9.4	-
pH	pH Units	6.3	5.9	5.3	6.1	14.1	5.3	16.2	6.2	5.5	5.5	7.1	6.4	5.5	16.1	-
Conductivity	uS/cm	86	63.6	88.5	59	53	69	65	67	68	70	68	75	69	104.0	-
Oxidation Reduction Potential	mV	109.9	178.8	323.9	337.5	135.5	275.4	140.3	147	175.4	87.6	55.9	76.3	31.2	225.4	-
Dissolved Oxygen	mg/L	9.06	7.11	6.29	9.19	12.21	4.62	7.18	6.13	7.34	5.45	5.47	7.22	8.49	0.42	-

Notes:

ODWQS	Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act", dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.
APV	Aquatic Protection Values
BOLD	Exceeds ODWQS
<u>UNDERLINED</u>	Exceeds APV
Units	All Units in mg/L Unless Otherwise Noted.
-	No data available

TABLE 17
Guideline B-7 Calculations - Spring 2025
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation					ODWQS	Guideline B-7 Calculation				
		Sample Collection Date (07/05/2025)						Cm = Cb + x (Cr - Cb)				
		BH5-II	BH6-III	BH7-II	BH8-I	BH9-I		Cb	x	Cr	Cm	
		7-May-25	7-May-25	7-May-25	7-May-25	7-May-25						
Health Related	Antimony	mg/L	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.006	0.0006	0.25	0.006	0.002
	Arsenic	mg/L	< 0.0002	< 0.0002	< 0.0002	0.0003	0.0010	0.01	0.0002	0.25	0.01	0.003
	Barium	mg/L	0.0811	0.1170	0.0100	0.144	0.148	1	0.019	0.25	1	0.26
	Boron	mg/L	0.193	0.243	0.010	0.218	0.350	5	0.011	0.25	5	1.26
	Cadmium	mg/L	0.000023	0.000011	0.000014	0.000050	0.000014	0.005	0.00004	0.25	0.005	0.001
	Chromium	mg/L	0.00028	0.00030	0.00036	0.00032	0.00081	0.05	0.0004	0.25	0.05	0.013
	Lead	mg/L	< 0.00009	< 0.00009	0.00024	< 0.00009	< 0.00009	0.01	0.0001	0.25	0.01	0.003
	Nitrate as N	mg/L	1.43	1.47	0.07	1.16	< 0.06	10	0.22	0.25	10	2.67
	Nitrite as N	mg/L	0.06	< 0.03	< 0.03	0.38	< 0.03	1	0.024	0.25	1	0.27
	Selenium	mg/L	0.00007	0.00007	0.00007	0.00011	0.00013	0.05	0.0002	0.25	0.05	0.013
	Uranium	mg/L	0.000187	0.000230	0.000149	0.000384	0.00113	0.02	0.0002	0.25	0.02	0.005
	Non-Health Related	pH Lab	pH Units	6.83	6.82	6.55	7.16	6.86	6.5-8.5	6.63	0.5	6.5-8.5
Hardness		mg/L	115	169	7.60	132	173	80-100	24.5	0.5	80-100	NC
Total Dissolved Solids		mg/L	194	277	34	254	394	500	50.1	0.5	500	275
Alkalinity		mg/L	74	77	10	145	106	30-500	12.4	0.5	30-500	NC
Chloride		mg/L	6	4	6	18	9	250	14.2	0.5	250	132
Sodium		mg/L	8.03	7.30	4.18	14.4	14.9	200	4.28	0.5	200	102
Sulphate		mg/L	56	120	48	35	180	500	4.54	0.5	500	252
Dissolved Organic Carbon		mg/L	4	4	2	5	7	5	1.39	0.5	5	3.20
Iron		mg/L	0.008	0.012	0.129	0.013	19	0.3	0.025	0.5	0.3	0.16
Manganese		mg/L	0.170	0.0271	0.00606	1.53	5.59	0.05	0.024	0.5	0.05	0.037
Turbidity		NTU	45	2.2	180	8	310	5	92.7	0.5	5	NC
Aluminum		mg/L	0.023	0.011	0.114	0.021	0.029	0.1	0.035	0.5	0.1	0.067
Copper		mg/L	0.002	0.003	0.001	0.003	0.001	1	0.001	0.5	1	0.50
Zinc		mg/L	< 0.002	0.004	0.008	< 0.002	< 0.002	5	0.002	0.5	5	2.50

Notes:

ODWQS

BOLD	Exceeds Cm value.
INSV	Insufficient volume to allow for sampling
NC	Not Calculated due to the background concentration (Cb) being in exceedance of the ODWQS (Cr).
CNL	Could Not Locate
LS	Limited Sample
Units	All Units in mg/L Unless Otherwise Noted.
Cb	Background Concentration
Cr	Maximum Acceptable Contaminant Concentration
x	Reduction Constant
Cm	Maximum Off-Site Acceptable Contaminant Concentration

TABLE 18
Guideline B-7 Calculations - Fall 2025
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation					ODWQS	Guideline B-7 Calculation				
		Sample Collection Date (dd/mm/yyyy)						Cm = Cb + x (Cr - Cb)				
		BH5-II 26-Sep-25	BH6-III 26-Sep-25	BH7-II 26-Sep-25	BH8-I 26-Sep-25	BH9-I 26-Sep-25		Cb	x	Cr	Cm	
Health Related	Antimony	mg/L	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.006	0.0005	0.25	0.006	0.002
	Arsenic	mg/L	0.0004	0.0003	< 0.0002	0.0003	0.0011	0.01	0.0002	0.25	0.01	0.003
	Barium	mg/L	0.122	0.116	0.0142	0.12	0.105	1	0.020	0.25	1	0.26
	Boron	mg/L	0.286	0.291	0.01	0.266	0.319	5	0.010	0.25	5	1.26
	Cadmium	mg/L	0.000014	0.000006	0.000018	0.000048	0.000009	0.005	0.00004	0.25	0.005	0.001
	Chromium	mg/L	0.00038	0.00021	0.00033	0.00026	0.00086	0.05	0.0004	0.25	0.05	0.013
	Lead	mg/L	< 0.00009	< 0.00009	0.00	< 0.00009	< 0.00009	0.01	0.0001	0.25	0.01	0.003
	Nitrate as N	mg/L	2.24	1.56	< 0.06	2.46	< 0.06	10	0.18	0.25	10	2.63
	Nitrite as N	mg/L	0.04	< 0.03	< 0.03	0.20	< 0.03	1	0.023	0.25	1	0.27
	Selenium	mg/L	0.0001	0.0001	0.0	0.0001	0.0001	0.05	0.0001	0.25	0.05	0.013
	Uranium	mg/L	0.00037	0.000337	0.000167	0.000262	0.00150	0.02	0.0002	0.25	0.02	0.005
Non-Health Related	pH Lab	pH Units	6.90	6.93	6.37	7.01	7.21	6.5-8.5	6.55	0.5	6.5-8.5	6.5 - 7.5
	Hardness	mg/L	176	185	10.5	122	198	80-100	25.2	0.5	80-100	NC
	Total Dissolved Solids	mg/L	223	246	37	194	274	500	49.5	0.5	500	273
	Alkalinity	mg/L	98	159	11	117	207	30-500	11.4	0.5	30-500	NC
	Chloride	mg/L	7	6	2	24	28	250	15.1	0.5	250	132
	Sodium	mg/L	10.2	9.5	4.0	18.3	18.8	200	4.29	0.5	200	102
	Sulphate	mg/L	81	86	14	30	42	500	4.39	0.5	500	252
	Dissolved Organic Carbon	mg/L	6	6	2	6	8	5	1.36	0.5	5	3.18
	Iron	mg/L	0.007	< 0.007	0.172	0.008	9.52	0.3	0.034	0.5	0.3	0.17
	Manganese	mg/L	0.107	0.032	0.0185	1.57	3.37	0.05	0.025	0.5	0.05	0.038
	Turbidity	NTU	190	8.4	850	37	600	5	82.2	0.5	5	NC
	Aluminum	mg/L	0.017	0.005	0.131	0.019	0.08	0.1	0.043	0.5	0.1	0.071
	Copper	mg/L	0.003	0.003	0.002	0.004	0.002	1	0.001	0.5	1	0.50
	Zinc	mg/L	0.01	0.011	0.014	0.009	0.01	5	0.002	0.5	5	2.50

Notes:

ODWQS Ontario Regulation 169/03 "Ontario Drinking Water Quality Standards" under the Safe Drinking Water Act", dated 2002, and "Technical Support Document for Ontario Drinking Water Standards, Objectives and Guidelines", dated June 2003.

BOLD	Exceeds Cm value.
NC	Not Calculated due to the background concentration (Cb) being in exceedance of the ODWQS (Cr).
Units	All Units in mg/L Unless Otherwise Noted.
Cb	Background Concentration
Cr	Maximum Acceptable Contaminant Concentration
x	Reduction Constant
Cm	Maximum Off-Site Acceptable Contaminant Concentration

TABLE 19
Surface Water Quality Results - SW1
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation Sample Collection Date (07/05/2025)																						PWQO	CWQG	
		SW1																								
		13-May-15	22-Oct-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	19-Jun-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25			
pH Lab	pH Units	5.6	6.5	6.5	6.4	6.7	5.9	6.2	6.4	5.37	3.97	6.79	5.92	6.64	5.90	6.55	6.38	6.27	6.92	6.33	6.47	6.30	6.56	6.5-8.5	6.5-9.0	
Conductivity	µS/cm	28	77	150	87	119	34	-	78	37	118	258	37	63	48	71	48	58	97	39	58	75	-	-		
Hardness	mg/L	7.9	25	39	25	22	10	-	21	10.0	17.8	19.4	8.9	14.9	13.7	15.8	13.1	15.8	26.0	12.6	19.0	18.0	26.4	-	-	
Total Dissolved Solids	mg/L	28	66	104	158	26	28	74	38	34	54	62	34	60	54	69	54	106	< 30	66	74	51	-	-		
Alkalinity	mg/L	1.7	6	11	7	14	<5	-	9	<5	<5	52	6	5	3	< 4	< 2	3	8	2	4	7	7	-	-	
Alkalinity Bicarbonate	-	-	-	-	-	-	-	8	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Chloride	mg/L	5	14	16	13	11	4	25.1	10	7.09	11.7	14.10	7.3	15.0	14.0	19	8.0	17.0	25.0	10	12.0	14	20	-	120	
Sodium	mg/L	1.6	3.5	5.16	3.75	3.43	1.68	-	3.09	2.42	3.51	4.48	1.95	4.16	4.58	4.64	2.54	4.64	6.35	2.55	3.41	4.06	4.79	-	-	
Calcium	mg/L	2.4	7.6	12.4	7.96	6.98	3.12	-	6.48	2.96	5.51	6.01	2.61	6.40	4.22	4.83	3.79	4.76	8.15	3.72	5.67	5.34	8.13	-	-	
Magnesium	mg/L	0.45	1.4	1.98	1.31	1.21	0.556	-	1.16	0.64	0.99	1.07	0.59	0.84	0.77	0.901	0.89	0.96	1.37	0.810	1.18	1.14	1.49	-	-	
Potassium	mg/L	0.5	1.5	2.15	0.841	0.923	0.551	-	0.677	0.23	0.80	0.84	0.59	0.44	0.56	0.568	0.64	0.51	1.07	0.397	0.64	0.477	1.08	-	-	
Sulphate	mg/L	<1	4	27	13	11	5	4	10	0.90	13.8	2.79	1.4	< 2	< 2	3	5.0	< 2	4.0	< 2	< 2	< 2	4	-	-	
Ammonia	mg/L	<0.05	0.069	0.02	0.01	0.02	0.02	0.05	0.01	0.09	0.08	<0.02	<0.02	< 0.04	0.04	< 0.04	< 0.04	< 0.04	0.04	< 0.04	< 0.1	< 0.1	< 0.1	-	-	
Un-ionized Ammonia	-	0.0009	0.0001	0.00003	0.00001	0.00005	0.00007	-	0.000011	-	-	-	-	0.000828	0.000169	-	-	-	-	-	-	-	-	-	0.02	0.019
Nitrate as N	mg/L	<0.1	<0.1	<0.1	0.2	0.1	<0.1	0.36	0.1	<0.05	<0.05	0.06	<0.05	< 0.06	<0.06	< 0.06	< 0.06	0.06	< 0.06	< 0.06	< 0.06	< 0.06	0.06	-	13	
Nitrite as N	mg/L	<0.01	<0.01	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	< 0.03	<0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	-	0.06	
Total Kjeldahl Nitrogen	mg/L	0.26	0.56	0.2	0.4	0.3	0.2	0.28	0.2	0.30	0.38	0.30	0.39	0.20	0.08	0.16	0.25	< 0.05	0.08	< 0.5	< 0.5	< 0.5	< 0.5	-	-	
Phenolics	mg/L	<0.001	<0.001	0.009	<0.001	0.002	<0.001	0.002	<0.001	0.001	0.003	0.001	<0.001	< 0.001	<0.001	< 0.001	< 0.001	< 0.001	< 0.001	0.002	0.001	< 0.001	< 0.001	0.001	0.004	
Dissolved Organic Carbon	mg/L	8.1	6.5	9.4	7.4	10.6	13.4	-	7	8.9	13.2	6.8	14.2	5.0	15.0	6	9.0	8.0	2.0	6	6	6	3	-	-	
Chemical Oxygen Demand	mg/L	21	40	35	32	30	21	25	25	19	30	19	16	16	25	20	17	22	22	9	17	12	10	-	-	
Biological Oxygen Demand	mg/L	<2	<2	4	<2	<2	<2	<5	<2	<5	<5	<5	-	< 4	< 4	8	< 4	< 4	< 4	< 4	< 4	< 4	< 4	-	-	
Iron	mg/L	0.52	3.30	<0.5	0.46	0.40	0.25	0.49	0.21	0.369	0.383	0.389	0.427	0.212	0.401	0.178	0.302	0.219	0.489	0.236	0.309	0.295	0.258	0.30	0.30	
Manganese	mg/L	0.054	0.12	0.063	0.057	0.045	0.032	-	0.046	0.057	0.070	0.041	0.059	0.034	0.041	0.0376	0.070	0.034	0.042	0.0333	0.037	0.0426	0.0228	-	-	
Phosphorus	mg/L	0.012	0.13	<0.01	<0.01	0.03	<0.01	<0.02	<0.01	0.02	0.02	<0.02	<0.02	0.01	0.01	< 0.003	0.01	0.02	0.02	0.003	0.02	0.004	0.010	0.03	-	
Orthophosphate	mg/L	<0.01	<0.01	-	-	-	-	-	-	<0.10	<0.10	<0.10	<0.10	< 0.03	-	< 0.03	-	< 0.03	< 0.03	< 0.03	< 0.03	-	< 0.03	-	-	
Total Suspended Solids	mg/L	1	11	<2	15	8	6	<10	<2	<10	<10	<10	18	<10	5	5	4	2	3	15	5	< 2	< 3	27	-	-
Bicarbonate	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Turbidity	NTU	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Anion Sum	-	0.167	0.59	1.24	0.79	0.82	0.28	-	0.66	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	0.272	0.74	1.06	0.69	0.62	0.29	-	0.57	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	NC	NC	-7.7	N/A	N/A	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.0001	<0.0001	<0.0005	<0.0001	<0.1	<0.0001	-	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	< 0.00005	<0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	0.0001	0.00025	
Aluminum	mg/L	0.27	0.8	0.085	0.139	0.177	0.178	-	0.158	0.200	0.220	0.104	0.248	0.115	0.177	0.138	0.25	0.169	0.028	0.162	0.119	0.176	0.040	0.075	0.1	
Antimony	mg/L	<0.0005	<0.0005	0.005	<0.0005	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.02	-	
Arsenic	mg/L	<0.001	<0.001	<0.005	<0.001	<0.001	<0.001	<0.003	<0.001	<0.003	<0.003	<0.003	<0.003	< 0.0002	<0.0002	< 0.0002	0.0002	0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	0.005	0.005	
Barium	mg/L	0.015	0.035	0.045	0.033	0.029	0.014	0.043	0.024	0.020	0.035	0.024	0.021	0.0253	0.0224	0.0274	0.0243	0.0254	0.0368	0.0193	0.0246	0.0282	0.0289	-	-	
Beryllium	mg/L	<0.0005	<0.0005	<0.0025	<0.0005	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.0005	0.000027	0.000030	0.000019	0.000048	0.000032	0.000039	0.000034	0.000020	0.000031	0.000032	1.1	-	
Bismuth	mg/L	<0.001	<0.001	0.01	<0.001	<0.001	<0.001	-	<0.001	<0.002	<0.002	<0.002	<0.002	< 0.00001	<0.00001	< 0.00001	0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	-	-	
Boron	mg/L	<0.01	0.013	0.111	0.053	0.139	0.03	0.022	0.032	<0.010	0.010	<0.010	<0.010	0.005	0.02	0.009	0.004	0.005	0.006	0.005	0.005	0.012	0.20	1.5	-	
Cadmium	mg/L	<0.0001	0.00024	<0.0005	<0.0001	<0.0001	0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	0.000031	0.000034	0.000024	0.000063	0.000040	0.000027	0.000034	0.000022	0.000043	0.000011	0.000020	0.00026	
Chromium	mg/L	<0.005	<0.005	<0.005	<0.001	<0.001	<0.001	<0.003	<0.001	<0.003	<0.003	<0.003	<0.003	0.0003	0.0003	0.00025	0.00044	0.00031	0.00034	0.00034	0.00039	0.00076	0.00021	0.0089	0.001	
Cobalt	mg/L	0.00100	0.00120	<0.0025	0.0009	0.0006	0.0005	-	0.0007	0.0012	0.0014	0.0006	0.0006	0.000527	0.000888	0.000644	0.00159	0.000639	0.000624	0.000620	0.000466	0.000390	0.000312	0.0009	-	
Copper	mg/L	<0.001	0.0023	<0.0025	0.0006	<0.0005	<0.0005	<0.002	0.0008	<0.001	<0.003	0.002	<0.001	0.0005	<0.004	0.0024	0.0008	0.0006	0.0009	< 0.001	< 0.001	0.001	< 0.001	0.005	0.004	
Molybdenum	mg/L	<0.0005	<0.0005	0.0029	<0.0005	0.0041	<0.0005	-	<0.0005	<0.002	<0.002	<0.002	<0.002	< 0.00004	< 0.00004	< 0.00004	< 0.00004	< 0.00004	< 0.00004	< 0.0004	< 0.0004	< 0.0004	< 0.0004	0.04	0.073	
Nickel	mg/L	<0.001	<0.001	<0.005	0.001	<0.001	<0.001	-	<0.001	<0.003	<0.003	<0.003	<0.003	0.0005	0.0011	0.0009	0.0011	0.0008	0.0005	0.0007	0.0008	0.0003	0.025	0.15	-	
Phosphate	mg/L	-	-	<0.0002	<0.2	<0.2	<0.2	-	<0.2	<0.10	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Lead	mg/L	<0.0005	0.0021	0.0025	0.0002	0.0003	0.0003	<0.001	0.0001	<0.001	<0.001	<0.001	<0.001	0.00025	0.00028	0.0002	0.00025	0.00027	0.00053	0.00034	0.0002	0.00022	0.00027	0.005	0.007	
Selenium	mg/L	<0.002	<0.002	0.0025	<0.001	<0.001	<0.001	-	<0.001	<0.004	<0.004	<0.004	<0.004	0.00005	<0.00004	< 0.00004	0.00006	0.00008	0.00007	0.00008	0.00005	0.00007	< 0.00004	0.1	0.001	
Silicon	mg/L	1.6	4.8	<0.005	2.26	2.63	1.77	-	2.49	2.07	2.79	3.19	2.67	2.62	2											

**TABLE 20
Surface Water Quality Results - SW2
Chapman Waste Disposal Site
Magnetawan, Ontario**

Parameter	Units	Sample Designation																				PWQO	CWQG	
		Sample Collection Date (07/05/2025)																						
		13-May-15	22-Oct-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25			26-Sep-25
pH Lab	pH Units	6.1	6.8	DRY	7.2	7.4	6.4	6.7	6.72	6.43	6.43	5.85	6.29	6.37	7.05	7.40	7.35	7.41	7.21	7.17	6.63	7.22	6.5-8.5	6.5-9.0
Conductivity	µS/cm	37	100	-	112	122	29	58	62	105	24	10	10	68	87	68	93	149	54	117	91	134	-	-
Hardness	mg/L	12	34	-	29	26	8	19	19.8	28.4	4.3	3.3	2.7	23.2	27.4	15.1	31.8	45.3	19.5	38.9	29.8	44.9	-	-
Total Dissolved Solids	mg/L	38	84	-	102	26	18	42	40	66	22	<20	< 30	40	66	66	77	123	37	89	60	77	-	-
Alkalinity	mg/L	4.2	14	-	21	40	<5	12	8	7	<5	<5	2	10	< 4	17	17	29	11	21	15	25	-	-
Alkalinity Bicarbonate	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Chloride	mg/L	4	12	-	9	7	3	6	6.99	11.1	2.12	0.3	< 1	9	12	6	12	20	6	15	10	20	-	120
Sodium	mg/L	1.9	5.1	-	4.62	4.81	1.39	2.65	3.16	4.63	1.08	0.36	0.34	5.27	4.75	2.56	5.36	8.11	3.05	6.03	4.48	8.00	-	-
Calcium	mg/L	3.3	8.9	-	8.85	10.2	2.53	5.68	6.02	8.65	1.16	0.86	0.69	7.01	8.45	4.46	9.45	13.60	5.88	11.50	8.91	13.4	-	-
Magnesium	mg/L	0.69	2.4	-	1.76	<2.0	0.515	1.2	1.15	1.65	0.35	0.28	0.24	1.38	1.53	0.97	2.00	2.78	1.17	2.50	1.85	2.77	-	-
Potassium	mg/L	0.81	3.1	-	2.12	2.53	0.616	1.02	1.19	1.55	0.65	0.22	0.09	1.38	1.37	0.85	1.54	2.37	0.989	2.24	1.480	2.34	-	-
Sulphate	mg/L	4	11	-	13	9	4	7	4.74	10.6	1.99	1.5	< 2	8.0	9	6.0	10.0	15.0	6	11.0	10	13	-	-
Ammonia	mg/L	<0.05	<0.05	-	0.35	1.42	0.06	0.03	0.19	0.12	<0.02	0.03	< 0.04	0.08	0.07	< 0.04	0.08	0.04	0.12	< 0.1	< 0.1	< 0.1	-	-
Un-ionized Ammonia	-	0.0002	0	-	0.003	0.018	0.0001	0.0001	-	-	-	0.00029	0.000452	0.0005411	-	-	-	-	-	-	-	-	0.02	0.019
Nitrate as N	mg/L	0.17	0.14	-	0.7	0.2	0.2	0.3	0.21	0.17	<0.05	<0.05	< 0.06	0.21	0.38	1.16	0.37	0.41	0.19	0.1	0.34	0.35	-	13
Nitrite as N	mg/L	<0.01	<0.01	-	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	< 0.03	<0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.06
Total Kjeldahl Nitrogen	mg/L	<0.5	0.18	-	0.6	1.4	0.2	0.2	0.43	0.41	0.22	0.42	0.20	0.19	0.2	0.26	0.29	0.06	0.29	< 0.5	< 0.5	< 0.5	-	-
Phenolics	mg/L	<0.001	<0.001	-	<0.001	0.002	<0.001	<0.001	<0.001	0.002	<0.001	<0.001	< 0.001	<0.001	< 0.001	< 0.001	< 0.001	< 0.001	0.002	0.002	< 0.001	< 0.001	0.001	0.004
Dissolved Organic Carbon	mg/L	5.5	6.3	-	5.4	7	7.7	4.8	6.4	9.8	3.5	7.7	9.0	3.0	4	6.0	4.0	3.0	4	4.0	5	3	-	-
Chemical Oxygen Demand	mg/L	9.1	7.4	-	29	16	13	21	16	22	6	<5	< 8	14	16	15	< 8	< 8	14	13	< 8	9	-	-
Biological Oxygen Dema-	mg/L	<2	<2	-	<2	<2	<2	<2	<5	<5	<5	< 4	< 4	3	< 4	< 4	< 4	< 4	< 4	< 4	< 4	< 4	-	-
Iron	mg/L	0.59	1.40	-	<0.1	0.39	0.30	0.16	0.151	0.088	0.308	1.080	0.401	0.195	0.091	0.301	0.104	0.029	0.153	0.055	0.087	0.074	0.30	0.30
Manganese	mg/L	0.11	0.12	-	0.031	1.29	0.048	1.2	0.070	0.030	0.461	0.068	0.018	0.035	0.0367	0.033	0.041	0.015	0.0369	0.015	0.0157	0.0628	-	-
Phosphorus	mg/L	0.01	0.017	-	<0.01	0.01	<0.01	<0.01	0.02	<0.02	0.05	<0.02	0.009	<0.003	< 0.003	0.01	0.009	< 0.003	0.005	0.003	0.003	< 0.003	0.03	-
Orthophosphate	mg/L	<0.01	<0.01	-	-	-	-	-	<0.10	<0.10	<0.10	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	-	-
Total Suspended Solids	mg/L	4	20	-	<2	11	6	<2	<10	<10	<10	<10	< 2	6	15	2	3	4	< 2	2	< 2	8	-	-
Bicarbonate	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Turbidity	NTU	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Anion Sum	-	0.286	0.847	-	1.02	1.19	0.26	0.58	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	0.356	1.03	-	0.84	0.94	0.24	0.52	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	NC	NC	-	-9.6	N/A	-3.3	-5.1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.0001	<0.0001	-	<0.0001	<0.1	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	< 0.00005	<0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	0.0001	0.00025
Aluminum	mg/L	0.40	0.89	-	0.082	0.042	0.12	0.12	0.110	0.099	0.097	0.071	0.03	0.085	0.063	0.128	0.069	0.013	0.110	0.029	0.079	0.016	0.075	0.1
Antimony	mg/L	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.001	<0.003	<0.001	<0.001	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.02	-
Arsenic	mg/L	<0.001	<0.001	-	<0.001	<0.001	<0.001	<0.001	<0.003	<0.003	<0.003	<0.003	< 0.0002	<0.0002	< 0.0002	0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	< 0.0002	0.10	0.01
Barium	mg/L	0.022	0.044	-	0.04	0.171	0.015	0.024	0.027	0.037	0.014	0.012	0.009	0.031	0.0293	0.023	0.030	0.041	0.0236	0.037	0.0300	0.0401	-	-
Beryllium	mg/L	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	<0.0005	<0.001	<0.0005	<0.0005	0.000017	0.00003	0.000026	0.000027	0.000018	< 0.000007	0.000024	0.000014	0.000019	0.000007	1.1	-	-
Bismuth	mg/L	<0.001	<0.001	-	<0.001	<0.001	<0.001	<0.001	<0.002	<0.002	<0.002	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	-	-
Boron	mg/L	0.018	0.053	-	0.07	0.61	0.021	0.027	0.028	0.043	<0.010	<0.010	0.002	0.041	0.04	0.015	0.056	0.052	0.028	0.044	0.044	0.057	0.20	1.50
Cadmium	mg/L	<0.0001	<0.0001	-	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	0.0003	0.000012	0.000017	0.000006	0.000022	0.000018	0.000007	0.000022	0.000008	0.000018	0.000009	0.00020	0.00026
Chromium	mg/L	<0.005	<0.005	-	<0.001	<0.001	<0.001	<0.001	<0.003	<0.003	<0.003	<0.003	0.00026	0.00031	0.00023	0.00028	0.0003	0.0002	0.00033	0.00031	0.00014	0.00022	0.0089	0.001
Cobalt	mg/L	0.0012	0.0011	-	<0.0005	0.0032	<0.0005	<0.0005	<0.0005	<0.0005	0.0028	0.0012	0.000637	0.000234	0.000199	0.000239	0.000231	0.000112	0.000243	0.000115	0.000320	0.000253	0.0009	-
Copper	mg/L	0.0012	0.0025	-	0.0006	0.0048	<0.0005	0.0006	<0.001	<0.003	<0.001	<0.001	0.0003	0.0006	0.0015	0.0007	0.001	0.0008	< 0.001	< 0.001	< 0.001	< 0.001	0.005	0.004
Molybdenum	mg/L	<0.0005	<0.0005	-	<0.0005	0.0015	<0.0005	<0.0005	<0.002	<0.002	<0.002	<0.002	< 0.00004	< 0.00004	< 0.00004	< 0.00004	< 0.00004	< 0.00004	< 0.0004	< 0.0004	< 0.0004	< 0.0004	0.04	0.073
Nickel	mg/L	0.0017	0.0012	-	0.001	0.001	<0.001	<0.001	<0.003	<0.003	<0.003	<0.003	0.0004	0.0008	0.0007	0.0008	0.0007	0.0005	0.0006	0.0005	0.0005	0.0002	0.025	0.15
Phosphate	mg/L	-	-	-	<0.2	<0.2	<0.0002	<0.0002	<0.10	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Lead	mg/L	0.00051	0.0013	-	<0.0001	<0.0001	0.0002	0.0001	<0.001	<0.001	<0.001</													

TABLE 21
Surface Water Quality Results - SW3
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation																						PWQO	CWQG	
		Sample Collection Date (07/05/2025)																								
		SW3																								
		13-May-15	22-Oct-15	13-Oct-16	18-May-17	25-Oct-17	2-May-18	19-Jun-18	17-Oct-18	11-Jun-19	26-Sep-19	1-Jun-20	30-Sep-20	12-May-21	7-Oct-21	4-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25			
pH lab	pH Units	6.4	7.6	7.0	7.3	6.8	7.1	7.1	7.0	7.34	6.79	7.16	6.35	7.56	6.68	7.5	6.88	7.78	7.93	7.53	7.55	7.25	7.13	6.5-8.5	6.5-9.0	
Conductivity	µS/cm	47	240	321	318	74	69	-	86	114	397	251	80	126	87	138	26	251	398	63	314	249	337	-	-	
Hardness	mg/L	14	76	88	95	20	17	-	25	35.6	96.6	77.1	21.4	35.4	29.1	43.5	8.6	92.9	120.0	18.2	100.0	81.6	114	-	-	
Total Dissolved Solids	mg/L	18	146	186	216	34	24	174	26	52	198	128	42	91	57	89	<30	149	237	49	169	154	183	-	-	
Alkalinity, total	mg/L	10	67	89	102	13	23	-	30	37	38	72	36	41	30	<4	6	83	149	24	124	76	137	-	-	
Alkalinity Bicarbonate	mg/L	-	-	-	-	-	-	108	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
Chloride	mg/L	3	21	27	18	6	5	27	7	5.88	29.2	14.30	5.7	10.0	10.0	12	<1	19.0	31.0	3	22.0	13	27	-	120	
Sodium	mg/L	2.3	12	10.9	14.3	2.84	2.96	-	3.29	4.83	16.8	12.00	3.6	6.3	6.7	7.44	1.6	14.3	22.0	2.99	16.7	11.40	17.6	-	-	
Calcium	mg/L	3.9	22	28.7	29.2	6.15	5.25	-	7.71	11.3	30.8	23.9	6.6	7.71	9.3	13.8	2.5	28.5	37.5	5.47	31.0	24.80	35.5	-	-	
Magnesium	mg/L	0.8	3.9	4.09	5.27	1.24	0.993	-	1.3	1.79	4.77	4.22	1.18	1.94	1.46	2.19	0.55	5.27	6.43	1.10	5.58	4.78	6.16	-	-	
Potassium	mg/L	1.3	10	8.55	8.66	1.37	1.69	-	2.22	2.88	9.14	5.65	1.93	2.33	2.44	2.93	0.66	5.28	9.98	1.30	9.26	5.66	9.18	-	-	
Sulphate	mg/L	4	8	14	31	8	3	16	3	6.70	75.5	21.10	2.4	6.0	2.0	9	<2	22.0	9.0	4	8.0	23	11	-	-	
Ammonia as N	mg/L	0.1	1.7	2.1	4.1	0.1	1.3	1.7	0.5	1.31	1.65	1.06	0.69	0.80	0.68	1.08	0.15	2.03	3.88	0.60	3.30	1.60	3.9	-	-	
Un-ionized Ammonia	mg/L	0	0.0013	0.009	0.038	0.0005	0.0077	-	0.0027	-	-	0.00089	0.00066	0.00612	0.00113	-	-	-	-	-	-	-	-	0.02	0.019	
Nitrate as N	mg/L	0.27	1.53	2.80	1.10	0.70	0.20	1.54	0.40	0.16	1.10	1.08	0.08	0.49	0.27	0.44	<0.06	0.53	0.41	0.14	0.4	1.02	0.42	-	13	
Nitrite as N	mg/L	<0.01	0.013	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	-	0.06	
Total Kjeldahl Nitrogen	mg/L	0.57	2.1	2.6	4.3	0.3	1.3	2.1	0.8	1.49	2.12	1.30	0.46	0.95	1.06	1.24	0.46	2.32	3.76	0.93	3.30	1.60	4.0	-	-	
Phenolics	mg/L	<0.001	<0.001	0.0040	<0.001	<0.001	<0.001	<0.001	<0.001	<0.001	0.001	<0.001	<0.001	<0.001	<0.001	0.002	<0.001	<0.001	0.001	0.002	0.002	<0.001	<0.001	0.001	0.004	
Dissolved Organic Carbon	mg/L	4.6	5.3	7.4	7	6.6	7.6	-	4	4.2	7.2	6.2	9.8	5.0	5.0	5	5.0	5.0	7.0	3	7.0	5	7	-	-	
Chemical Oxygen Demand	mg/L	1.1	7.4	48	33	17	17	26	18	7	17	13	<5	18	9	13	16	29	23	8	10	27	15	22	-	-
Biological Oxygen Demand	mg/L	<2	<2	11	<2	<2	<2	<5	<2	<5	<2	<5	<4	<4	<4	<2	<4	<4	<4	<4	<4	<4	<4	-	-	
Iron	mg/L	0.64	0.24	1.23	<0.1	0.2	1.70	0.013	5.60	0.411	5.82	0.298	0.81	0.44	0.55	0.563	1.00	0.57	5.52	0.647	1.25	1.490	3.70	0.30	0.30	
Manganese	mg/L	0.063	0.56	3.03	1.72	0.069	0.57	-	3.03	0.46	0.613	5.49	0.943	1.21	0.80	0.48	1.07	0.26	2.03	5.54	0.397	3.14	1.040	3.60	-	-
Phosphorus, total	mg/L	0.016	0.009	0.03	<0.01	<0.01	<0.01	<0.02	0.01	0.02	0.02	0.03	<0.02	0.01	<0.003	<0.003	0.02	0.01	0.01	<0.003	0.004	<0.003	0.003	0.03	-	
Orthophosphate	mg/L	<0.01	<0.01	-	-	-	-	-	-	-	<0.10	<0.10	<0.10	<0.03	-	<0.03	-	<0.03	<0.03	<0.03	<0.03	<0.03	<0.03	-	-	
Total Suspended Solids	mg/L	<1	<10	65	6	14	39	<10	21	<10	30	<10	<10	<10	<2	<10	3	44	2	15	3	13	2	3	-	-
Bicarbonate	mg/L	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Turbidity	NTU	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Anion Sum	-	0.388	2.19	3.03	3.27	0.66	0.67	-	0.89	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	0.452	2.44	2.46	2.73	0.57	0.52	-	0.69	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	NC	NC	-10.3	-8.9	N/A	<0.1	-	-12.7	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	<0.0001	<0.0001	<0.0005	<0.0001	<0.1	<0.0001	-	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	<0.00005	0.0001	0.00025	
Aluminum	mg/L	0.100	0.076	0.019	0.190	0.096	0.025	-	0.071	0.035	0.016	0.013	0.048	0.022	0.015	0.022	0.067	0.028	0.005	0.048	0.008	0.016	0.006	0.075	0.1	
Antimony	mg/L	<0.0005	<0.0005	0.0087	<0.0005	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.0005	<0.001	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009	<0.0009
Arsenic	mg/L	<0.001	<0.001	<0.005	<0.001	<0.001	<0.001	<0.003	<0.001	<0.003	<0.003	<0.003	<0.003	<0.002	<0.002	0.0002	0.0002	<0.0002	0.0003	<0.0002	0.0002	0.0002	0.0004	0.10	0.01	
Barium	mg/L	0.021	0.082	0.13	0.085	0.028	0.029	0.061	0.022	0.033	0.154	0.040	0.028	0.026	0.022	0.0321	0.013	0.045	0.084	0.0186	0.059	0.0438	0.0874	-	-	
Beryllium	mg/L	<0.0005	<0.0005	<0.0025	<0.0005	<0.0005	<0.0005	-	<0.0005	<0.0005	<0.001	<0.0005	<0.0005	0.00001	0.000013	<0.000007	0.000016	0.000011	0.000015	0.000016	0.000007	0.000007	0.000010	1.1	-	
Bismuth	mg/L	<0.001	<0.001	0.035	<0.001	<0.001	<0.001	-	<0.001	<0.002	<0.002	<0.002	<0.002	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	<0.00001	-	-	
Boron	mg/L	0.03	0.15	0.18	0.22	0.06	0.04	0.26	0.034	0.075	0.232	0.175	0.048	0.095	0.057	0.097	0.013	0.241	0.192	0.040	0.173	0.201	0.207	0.20	1.50	
Cadmium	mg/L	<0.0001	<0.0001	<0.0005	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	0.0002	<0.0001	<0.0001	0.000016	0.000015	0.000012	0.000019	0.000028	0.000045	0.000019	0.000027	0.000017	0.000018	0.00020	0.00026	
Chromium	mg/L	<0.005	<0.005	<0.005	<0.001	<0.001	<0.001	<0.003	<0.001	<0.003	<0.003	<0.003	<0.003	0.00037	0.00026	0.00031	0.00034	0.00042	0.00075	0.00022	0.00041	0.00359	0.00057	0.0089	0.001	
Cobalt	mg/L	0.0010	0.0022	0.0117	0.0021	<0.0005	0.0034	-	0.0016	0.0021	0.0166	0.0023	0.0031	0.0023	0.0018	0.0035	0.0012	0.0047	0.0129	0.00153	0.0064	0.00037	0.00947	0.0009	-	
Copper	mg/L	<0.001	0.0022	0.00380	0.0023	<0.0005	<0.0005	<0.002	0.0009	0.001	0.004	<0.001	0.002	0.001	0.001	0.0027	0.001	0.001	0.003	<0.001	0.002	<0.001	0.005	0.004	-	
Molybdenum	mg/L	<0.0005	<0.0005	0.0093	<0.0005	<0.0005	<0.0005	-	<0.0005	<0.002	<0.002	<0.002	<0.002	0.00006	0.00004	0.00007	<0.00004	0.00008	0.00026	<0.0004	<0.0004	<0.0004	<0.0004	0.04	0.073	
Nickel	mg/L	<0.001	<0.001	<0.005	0.001	<0.001	0.001	-	<0.001	<0.003	<0.003	<0.003	<0.003	0.0008	0.0008	0.001	0.0008	0.0014	0.0026	0.0007	0.0027	0.0010	0.0016	0.025	0.15	
Phosphate as P	mg/L	-	-	<0.0002	<0.2	<0.2	<0.2	-	<0.2	<0.10	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Lead	mg/L	<0.0005	<0.0005	0.0014	<0.0001	<0.0001	0.0005	<0.001	0.0003	<0.001	<0.001	<0.001	<0.001	<0.00009	0.00014	<0.00009	0.00045	<0.00009	0.00013	0.00011	<0.00009	<0.00009	<0.00009	0.005	0.007	
Selenium	mg/L	<0.002	<0.002	<0.005	<0.001	<0.001	<0.001	-	<0.001	<0.004	<0.004	<0.004	<0.004	<0.00004	<0.00004	<0.00004	0.00006	0.0001	0.00015	0.00006	0.00007	0.00009	<0.00004	0.1	0.001	
Silicon	mg/L	1.3	3.9	2.9	2.9	2.71	1.36	-	1.17	1.44	4.79	3.18	2.24	1.72	2.51	2.9	1.02	3.91	5.25	1.93	4.78	4.50	5.57	-	-	
Tin	mg/L	<0.001	<0.001	<0.025	<0.005	<0.005	<																			

TABLE 22
Surface Water Quality Results - SEEP
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	Sample Designation Sample Collection Date (07/05/2025)										PWQO	CWQG
		SEEP											
		12-May-21	7-Oct-21	12-May-22	19-Oct-22	10-May-23	28-Sep-23	23-Apr-24	2-Oct-24	7-May-25	26-Sep-25		
pH lab	pH Units	7.72	6.91	7.91	7.69	7.71	7.80	7.74	7.26	7.75	7.02	6.5-8.5	6.5-9.0
Conductivity	µS/cm	413	379	344	364	485	385	319	324	437	279	-	-
Hardness	mg/L	123.0	112.0	136	126.0	172.0	112.0	114	109.0	142	101	-	-
Total Dissolved Solids	mg/L	269	229	211	220	254	220	211	197	254	154	-	-
Alkalinity, total	mg/L	143	147	< 4	137	173	145	144	134	154	101	-	-
Alkalinity Bicarbonate	mg/L	-	-	-	-	-	-	-	-	-	-	-	-
Chloride	mg/L	30	34	36	33	31	30	25	26	23	25	-	120
Sodium	mg/L	21.0	21.2	23.9	25.9	25.6	21.2	21.1	17.5	21.5	16.7	-	-
Calcium	mg/L	38.8	36.1	43.5	39.8	53.1	35.7	34.4	34.7	42.9	32.3	-	-
Magnesium	mg/L	6.37	5.31	6.7	6.34	9.71	5.46	6.76	5.31	8.54	5.01	-	-
Potassium	mg/L	8.64	9.27	9.13	10.10	9.83	10.20	9.05	9.55	10.60	8.75	-	-
Sulphate	mg/L	19	8	26	6	42	6	11	7	29	9	-	-
Ammonia as N	mg/L	3.44	3.98	3.29	2.70	4.69	2.85	4.84	3.10	4.20	0.9	-	-
Un-ionized Ammonia	mg/L	0.0125	0.0015	-	-	-	-	-	-	-	-	0.02	0.019
Nitrate as N	mg/L	0.88	0.70	0.64	0.18	0.37	0.52	0.64	0.09	0.84	1.20	-	13
Nitrite as N	mg/L	< 0.03	<0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	-	0.06
Total Kjeldahl Nitrogen	mg/L	4.03	4.16	3.26	3.34	4.97	3.06	4.60	3.40	4.20	1.3	-	-
Phenolics	mg/L	< 0.001	<0.001	0.003	0.001	< 0.001	< 0.001	0.002	0.002	< 0.001	< 0.001	0.001	0.004
Dissolved Organic Carbon	mg/L	8	7	7	7	10	6	6	8.0	6	5	-	-
Chemical Oxygen Demand	mg/L	20	31	26	33	26	18	15	36	34	17	-	-
Biological Oxygen Demand	mg/L	< 4	5	22	< 4	< 4	4	< 4	4	< 4	5	-	-
Iron	mg/L	2.66	36.3	7.88	48.4	3.5	7.1	7.04	35.5	0.74	2.84	0.30	0.30
Manganese	mg/L	4.65	6.97	6.52	4.85	6.39	3.09	5.50	7.28	3.83	2.62	-	-
Phosphorus, total	mg/L	0.004	0.044	0.003	0.030	0.008	0.019	0.004	0.039	< 0.003	0.016	0.03	-
Orthophosphate	mg/L	< 0.03	-	< 0.03	-	< 0.03	< 0.03	< 0.03	-	-	< 0.03	-	-
Total Suspended Solids	mg/L	3	36	119	117	9	38	5	420	< 2	88	-	-
Bicarbonate	mg/L	-	-	-	-	-	-	-	-	-	-	-	-
Turbidity	NTU	-	-	-	-	-	-	-	-	-	-	-	-
Anion Sum	-	-	-	-	-	-	-	-	-	-	-	-	-
Cation Sum	-	-	-	-	-	-	-	-	-	-	-	-	-
Ion Balance	%	-	-	-	-	-	-	-	-	-	-	-	-
Silver	mg/L	< 0.00005	<0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	0.0001	0.00025
Aluminum	mg/L	0.005	0.006	0.003	0.007	0.006	0.005	0.007	0.007	0.007	0.004	0.075	0.1
Antimony	mg/L	< 0.0009	<0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	0.02	-
Arsenic	mg/L	< 0.0002	0.0013	0.0003	0.0016	0.0003	0.0003	0.0003	0.0008	< 0.0002	< 0.0002	0.10	0.01
Barium	mg/L	0.107	0.209	0.11	0.143	0.107	0.091	0.104	0.188	0.085	0.0757	-	-
Beryllium	mg/L	0.00009	0.000071	0.000011	0.000057	0.000014	0.000022	0.000015	0.000052	< 0.000007	0.000008	1.1	-
Bismuth	mg/L	< 0.00001	<0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	-	-
Boron	mg/L	0.336	0.197	0.347	0.197	0.468	0.187	0.274	0.203	0.364	0.213	0.20	1.50
Cadmium	mg/L	0.000022	0.000052	0.00003	0.000042	0.000032	0.000026	0.000042	0.000044	0.000028	0.000011	0.00020	0.00026
Chromium	mg/L	0.00062	0.00161	0.00085	0.00186	0.00072	0.0007	0.00064	0.00142	0.00868	0.00047	0.0089	0.001
Cobalt	mg/L	0.0145	0.0335	0.0202	0.0195	0.0156	0.0087	0.0166	0.0324	0.001	0.00734	0.0009	-
Copper	mg/L	0.002	0.004	0.0039	0.003	0.002	0.004	0.002	0.002	0.002	0.001	0.005	0.004
Molybdenum	mg/L	0.00022	0.00068	0.00018	0.00074	0.00024	0.00032	< 0.0004	0.0005	< 0.0004	< 0.0004	0.04	0.073
Nickel	mg/L	0.0018	0.0027	0.0027	0.0024	0.0026	0.0017	0.0025	0.0021	0.0021	0.0013	0.025	0.15
Phosphate as P	mg/L	-	-	-	-	-	-	-	-	-	-	-	-
Lead	mg/L	< 0.00009	0.00086	< 0.00009	0.00053	< 0.00009	< 0.00009	< 0.00009	0.00052	< 0.00009	< 0.00009	0.005	0.007
Selenium	mg/L	0.00007	0.00007	0.00007	0.00025	0.00017	0.00016	0.00013	0.00019	0.00014	< 0.00004	0.1	0.001
Silicon	mg/L	4.88	7.01	6.09	6.85	5.86	5.16	5.57	5.45	5.60	5.36	-	-
Tin	mg/L	< 0.00006	0.0002	0.00015	0.00007	0.00012	< 0.00006	0.00007	0.00015	0.00009	0.00009	-	-
Strontium	mg/L	0.252	0.224	0.296	0.249	0.358	0.237	0.215	0.227	0.290	0.199	-	-
Titanium	mg/L	0.001	0.014	0.00063	0.005	0.001	0.001	0.0007	0.009	0.002	0.005	-	-
Uranium	mg/L	0.000404	0.000927	0.000443	0.000623	0.000652	0.000309	0.000427	0.000427	0.000316	0.000151	0.005	0.015
Vanadium	mg/L	0.00027	0.00164	0.00059	0.00184	0.00043	0.00037	0.00061	0.00116	0.00020	0.00015	0.006	-
Zinc	mg/L	< 0.002	0.004	0.006	0.004	0.002	0.004	< 0.002	0.004	0.002	0.003	0.03	0.093
Dissolved Mercury	mg/L	-	-	-	-	-	-	-	-	-	-	0.0002	0.000026
Field Measurements													
Temperature	oC	13.25	10	8.9	7.8	11.3	11.7	8.6	11.4	10.3	3.8	-	-
pH	pH Units	13.05	6.58	16.14	6.58	6.01	6.53	7.8	6.23	6.03	8.31	-	-
Conductivity	µS/cm	301	310	300.6	233.5	365.2	277.9	271.4	295.2	367.5	329.6	-	-
Oxidation Reduction Potential	mV	71.5	69.3	-15.1	118.9	73.4	99.5	-20.1	319	108.8	217.5	-	-
Dissolved Oxygen	mg/L	8.06	3.54	7.05	4.12	5.35	1.22	5.26	6.07	39	0.26	-	-

Notes:

- PWQO Provincial Water Quality Objective
- CWQG Canadian Water Quality Guidelines
- BOLD** Exceeds PWQO
- UNDERLINED Exceeds CWQG
- No data available
- Units All Units in mg/L Unless Otherwise Noted.

TABLE 23
Groundwater Duplicate Data
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	RDL	PQL	7-May-25						26-Sep-25					
				BH11	GW DUP 1	Relative Percent Difference (%)	BH8-I	GW DUP 2	Relative Percent Difference (%)	BH11	GW DUP 1	Relative Percent Difference (%)	BH4-II	GW DUP 2	Relative Percent Difference (%)
pH Lab	pH Units	0.05	0.25	6.40	6.31	1.42	7.16	7.12	0.56	6.26	6.27	0.16	7.29	7.35	0.82
Conductivity	µS/cm	2	10	83	83	0.00	423	414	2.15	100	101	1.0	706	707	0.14
Hardness	mg/L	0.05	0.25	27.4	25.8	6.02	132	133	0.75	31.3	31.2	0.32	330	323	2.14
Total Dissolved Solids	mg/L	30	150	91	89	2.22	254	263	3.48	77	49	44.44	440	429	2.53
Alkalinity	mg/L	2	10	8	9	11.76	145	142	2.09	9	8	11.76	280	284	1.42
Chloride	mg/L	1	5	15	17	12.50	18	19	5.41	22	23	4.44	6	6	0.00
Sodium	mg/L	0.01	0.05	4.04	3.87	4.30	14.4	14.4	0.00	4.95	4.83	2.45	12.1	11.9	1.67
Calcium	mg/L	0.01	0.05	9.13	8.61	5.86	42.0	42.6	1.42	10.2	10.1	0.99	108	106	1.87
Magnesium	mg/L	0.001	0.005	1.120	1.050	6.45	6.53	6.56	0.46	1.43	1.46	2.08	14.7	14.3	2.76
Potassium	mg/L	0.009	0.045	1.240	1.170	5.81	8.68	8.87	2.17	1.54	1.49	3.30	11.0	11.0	0.00
Sulphate	mg/L	2	10	3	3	0.00	35	36	2.82	4	4	0.00	85	83	2.38
Ammonia	mg/L	0.1	0.5	< 0.1	< 0.1	NC	2.20	2.10	4.65	< 0.1	< 0.1	NC	0.4	0.4	0.00
Nitrate as N	mg/L	0.06	0.3	0.26	0.28	7.41	1.16	1.16	0.00	0.17	0.19	11.11	4.17	3.85	7.98
Nitrite as N	mg/L	0.03	0.15	< 0.03	< 0.03	NC	0.38	0.35	8.22	< 0.03	< 0.03	NC	< 0.03	< 0.03	NC
Total Kjeldahl Nitrogen	mg/L	0.5	2.5	< 0.5	< 0.5	NC	2.10	2.20	4.65	< 0.5	< 0.5	NC	0.7	0.7	0.00
Phenolics	mg/L	0.002	0.01	< 0.002	< 0.002	NC	< 0.002	< 0.002	NC	< 0.002	< 0.002	NC	< 0.002	< 0.002	NC
Dissolved Organic Carbon	mg/L	1	5	1	1	0.00	5	5	0.00	2	2	0.00	10	10	0.00
Chemical Oxygen Demand	mg/L	8	40	8	< 8	NC	26	19	31.11	< 8	< 8	NC	27	27	0.00
Iron	mg/L	0.007	0.035	0.121	0.166	31.36	0.013	0.012	8.00	0.024	0.023	4.26	0.020	0.023	13.95
Manganese	mg/L	0.00001	0.00005	0.0306	0.0316	3.22	1.53	1.53	0.00	0.0210	0.0205	2.41	0.289	0.289	0.00
Phosphorus	mg/L	0.03	0.15	0.34	0.12	95.65	0.41	0.40	2.47	0.60	0.36	50.00	< 0.03	< 0.03	NC
Turbidity	NTU	0.1	0.5	29	17	52.17	8	39	129.81	18	16	11.76	8.8	7.4	17.28
Total Suspended Solids	mg/L	2	10	373	272	31.32	158	159	0.63	183	205	11.34	8	8	0.00
BOD	mg/L	2	10	< 4	< 4	NC	9	8	11.76	< 4	< 4	NC	< 4	< 4	NC
Silver	mg/L	0.00005	0.00025	< 0.00005	< 0.00005	NC	< 0.00005	< 0.00005	NC	< 0.00005	< 0.00005	NC	< 0.00005	< 0.00005	NC
Aluminum	mg/L	0.001	0.005	0.094	0.121	25.12	0.021	0.022	4.65	0.025	0.025	0.00	0.020	0.020	0.00
Antimony	mg/L	0.0009	0.0045	< 0.0009	< 0.0009	NC	< 0.0009	< 0.0009	NC	< 0.0009	< 0.0009	NC	< 0.0009	< 0.0009	NC
Arsenic	mg/L	0.0002	0.001	< 0.0002	< 0.0002	NC	0.0003	0.0003	0.00	< 0.0002	< 0.0002	NC	0.0005	0.0004	22.22
Barium	mg/L	0.00008	0.0004	0.0233	0.02390	2.54	0.144	0.140	2.82	0.0244	0.0237	2.91	0.105	0.105	0.00
Beryllium	mg/L	0.000007	0.000035	0.000052	0.000057	9.17	0.000011	0.000009	20.00	0.000055	0.000059	7.02	0.000018	0.000019	5.41
Bismuth	mg/L	0.00001	0.00005	< 0.00001	< 0.00001	NC	< 0.00001	< 0.00001	NC	< 0.00001	< 0.00001	NC	< 0.00001	< 0.00001	NC
Boron	mg/L	0.002	0.01	0.006	0.008	28.57	0.218	0.220	0.91	0.005	0.004	22.22	0.511	0.506	0.98
Cadmium	mg/L	0.000003	0.000015	0.000015	0.000027	57.14	0.000050	0.000061	19.82	0.000029	0.000028	3.51	0.000026	0.000038	37.50
Chromium	mg/L	0.00008	0.0004	0.00025	0.00026	3.16	0.00046	0.00047	0.86	0.00009	0.00012	28.57	0.00061	0.00051	17.86
Cobalt	mg/L	0.000004	0.00002	0.000330	0.000320	3.08	0.000320	0.000400	22.22	0.000047	0.000055	15.69	0.00125	0.00123	1.61
Copper	mg/L	0.001	0.005	< 0.001	< 0.001	NC	0.003	0.003	0.00	< 0.001	< 0.001	NC	0.008	0.008	0.00
Molybdenum	mg/L	0.0004	0.002	< 0.0004	< 0.0004	NC	< 0.0004	< 0.0004	NC	< 0.0004	< 0.0004	NC	0.0011	0.0012	8.70
Nickel	mg/L	0.0001	0.0005	0.0001	0.0002	66.67	0.0006	0.0006	0.00	0.0002	0.0002	0.00	0.0019	0.0020	5.13
Phosphate	mg/L	0.03	0.15	-	-	-	-	-	-	-	-	-	-	-	-
Lead	mg/L	0.00009	0.00045	< 0.00009	0.00011	NC	< 0.00009	< 0.00009	NC	< 0.00009	< 0.00009	NC	< 0.00009	< 0.00009	NC
Selenium	mg/L	0.00004	0.0002	< 0.00004	< 0.00004	NC	0.00011	0.00011	0.00	< 0.00004	< 0.00004	NC	0.00016	0.00019	17.14
Tin	mg/L	0.00006	0.0003	< 0.00006	< 0.00006	NC	< 0.00006	< 0.00006	NC	< 0.00006	< 0.00006	NC	0.00007	0.00007	0.00
Strontium	mg/L	0.00008	0.0004	0.0967	0.0965	0.21	0.265	0.269	1.50	0.106	0.105	0.95	0.412	0.409	0.73
Titanium	mg/L	0.0001	0.0005	0.0041	0.0056	30.93	0.0005	0.0005	0.00	0.0002	0.0002	0.00	0.0014	0.0007	66.67
Uranium	mg/L	0.000002	0.00001	0.000054	0.000058	7.14	0.000384	0.000376	2.11	0.000051	0.000045	12.50	0.00660	0.00674	2.10
Vanadium	mg/L	0.00001	0.00005	0.00017	0.00028	48.89	0.00016	0.00016	0.00	0.00008	0.00006	28.57	0.00037	0.00036	2.74
Zinc	mg/L	0.002	0.01	< 0.002	< 0.002	NC	< 0.002	< 0.002	NC	0.010	0.009	10.53	0.009	0.010	10.53

Notes:

NC

Not calculable due to one or more of the concentrations being quantified over the reasonable detection limit (RDL) or the practical quantification limit (PQL).

BOLD

Bolded and shaded entries indicates that the relative percent difference (RPD) exceeds the industry standard of 50%.

TABLE 24
Surface Water Duplicate Data
Chapman Waste Disposal Site
Magnetawan, Ontario

Parameter	Units	RDL	PQL	7-May-25			26-Sep-25		
				SW1	SW DUP	Relative Percent Difference (%)	SW1	SW DUP	Relative Percent Difference (%)
pH	pH Units	0.05	0.25	6.30	6.80	7.63	6.56	6.54	0.31
Electrical Conductivity	µS/cm	2	10	65	88	30.07	75	83	10.13
Total Hardness (as CaCO3) (Calculated)	mg/L	0.05	0.25	18.0	18.1	0.55	26.4	25.9	1.91
Total Dissolved Solids	mg/L	30	150	74	83	11.46	51	80	44.27
Alkalinity (as CaCO3)	mg/L	2	10	7	15	72.73	7	8	13.33
Chloride	mg/L	1	5	14	15	6.90	20	19	5.13
Sodium	mg/L	0.01	0.05	4.06	4.07	0.25	4.79	4.66	2.75
Calcium	mg/L	0.01	0.05	5.34	5.36	0.37	8.13	7.97	1.99
Magnesium	mg/L	0.001	0.005	1.14	1.15	0.87	1.49	1.45	2.72
Potassium	mg/L	0.009	0.045	0.477	0.483	1.25	1.08	1.07	0.93
Sulphate	mg/L	2	10	< 2	< 2	NC	4	4	0.00
Ammonia as N	mg/L	0.1	0.5	< 0.1	< 0.1	NC	< 0.1	< 0.1	NC
Nitrate as N	mg/L	0.06	0.3	< 0.06	0.06	NC	0.06	0.07	15.38
Nitrite as N	mg/L	0.03	0.15	< 0.03	< 0.03	NC	< 0.03	< 0.03	NC
Total Kjeldahl Nitrogen	mg/L	0.5	2.5	< 0.5	< 0.5	NC	< 0.5	< 0.5	NC
Phenols	mg/L	0.002	0.01	< 0.001	< 0.001	NC	< 0.001	< 0.001	NC
Dissolved Organic Carbon	mg/L	1	5	6	6	0.00	3	3	0.00
Chemical Oxygen Demand	mg/L	8	40	12	18	40.00	10	8	22.22
BOD (5)	mg/L	2	10	< 4	< 4	NC	< 4	< 4	NC
Iron	mg/L	0.007	0.035	0.295	0.292	1.02	0.258	0.247	4.36
Manganese	mg/L	0.00001	0.00005	0.0426	0.0447	4.81	0.0228	0.0239	4.71
Total Phosphorus	mg/L	0.003	0.015	0.004	0.006	40.00	0.010	0.013	26.09
Total Suspended Solids	mg/L	2	10	< 3	2	NC	27	37	31.25
Silver	mg/L	0.00005	0.00025	< 0.00005	< 0.00005	NC	< 0.00005	< 0.00005	NC
Aluminum-dissolved	mg/L	0.001	0.005	0.176	0.176	0.00	0.040	0.045	11.76
Antimony	mg/L	0.0009	0.0045	< 0.0009	< 0.0009	NC	< 0.0009	< 0.0009	NC
Arsenic	mg/L	0.0002	0.001	< 0.0002	< 0.0002	NC	< 0.0002	< 0.0002	NC
Barium	mg/L	0.00008	0.0004	0.0282	0.0273	3.24	0.0289	0.0287	0.69
Beryllium	mg/L	0.000007	0.000035	0.000031	0.000036	14.93	0.000032	0.000032	0.00
Bismuth	mg/L	0.00001	0.00005	< 0.00001	< 0.00001	NC	< 0.00001	< 0.00001	NC
Boron	mg/L	0.002	0.01	0.005	0.009	57.14	0.012	0.008	40.00
Cadmium	mg/L	0.000003	0.000015	0.000043	0.000046	6.74	0.000011	0.000019	53.33
Chromium	mg/L	0.00008	0.0004	0.00039	0.00032	19.72	0.00021	0.00023	9.09
Cobalt	mg/L	0.000004	0.00002	0.000758	0.000775	2.22	0.000312	0.000291	6.97
Copper	mg/L	0.001	0.005	0.001	< 0.001	NC	< 0.001	< 0.001	NC
Molybdenum	mg/L	0.0004	0.002	< 0.0004	< 0.0004	NC	< 0.0004	< 0.0004	NC
Nickel	mg/L	0.0001	0.0005	0.0008	0.0007	13.33	0.0003	0.0002	40.00
Ortho Phosphate as P	mg/L	0.03	0.15	-	-	NC	< 0.03	< 0.03	NC
Lead	mg/L	0.00009	0.00045	0.00022	0.00023	4.44	0.00027	0.00024	11.76
Selenium	mg/L	0.00004	0.0002	0.00007	0.00007	0.00	< 0.00004	< 0.00004	NC
Silicon	mg/L	0.02	0.1	-	-	-	4.99	5.06	1.39
Tin	mg/L	0.00006	0.0003	0.00007	< 0.00006	NC	< 0.00006	0.00007	NC
Strontium	mg/L	0.00008	0.0004	0.0633	0.0643	1.57	0.0904	0.0889	1.67
Titanium	mg/L	0.0001	0.0005	0.0015	0.0017	12.50	0.0021	0.0026	21.28
Uranium	mg/L	0.000002	0.00001	0.000016	0.000017	6.06	0.000033	0.000026	23.73
Vanadium	mg/L	0.00001	0.00005	0.00023	0.00020	13.95	0.00020	0.00019	5.13
Zinc	mg/L	0.002	0.01	0.009	0.010	10.53	0.003	0.003	0.00

Notes:

NC

Not calculable due to one or more of the concentrations being quantified over the reasonable detection limit (RDL) or the practical quantification limit (PQL).

BOLD

Bolded and shaded entries indicates that the relative percent difference (RPD) exceeds the industry standard of 50%.

APPENDIX V
Photoplates



BH1
(Fall 2025)



BH1
(Fall 2025)



BH2
(Fall 2025)



BH2
(Fall 2025)



BH3-II
(Fall 2025)



BH3-II
(Fall 2025)



BH4
(Fall 2025)



BH4-II
(Fall 2025)



**BH4 & BH4-II
(NEST)**



**BH5-II
(Spring 2025)**



BH5-II
(Fall 2025)



BH6-II
(Fall 2025)



BH6-II
(Fall 2025)



BH6-III
(Fall 2025)



BH6-III
(Fall 2025)



BH7-II
(Fall 2025)



BH7-II
(Fall 2025)



BH8-I
(Spring 2025)



BH8-I
(Spring 2025)



BH9-I
(Fall 2025)



BH9-I
(Fall 2025)



BH10-I
(Fall 2025)



BH10-I
(Fall 2025)



BH11
(Fall 2025)



BH11
(Fall 2025)



SW1
(Spring 2025)



SW1
(Spring 2025)



SW2
(Spring 2025)



SW2
(Spring 2025)



SW3
(Spring 2025)





SEEP
(Spring 2025)

APPENDIX VI
Laboratory Certificates of Analysis



FINAL REPORT

CA15928-MAY25 R

225335.010, Chapman Landfill SW

Prepared for

Pinchin Ltd

First Page

CLIENT DETAILS

Client Pinchin Ltd

Address 662 Falconbridge Road, Unit 3, Sudbury
Canada, P3A 4S4
Phone: 705-521-0560. Fax:

Contact Alana Valle
Telephone 705-521-0560
Facsimile
Email avalue@Pinchin.com
Project 225335.010, Chapman Landfill SW
Order Number
Samples Surface Water (5)

LABORATORY DETAILS

Project Specialist Brad Moore Hon. B.Sc
Laboratory SGS Canada Inc.
Address 185 Concession St., Lakefield ON, K0L 2H0

Telephone 705-652-2143
Facsimile 705-652-6365
Email brad.moore@sgs.com
SGS Reference CA15928-MAY25
Received 05/09/2025
Approved 05/20/2025
Report Number CA15928-MAY25 R
Date Reported 05/20/2025

COMMENTS

Temperature of Sample upon Receipt: 5 degrees C

Phos TR spk low due to sample matrix

SIGNATORIES

Brad Moore Hon. B.Sc




TABLE OF CONTENTS

First Page.....	1
Index.....	2
Results.....	3-5
Exceedance Summary.....	6
QC Summary.....	7-16
Legend.....	17
Annexes.....	18



FINAL REPORT

CA15928-MAY25 R

Client: Pinchin Ltd

Project: 225335.010, Chapman Landfill SW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

L1 = PWQQ_L / WATER / - - Table 2 - General - July 1999 PIBS 3303E

Sample Number	6	7	8	9	10
Sample Name	SW1	SW2	SW3	SEEP	SW DUP
Sample Matrix	Surface Water	Surface Water	Surface Water	Surface Water	Surface Water
Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

Parameter	Units	RL	L1	Result	Result	Result	Result	Result
General Chemistry								
Biochemical Oxygen Demand (BOD5)	mg/L	2		< 4 †	< 4 †	< 4 †	< 4 †	< 4 †
Prep BOD	Prep	no		45786	45786	45786	45786	45786
Total Suspended Solids	mg/L	2		< 3 †	< 2	2	< 2	2
Alkalinity	mg/L as CaCO3	2		7	15	76	154	15
Conductivity	uS/cm	2		65	91	249	437	88
Total Dissolved Solids	mg/L	30		74	60	154	254	83
Chemical Oxygen Demand	mg/L	8		12	< 8	15	34	18
Colour	TCU	3		49	24	22	10	49
Total Kjeldahl Nitrogen	as N mg/L	0.5		< 0.5	< 0.5	1.6	4.2	< 0.5
Ammonia+Ammonium (N)	as N mg/L	0.1		< 0.1	< 0.1	1.6	4.2	< 0.1
Total Reactive Phosphorous (o-phosphate as P)	mg/L	0.03		< 0.03	< 0.03	< 0.03	< 0.03	< 0.03
Dissolved Organic Carbon	mg/L	1		6	5	5	6	6

Metals and Inorganics

Sulphate	mg/L	2		< 2	10	23	29	< 2
Nitrite (as N)	as N mg/L	0.03		< 0.03	< 0.03	< 0.03	< 0.03	< 0.03
Nitrate (as N)	as N mg/L	0.06		< 0.06	0.34	1.02	0.84	0.06
Hardness	mg/L as CaCO3	0.05		18.0	29.8	81.6	142	18.1
Silver (total)	mg/L	0.00005	0.0001	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005
Aluminum (0.2µm)	mg/L	0.001	0.015 0.075	0.176	0.079	0.016	0.007	0.176
Arsenic (total)	mg/L	0.0002	0.005	< 0.0002	< 0.0002	0.0002	< 0.0002	< 0.0002



FINAL REPORT

CA15928-MAY25 R

Client: Pinchin Ltd

Project: 225335.010, Chapman Landfill SW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

L1 = PWQO_L / WATER / - - Table 2 - General - July 1999 PIBS 3303E

Sample Number	6	7	8	9	10
Sample Name	SW1	SW2	SW3	SEEP	SW DUP
Sample Matrix	Surface Water	Surface Water	Surface Water	Surface Water	Surface Water
Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

Parameter	Units	RL	L1	Result	Result	Result	Result	Result
Metals and Inorganics (continued)								
Barium (total)	mg/L	0.00008		0.0282	0.0300	0.0438	0.0852	0.0273
Beryllium (total)	mg/L	0.000007	0.011 1.1	0.000031	0.000019	0.000007	< 0.000007	0.000036
Bismuth (total)	mg/L	0.00001		< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001
Boron (total)	mg/L	0.002	0.2	0.005	0.044	0.201	0.364	0.009
Calcium (total)	mg/L	0.01		5.34	8.91	24.8	42.9	5.36
Cadmium (total)	mg/L	0.000003	0.0001 0.0005	0.000043	0.000018	0.000017	0.000028	0.000046
Cobalt (total)	mg/L	0.000004	0.0009	0.000758	0.000140	0.00359	0.00868	0.000775
Chromium (total)	mg/L	0.00008		0.00039	0.00032	0.00037	0.00058	0.00032
Copper (total)	mg/L	0.001	0.001 0.005	0.001	< 0.001	0.002	0.002	< 0.001
Iron (total)	mg/L	0.007	0.3	0.295	0.087	1.49	0.735	0.292
Potassium (total)	mg/L	0.009		0.477	1.48	5.66	10.6	0.483
Magnesium (total)	mg/L	0.001		1.14	1.85	4.78	8.54	1.15
Manganese (total)	mg/L	0.00001		0.0426	0.0157	1.04	3.83	0.0447
Molybdenum (total)	mg/L	0.0004	0.04	< 0.0004	< 0.0004	< 0.0004	< 0.0004	< 0.0004
Sodium (total)	mg/L	0.01		4.06	4.48	11.4	21.5	4.07
Nickel (total)	mg/L	0.0001	0.025	0.0008	0.0005	0.0010	0.0021	0.0007
Lead (total)	mg/L	0.00009	0.005 0.02 0.025	0.00022	< 0.00009	< 0.00009	< 0.00009	0.00023
Phosphorus (total)	mg/L	0.003	0.01	0.004	0.003	< 0.003	< 0.003	0.006



FINAL REPORT

CA15928-MAY25 R

Client: Pinchin Ltd

Project: 225335.010, Chapman Landfill SW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

Sample Number	6	7	8	9	10
Sample Name	SW1	SW2	SW3	SEEP	SW DUP
Sample Matrix	Surface Water	Surface Water	Surface Water	Surface Water	Surface Water
Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

L1 = PWQQ_L / WATER / - - Table 2 - General - July 1999 PIBS 3303E

Parameter	Units	RL	L1	Result	Result	Result	Result	Result
Metals and Inorganics (continued)								
Antimony (total)	mg/L	0.0009	0.02	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009
Selenium (total)	mg/L	0.00004	0.1	0.00007	0.00006	0.00009	0.00014	0.00007
Silicon (total)	mg/L	0.02		2.76	3.02	4.50	5.60	2.80
Tin (total)	mg/L	0.00006		0.00007	< 0.00006	0.00007	0.00009	< 0.00006
Strontium (total)	mg/L	0.00008		0.0633	0.0682	0.165	0.290	0.0643
Titanium (total)	mg/L	0.0001		0.0015	0.0015	0.0004	0.0002	0.0017
Uranium (total)	mg/L	0.000002	0.005	0.000016	0.000036	0.000163	0.000316	0.000017
Vanadium (total)	mg/L	0.00001	0.006	0.00023	0.00019	0.00021	0.00020	0.00020
Zinc (total)	mg/L	0.002	0.02	0.009	0.004	0.003	0.002	0.010
Other (ORP)								
pH	No unit	0.05	0.1 8.6	6.30	6.63	7.25	7.75	6.80
Chloride	mg/L	1		14	10	13	23	15
Phenols								
4AAP-Phenolics	mg/L	0.001	0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	PWQO_L / WATER / - - Table 2 - General - July 1999 PIBS 3303E L1
-----------	--------	-------	--------	--

SW1

Aluminum (dissolved)	SM 3030/EPA 200.8	mg/L	0.176	0.015
pH	SM 4500	No unit	6.30	0.1

SW2

Aluminum (dissolved)	SM 3030/EPA 200.8	mg/L	0.079	0.075
----------------------	-------------------	------	-------	-------

SW3

Boron	SM 3030/EPA 200.8	mg/L	0.201	0.2
Cobalt	SM 3030/EPA 200.8	mg/L	0.00359	0.0009
Iron	SM 3030/EPA 200.8	mg/L	1.49	0.3

SEEP

Boron	SM 3030/EPA 200.8	mg/L	0.364	0.2
Cobalt	SM 3030/EPA 200.8	mg/L	0.00868	0.0009
Iron	SM 3030/EPA 200.8	mg/L	0.735	0.3

SW DUP

Aluminum (dissolved)	SM 3030/EPA 200.8	mg/L	0.176	0.075
----------------------	-------------------	------	-------	-------

QC SUMMARY

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-1ENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0244-MAY25	mg/L as CaCO3	2	< 2	3	20	102	80	120	NA		
Alkalinity	EWL0274-MAY25	mg/L as CaCO3	2	< 2	1	20	98	80	120	NA		

Ammonia by SFA

Method: SM 4500 | Internal ref.: ME-CA-1ENVISFA-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Ammonia+Ammonium (N)	SKA0132-MAY25	as N mg/L	0.1	<0.1	0	10	100	90	110	103	75	125
Ammonia+Ammonium (N)	SKA0150-MAY25	as N mg/L	0.1	<0.1	0	10	100	90	110	98	75	125



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO5017-MAY25	mg/L	1	<1	2	20	102	80	120	103	75	125
Sulphate	DIO5017-MAY25	mg/L	2	<2	2	20	100	80	120	93	75	125

Anions by IC

Method: EPA300/MA300-Ions1.3 | Internal ref.: ME-CA-IENVIIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Nitrite (as N)	DIO0304-MAY25	mg/L	0.03	<0.03	ND	20	100	90	110	103	75	125
Nitrate (as N)	DIO0304-MAY25	mg/L	0.06	<0.06	ND	20	103	90	110	101	75	125
Nitrite (as N)	DIO0305-MAY25	mg/L	0.03	<0.03	ND	20	99	90	110	102	75	125
Nitrate (as N)	DIO0305-MAY25	mg/L	0.06	<0.06	0	20	103	90	110	103	75	125
Nitrite (as N)	DIO0306-MAY25	mg/L	0.03	<0.03	ND	20	100	90	110	105	75	125
Nitrate (as N)	DIO0306-MAY25	mg/L	0.06	<0.06	ND	20	103	90	110	106	75	125



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Biochemical Oxygen Demand

Method: SM 5210 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Biochemical Oxygen Demand (BOD5)	BOD0018-MAY25	mg/L	2	< 2	4	30	109	70	130	88	70	130

Carbon by SFA

Method: SM 5310 | Internal ref.: ME-CA-IENVISFA-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Dissolved Organic Carbon	SKA0130-MAY25	mg/L	1	<1	1	20	98	90	110	93	75	125



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Chemical Oxygen Demand

Method: HACH 8000 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chemical Oxygen Demand	EWL0284-MAY25	mg/L	8	<8	4	20	100	80	120	104	75	125
Chemical Oxygen Demand	EWL0285-MAY25	mg/L	8	<8	ND	20	90	80	120	94	75	125
Chemical Oxygen Demand	EWL0288-MAY25	mg/L	8	<8	6	20	100	80	120	96	75	125

Colour

Method: SM 2120 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Colour	EWL0300-MAY25	TCU	3	< 3	0	10	100	80	120	NA		



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-ENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0244-MAY25	uS/cm	2	< 2	1	20	99	90	110	NA		



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Silver (total)	EMS0131-MAY25	mg/L	0.00005	<0.00005	ND	20	108	90	110	81	70	130
Aluminum (0.2µm)	EMS0131-MAY25	mg/L	0.001	<0.001	7	20	98	90	110	105	70	130
Arsenic (total)	EMS0131-MAY25	mg/L	0.0002	<0.0002	ND	20	100	90	110	108	70	130
Barium (total)	EMS0131-MAY25	mg/L	0.00008	<0.00008	ND	20	99	90	110	93	70	130
Beryllium (total)	EMS0131-MAY25	mg/L	0.000007	<0.000007	ND	20	93	90	110	94	70	130
Boron (total)	EMS0131-MAY25	mg/L	0.002	<0.002	14	20	106	90	110	94	70	130
Bismuth (total)	EMS0131-MAY25	mg/L	0.00001	<0.00001	ND	20	100	90	110	90	70	130
Calcium (total)	EMS0131-MAY25	mg/L	0.01	<0.01	2	20	102	90	110	108	70	130
Cadmium (total)	EMS0131-MAY25	mg/L	0.000003	<0.000003	ND	20	101	90	110	96	70	130
Cobalt (total)	EMS0131-MAY25	mg/L	0.000004	<0.000004	9	20	102	90	110	93	70	130
Chromium (total)	EMS0131-MAY25	mg/L	0.00008	<0.00008	ND	20	95	90	110	119	70	130
Copper (total)	EMS0131-MAY25	mg/L	0.001	<0.001	14	20	99	90	110	89	70	130
Iron (total)	EMS0131-MAY25	mg/L	0.007	<0.007	0	20	107	90	110	100	70	130
Potassium (total)	EMS0131-MAY25	mg/L	0.009	<0.009	6	20	101	90	110	88	70	130
Magnesium (total)	EMS0131-MAY25	mg/L	0.001	<0.001	19	20	104	90	110	114	70	130
Manganese (total)	EMS0131-MAY25	mg/L	0.00001	<0.00001	8	20	98	90	110	96	70	130
Molybdenum (total)	EMS0131-MAY25	mg/L	0.0004	<0.0004	ND	20	102	90	110	105	70	130
Sodium (total)	EMS0131-MAY25	mg/L	0.01	<0.01	8	20	102	90	110	98	70	130
Nickel (total)	EMS0131-MAY25	mg/L	0.0001	<0.0001	5	20	97	90	110	86	70	130
Lead (total)	EMS0131-MAY25	mg/L	0.00009	<0.00009	ND	20	97	90	110	91	70	130



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Phosphorus (total)	EMS0131-MAY25	mg/L	0.003	<0.003	ND	20	103	90	110	NV	70	130
Antimony (total)	EMS0131-MAY25	mg/L	0.0009	<0.0009	ND	20	100	90	110	107	70	130
Selenium (total)	EMS0131-MAY25	mg/L	0.00004	<0.00004	ND	20	104	90	110	103	70	130
Silicon (total)	EMS0131-MAY25	mg/L	0.02	<0.02	ND	20	97	90	110	NV	70	130
Tin (total)	EMS0131-MAY25	mg/L	0.00006	<0.00006	ND	20	104	90	110	NV	70	130
Strontium (total)	EMS0131-MAY25	mg/L	0.00008	<0.00008	ND	20	97	90	110	88	70	130
Titanium (total)	EMS0131-MAY25	mg/L	0.0001	<0.0001	ND	20	107	90	110	NV	70	130
Uranium (total)	EMS0131-MAY25	mg/L	0.000002	<0.000002	6	20	99	90	110	89	70	130
Vanadium (total)	EMS0131-MAY25	mg/L	0.00001	<0.00001	ND	20	96	90	110	103	70	130
Zinc (total)	EMS0131-MAY25	mg/L	0.002	<0.002	3	20	102	90	110	94	70	130

pH

Method: SM 4500 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0244-MAY25	No unit	0.05	NA	0		100			NA		



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Phenols by SFA

Method: SM 5530B-D | Internal ref.: ME-CA-IENVISFA-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
4AAP-Phenolics	SKA0129-MAY25	mg/L	0.001	<0.001	ND	10	98	80	120	98	75	125

Reactive Phosphorus by SFA

Method: SM 4500-P F | Internal ref.: ME-CA-IENVISFA-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Reactive Phosphorous (o-phosphate as P)	SKA0116-MAY25	mg/L	0.03	<0.03	ND	10	96	90	110	88	75	125
Total Reactive Phosphorous (o-phosphate as P)	SKA0125-MAY25	mg/L	0.03	<0.03	ND	10	95	90	110	74	75	125



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Solids Analysis

Method: SM 2540C | Internal ref.: ME-CA-IENVIEWL-LAK-AN-005

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Dissolved Solids	EWL0262-MAY25	mg/L	30	<30	8	20	94	80	120	NA		
Total Dissolved Solids	EWL0275-MAY25	mg/L	30	<30	0	20	97	80	120	NA		

Suspended Solids

Method: SM 2540D | Internal ref.: ME-CA-IENVIEWL-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Suspended Solids	EWL0295-MAY25	mg/L	2	< 2	3	10	95	90	110	NA		
Total Suspended Solids	EWL0325-MAY25	mg/L	2	< 2	3	10	100	90	110	NA		



FINAL REPORT

CA15928-MAY25 R

QC SUMMARY

Total Nitrogen

Method: SM 4500-N C/4500-NO3- F | Internal ref.: ME-CA-IENVISFA-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Kjeldahl Nitrogen	SKA0131-MAY25	as N mg/L	0.5	<0.5	4	10	96	90	110	92	75	125
Total Kjeldahl Nitrogen	SKA0151-MAY25	as N mg/L	0.5	<0.5	1	10	98	90	110	98	75	125

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND

FOOTNOTES

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY (General)

SGS Environmental Services - Lakefield: 185 Concession St., Lakefield, ON K0L 2H0 Phone: 705-652-2000 Toll Free: 877-747-7658 Fax: 705-652-6365 Web: www.ca.sgs.com (4)
 SGS Environmental Services - London: 657 Consortium Court, London, ON, N6E 2S8 Phone: 519-672-4500 Toll Free: 877-848-8060 Fax: 519-672-0361 Web: www.ca.sgs.com (4)

Laboratory Information Section

Received Date (mm/dd/yyyy): MAY 09 2025LAB LIMS #: CA-15928-May 25 NP

Received Time (After Hours Only): _____

Temperature Upon Receipt (°C): 5X3

Billing & Reporting Information

Invoice/Receipt to (3):	Company:	Pinchin	Quote #:	2023 544
	Attention:	Alana Valle	Attached Parameter List:	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
	Address:	662 Falconbridge Rd, Unit 3 Sudbury, Ontario P3A 4S4	Turnaround Time	
	Email:	avalle@pinchin.com	Is *Rush Turnaround Time Required?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Project Name/Number:		225335.010-Chapman Landfill SW	P.O. #:	
				Specify: _____
				* Rush TA Requests Require Lab Approval

Client Information/Report To:

Client Lab #: _____

Company Name:	Pinchin Ltd.	Phone Number:	705.507.9479
Contact Name:	Alana Valle	Fax Number:	
Address:	662 Falconbridge Rd, Unit 3	E-mail:	
Copy to:	avalle@pinchin.com		

Sample Information

Sample Identifier	Date Sampled (mm/dd/yy)	Time Sampled	# of Bottles	Analysis Requested (please enter the analysis required below and check off which analysis applies to each sample)			
				Field Filtered	Field Temp (°C)	Field pH	SW Package
SW1	05/07/25	9:30	10	N	10.7	4.97	X
SW2	↓	↓	11	N	10.5	7.73	X
SW3	↓	↓	11	N	10.2	6.01	X
SEEP	↓	↓	11	N	10.3	6.03	X
SW DUP	↓	3:00	11	N	10.7	4.97	X

Sampled By {1}: (Name) <u>Julia Hayes + Katie Binaldi</u>	(Signature) <u>[Signature]</u>	Date:	<u>05/07/25</u>	(mm/dd/yy)
Relinquished by {2}: (Name) <u>Katie Binaldi</u>	(Signature) <u>[Signature]</u>	Date:	<u>05/08/25</u>	(mm/dd/yy)

Note: (1) Submission of samples to SGS is acknowledgement that you have been provided direction on sample collection/handling and transportation of samples. (2) Submission of samples to SGS is considered authorization for completion of work. Signatures may appear on this form or be retained on file in the contract, or in an alternative format (e.g. shipping documents). (3) Results may be sent by email to an unlimited number of addresses for no additional cost. Fax is available upon request. (4) Completion of work may require the subcontracting of samples between the London and Lakefield laboratories.

This document is issued by the Company under its General Conditions of Service accessible at http://www.sgs.com/terms_and_conditions.htm. (Printed copies are available upon request.) Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.

335376154803
RTN NP 10:15



FINAL REPORT

CA15932-MAY25 R1

225335.010, Chapman GW

Prepared for

Pinchin Ltd

First Page

CLIENT DETAILS

Client Pinchin Ltd

Address 662 Falconbridge Road, Unit 3, Sudbury
Canada, P3A 4S4
Phone: 705-521-0560. Fax:

Contact Alana Valle
Telephone 705-521-0560
Facsimile
Email avalue@Pinchin.com
Project 225335.010, Chapman GW
Order Number
Samples Ground Water (14)

LABORATORY DETAILS

Project Specialist Brad Moore Hon. B.Sc
Laboratory SGS Canada Inc.
Address 185 Concession St., Lakefield ON, K0L 2H0

Telephone 705-652-2143
Facsimile 705-652-6365
Email brad.moore@sgs.com
SGS Reference CA15932-MAY25
Received 05/09/2025
Approved 05/22/2025
Report Number CA15932-MAY25 R1
Date Reported 05/22/2025

COMMENTS

Temperature of Sample upon Receipt: 7 degrees C

Phos TR spike low due to sample matrix

COD dup RPD % high, results within RL

SIGNATORIES

Brad Moore Hon. B.Sc




TABLE OF CONTENTS

First Page.....	1
Index.....	2
Results.....	3-10
Exceedance Summary.....	11-12
QC Summary.....	13-23
Legend.....	24
Annexes.....	25



FINAL REPORT

CA15932-MAY25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

	Sample Number	7	8	9	10	11	12	13	14
	Sample Name	BH1	BH2	BH3-II	BH4	BH4-II	BH5-II	BH6-III	BH7-II
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result	Result	Result
Acid Rock Drainage												
pH Check <2	pH	0.05			1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

BTEX

Benzene	µg/L	0.5		1	---	---	---	---	< 0.5	---	---	---
Toluene	µg/L	0.5		60	---	---	---	---	< 0.5	---	---	---

General Chemistry

Biochemical Oxygen Demand (BOD5)	mg/L	2			4	< 4 †	< 4 †	< 4 †	< 4 †	< 4 †	< 4 †	< 4 †	
Prep BOD	Prep	no			45789	45789	45789	45789	45789	45789	45789	45789	
Total Suspended Solids	mg/L	2			< 2	30	1280	177	19	1040	161	400	
Alkalinity	mg/L as CaCO3	2		500	113	252	8	184	227	74	77	10	
Conductivity	uS/cm	2			371	626	30	579	701	285	402	40	
Total Dissolved Solids	mg/L	30		500	223	366	51	403	491	194	277	34	
Chemical Oxygen Demand	mg/L	8			< 8	26	< 8	26	29	26	12	12	
Turbidity	NTU	0.10		5	1	0.40	40	170	50	0.90	45	2.2	180
Total Kjeldahl Nitrogen	as N mg/L	0.5			3.5	6.4	< 0.5	< 0.5	< 0.5	< 0.5	< 0.5	< 0.5	
Ammonia+Ammonium (N)	as N mg/L	0.1			3.8	6.7	< 0.1	< 0.1	< 0.1	0.3	< 0.1	< 0.1	
Total Reactive Phosphorous (o-phosphate as P)	mg/L	0.03			< 0.03	< 0.03	0.17	< 0.03	< 0.03	< 0.03	< 0.03	0.25	
Dissolved Organic Carbon	mg/L	1		5	4	8	2	10	12	4	4	2	



FINAL REPORT

CA15932-MAY25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

	Sample Number	7	8	9	10	11	12	13	14
	Sample Name	BH1	BH2	BH3-II	BH4	BH4-II	BH5-II	BH6-III	BH7-II
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result	Result	Result
Metals and Inorganics												
Phosphorus (total)	mg/L	0.03			< 0.03	< 0.03	0.50	0.12	< 0.03	18.8	< 0.03	0.69
Sulphate	mg/L	2	500		14	43	15	91	83	56	120	48
Nitrite (as N)	as N mg/L	0.03		1	0.03	< 0.03	< 0.03	< 0.03	< 0.03	0.06	< 0.03	< 0.03
Nitrate (as N)	as N mg/L	0.06		10	3.77	0.26	0.13	6.81	14.3	1.43	1.47	0.07
Hardness (dissolved)	mg/L as CaCO3	0.05	100		108	239	5.0	272	328	115	169	7.6
Silver (dissolved)	mg/L	0.00005			< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005
Aluminum (dissolved)	mg/L	0.001			0.016	0.016	0.056	0.036	0.015	0.023	0.011	0.114
Arsenic (dissolved)	mg/L	0.0002		0.01	0.0004	0.0004	0.0004	0.0004	0.0005	< 0.0002	< 0.0002	< 0.0002
Barium (dissolved)	mg/L	0.00008		1	0.107	0.224	0.00357	0.0784	0.0944	0.0811	0.117	0.00995
Beryllium (dissolved)	mg/L	0.000007			0.000021	0.000008	0.000027	< 0.000007	0.000010	0.000011	0.000013	0.000049
Bismuth (dissolved)	mg/L	0.00001			< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001
Boron (dissolved)	mg/L	0.002		5	0.208	0.448	0.009	0.324	0.495	0.193	0.243	0.010
Calcium (dissolved)	mg/L	0.01			35.3	75.0	1.58	97.9	114	33.9	52.8	1.70
Cadmium (dissolved)	mg/L	0.000003		0.005	0.000068	0.000079	0.000009	0.000006	0.000016	0.000023	0.000011	0.000014
Cobalt (dissolved)	mg/L	0.000004			0.00236	0.00524	0.000120	0.000240	0.000953	0.000254	0.000298	0.000256
Chromium (dissolved)	mg/L	0.00008		0.05	0.00040	0.00080	0.00028	0.00055	0.00075	0.00028	0.00030	0.00036
Copper (dissolved)	mg/L	0.001	1		0.003	0.003	< 0.001	0.004	0.007	0.002	0.003	0.001
Iron (dissolved)	mg/L	0.007	0.3		< 0.007	5.37	0.021	0.043	0.009	0.008	0.012	0.129
Potassium (dissolved)	mg/L	0.009			10.3	11.1	0.408	6.80	9.69	3.65	4.62	1.04
Magnesium (dissolved)	mg/L	0.001			4.87	12.5	0.249	6.72	10.6	7.44	9.11	0.801
Manganese (dissolved)	mg/L	0.00001	0.05		2.47	3.65	0.00770	0.00728	0.147	0.170	0.0271	0.00606
Molybdenum (dissolved)	mg/L	0.0004			< 0.0004	0.0007	< 0.0004	0.0008	0.0009	< 0.0004	< 0.0004	< 0.0004



FINAL REPORT

CA15932-MAY25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

	Sample Number	7	8	9	10	11	12	13	14
	Sample Name	BH1	BH2	BH3-II	BH4	BH4-II	BH5-II	BH6-III	BH7-II
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result	Result	Result
Metals and Inorganics (continued)												
Sodium (dissolved)	mg/L	0.01	200	20	15.5	21.1	3.41	5.55	10.1	8.03	7.30	4.18
Nickel (dissolved)	mg/L	0.0001			0.0007	0.0017	0.0001	0.0005	0.0016	0.0011	0.0013	0.0005
Lead (dissolved)	mg/L	0.00009		0.01	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	0.00024
Antimony (dissolved)	mg/L	0.0009		0.006	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009
Selenium (dissolved)	mg/L	0.00004		0.05	0.00009	0.00012	< 0.00004	0.00012	0.00016	0.00007	0.00007	0.00007
Tin (dissolved)	mg/L	0.00006			< 0.00006	0.00007	0.00011	0.00010	0.00012	< 0.00006	0.00007	< 0.00006
Strontium (dissolved)	mg/L	0.00008			0.264	0.445	0.0169	0.336	0.408	0.215	0.320	0.0149
Titanium (dissolved)	mg/L	0.0001			0.0001	0.0005	0.0007	0.0022	0.0002	0.0003	0.0010	0.0058
Thallium (dissolved)	mg/L	0.000005			0.000110	< 0.000005	< 0.000005	0.000008	0.000026	0.000011	0.000008	0.000016
Uranium (dissolved)	mg/L	0.000002		0.02	0.000343	0.00358	0.000239	0.00273	0.00654	0.000187	0.000230	0.000149
Vanadium (dissolved)	mg/L	0.00001			0.00012	0.00107	0.00013	0.00035	0.00031	0.00019	0.00012	0.00033
Tungsten (dissolved)	mg/L	0.0002			< 0.0002	< 0.0002	< 0.0002	< 0.0002	0.0004	< 0.0002	0.0005	< 0.0002
Zinc (dissolved)	mg/L	0.002	5		< 0.002	< 0.002	0.002	< 0.002	< 0.002	< 0.002	0.004	0.008



FINAL REPORT

CA15932-MAY25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

	Sample Number	7	8	9	10	11	12	13	14
	Sample Name	BH1	BH2	BH3-II	BH4	BH4-II	BH5-II	BH6-III	BH7-II
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result	Result	Result
-----------	-------	----	----	----	--------	--------	--------	--------	--------	--------	--------	--------

Other (ORP)

pH	No unit	0.05	8.5		7.01	7.37	6.37	7.80	7.58	6.83	6.82	6.55
Chloride	mg/L	1	250		25	24	4	3	6	6	4	6
Mercury (total)	mg/L	0.00001			---	---	---	---	< 0.00001	---	---	---

Phenols

4AAP-Phenolics	mg/L	0.002			< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002
----------------	------	-------	--	--	---------	---------	---------	---------	---------	---------	---------	---------

VOCs

1,4-Dichlorobenzene	µg/L	0.5			---	---	---	---	< 0.5	---	---	---
Dichloromethane	µg/L	0.5			---	---	---	---	< 0.5	---	---	---
Vinyl Chloride	µg/L	0.2			---	---	---	---	< 0.2	---	---	---



FINAL REPORT

CA15932-MAY25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

Sample Number	15	16	17	18	19	20
Sample Name	BH8-I	BH9-I	BH10-I	BH11-I	GW DUP 1	GW DUP 2
Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result
Acid Rock Drainage										
pH Check <2	pH	0.05			1.00	1.00	1.00	1.00	1.00	1.00

General Chemistry

Biochemical Oxygen Demand (BOD5)	mg/L	2			9	< 4 †	< 4 †	< 4 †	< 4 †	8
Prep BOD	Prep	no			45789	45789	45789	45789	45789	45789
Total Suspended Solids	mg/L	2			158	441	207	373	272	159
Alkalinity	mg/L as CaCO3	2	500		145	106	36	8	9	142
Conductivity	uS/cm	2			423	598	168	83	83	414
Total Dissolved Solids	mg/L	30	500		254	394	149	91	89	263
Chemical Oxygen Demand	mg/L	8			26	30	14	8	< 8	19
Turbidity	NTU	0.10	5	1	8.3	310	50	29	17	39
Total Kjeldahl Nitrogen	as N mg/L	0.5			2.1	6.4	< 0.5	< 0.5	< 0.5	2.2
Ammonia+Ammonium (N)	as N mg/L	0.1			2.2	6.7	< 0.1	< 0.1	< 0.1	2.1
Total Reactive Phosphorous (o-phosphate as P)	mg/L	0.03			< 0.03	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03
Dissolved Organic Carbon	mg/L	1	5		5	7	4	1	1	5



FINAL REPORT

CA15932-MAY25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Sample Number	15	16	17	18	19	20
Sample Name	BH8-I	BH9-I	BH10-I	BH11-I	GW DUP 1	GW DUP 2
Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result
Metals and Inorganics										
Phosphorus (total)	mg/L	0.03			0.41	1.61	0.07	0.34	0.12	0.40
Sulphate	mg/L	2	500		35	180	31	3	3	36
Nitrite (as N)	as N mg/L	0.03		1	0.38	< 0.03	< 0.03	< 0.03	< 0.03	0.35
Nitrate (as N)	as N mg/L	0.06		10	1.16	< 0.06	3.51	0.26	0.28	1.16
Hardness (dissolved)	mg/L as CaCO3	0.05	100		132	173	60.6	27.4	25.8	133
Silver (dissolved)	mg/L	0.00005			< 0.00005	< 0.00005	0.00008	< 0.00005	< 0.00005	< 0.00005
Aluminum (dissolved)	mg/L	0.001			0.021	0.029	0.071	0.094	0.121	0.022
Arsenic (dissolved)	mg/L	0.0002		0.01	0.0003	0.0010	0.0008	< 0.0002	< 0.0002	0.0003
Barium (dissolved)	mg/L	0.00008		1	0.144	0.148	0.0548	0.0233	0.0239	0.140
Beryllium (dissolved)	mg/L	0.000007			0.000011	0.000021	< 0.000007	0.000052	0.000057	0.000009
Bismuth (dissolved)	mg/L	0.00001			< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001
Boron (dissolved)	mg/L	0.002		5	0.218	0.350	0.106	0.006	0.008	0.220
Calcium (dissolved)	mg/L	0.01			42.0	53.5	16.5	9.13	8.61	42.6
Cadmium (dissolved)	mg/L	0.000003		0.005	0.000050	0.000014	0.000007	0.000015	0.000027	0.000061
Cobalt (dissolved)	mg/L	0.000004			0.000463	0.0201	0.000134	0.000249	0.000257	0.000467
Chromium (dissolved)	mg/L	0.00008		0.05	0.00032	0.00081	0.00052	0.00033	0.00032	0.00040
Copper (dissolved)	mg/L	0.001	1		0.003	0.001	0.002	< 0.001	< 0.001	0.003
Iron (dissolved)	mg/L	0.007	0.3		0.013	19.4	0.062	0.121	0.166	0.012
Potassium (dissolved)	mg/L	0.009			8.68	9.80	3.60	1.24	1.17	8.87
Magnesium (dissolved)	mg/L	0.001			6.53	9.65	4.71	1.12	1.05	6.56
Manganese (dissolved)	mg/L	0.00001	0.05		1.53	5.59	0.00189	0.0306	0.0316	1.53
Molybdenum (dissolved)	mg/L	0.0004			< 0.0004	0.0005	< 0.0004	< 0.0004	< 0.0004	< 0.0004



FINAL REPORT

CA15932-MAY25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

Sample Number	15	16	17	18	19	20
Sample Name	BH8-I	BH9-I	BH10-I	BH11-I	GW DUP 1	GW DUP 2
Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result
Metals and Inorganics (continued)										
Sodium (dissolved)	mg/L	0.01	200	20	14.4	14.9	3.71	4.04	3.87	14.4
Nickel (dissolved)	mg/L	0.0001			0.0006	0.0023	0.0006	0.0001	0.0002	0.0006
Lead (dissolved)	mg/L	0.00009		0.01	< 0.00009	< 0.00009	< 0.00009	< 0.00009	0.00011	< 0.00009
Antimony (dissolved)	mg/L	0.0009		0.006	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009
Selenium (dissolved)	mg/L	0.00004		0.05	0.00011	0.00013	0.00004	< 0.00004	< 0.00004	0.00011
Tin (dissolved)	mg/L	0.00006			< 0.00006	< 0.00006	0.00020	< 0.00006	< 0.00006	< 0.00006
Strontium (dissolved)	mg/L	0.00008			0.265	0.349	0.108	0.0967	0.0965	0.269
Titanium (dissolved)	mg/L	0.0001			0.0005	0.0009	0.0021	0.0041	0.0056	0.0005
Thallium (dissolved)	mg/L	0.000005			0.000076	0.000040	0.000019	< 0.000005	0.000005	0.000078
Uranium (dissolved)	mg/L	0.000002		0.02	0.000384	0.001130	0.000536	0.000054	0.000058	0.000376
Vanadium (dissolved)	mg/L	0.00001			0.00016	0.00130	0.00047	0.00017	0.00028	0.00016
Tungsten (dissolved)	mg/L	0.0002			< 0.0002	< 0.0002	0.0020	< 0.0002	< 0.0002	< 0.0002
Zinc (dissolved)	mg/L	0.002	5		< 0.002	< 0.002	0.002	< 0.002	< 0.002	< 0.002



FINAL REPORT

CA15932-MAY25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Julia Hayes + Katie Rinaldi

MATRIX: WATER

	Sample Number	15	16	17	18	19	20
	Sample Name	BH8-I	BH9-I	BH10-I	BH11-I	GW DUP 1	GW DUP 2
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025	07/05/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result
Other (ORP)										
pH	No unit	0.05	8.5		7.16	6.86	6.85	6.40	6.31	7.12
Chloride	mg/L	1	250		18	9	1	15	17	19
Phenols										
4AAP-Phenolics	mg/L	0.002			< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03		ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03	
				L1	L2	L1	L2

BH1

Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	108	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	2.47	0.05	

BH2

Turbidity	SM 2130	NTU	40	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	239	100	
Iron (dissolved)	SM 3030/EPA 200.8	mg/L	5.37	0.3	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	3.65	0.05	
Sodium (dissolved)	SM 3030/EPA 200.8	mg/L	21.1		20
Dissolved Organic Carbon	SM 5310	mg/L	8	5	

BH3-II

Turbidity	SM 2130	NTU	170	5	1
-----------	---------	-----	-----	---	---

BH4

Turbidity	SM 2130	NTU	50	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	272	100	
Dissolved Organic Carbon	SM 5310	mg/L	10	5	

BH4-II

Nitrate as Nitrogen	EPA300/MA300-Ions1.3	as N mg/L	14.3		10
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	328	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	0.147	0.05	
Dissolved Organic Carbon	SM 5310	mg/L	12	5	

BH5-II

Turbidity	SM 2130	NTU	45	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	115	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	0.170	0.05	

BH6-III

Turbidity	SM 2130	NTU	2.2		1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	169	100	

BH7-II

Turbidity	SM 2130	NTU	180	5	1
-----------	---------	-----	-----	---	---

BH8-I

Turbidity	SM 2130	NTU	8.3	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	132	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	1.53	0.05	

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03	ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03
				L1	L2

BH8-I (continued)

BH9-I

Turbidity	SM 2130	NTU	310	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO ₃	173	100	
Iron (dissolved)	SM 3030/EPA 200.8	mg/L	19.4	0.3	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	5.59	0.05	
Dissolved Organic Carbon	SM 5310	mg/L	7	5	

BH10-I

Turbidity	SM 2130	NTU	50	5	1
-----------	---------	-----	----	---	---

BH11-I

Turbidity	SM 2130	NTU	29	5	1
-----------	---------	-----	----	---	---

GW DUP 1

Turbidity	SM 2130	NTU	17	5	1
-----------	---------	-----	----	---	---

GW DUP 2

Turbidity	SM 2130	NTU	39	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO ₃	133	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	1.53	0.05	



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-1ENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0244-MAY25	mg/L as CaCO3	2	< 2	3	20	102	80	120	NA		

Ammonia by SFA

Method: SM 4500 | Internal ref.: ME-CA-1ENVISFA-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Ammonia+Ammonium (N)	SKA0146-MAY25	as N mg/L	0.1	<0.1	ND	10	101	90	110	95	75	125
Ammonia+Ammonium (N)	SKA0160-MAY25	as N mg/L	0.1	<0.1	1	10	100	90	110	96	75	125



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO5016-MAY25	mg/L	1	<1	1	20	98	80	120	100	75	125
Sulphate	DIO5016-MAY25	mg/L	2	<2	ND	20	100	80	120	102	75	125

Anions by IC

Method: EPA300/MA300-Ions1.3 | Internal ref.: ME-CA-IENVIIC-LAK-AN-001

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Nitrite (as N)	DIO0285-MAY25	mg/L	0.03	<0.03	1	20	99	90	110	95	75	125
Nitrate (as N)	DIO0285-MAY25	mg/L	0.06	<0.06	0	20	102	90	110	96	75	125
Nitrite (as N)	DIO0286-MAY25	mg/L	0.03	<0.03	ND	20	100	90	110	101	75	125
Nitrate (as N)	DIO0286-MAY25	mg/L	0.06	<0.06	2	20	102	90	110	100	75	125
Nitrite (as N)	DIO0305-MAY25	mg/L	0.03	<0.03	ND	20	99	90	110	102	75	125
Nitrate (as N)	DIO0305-MAY25	mg/L	0.06	<0.06	0	20	103	90	110	103	75	125
Nitrite (as N)	DIO0313-MAY25	mg/L	0.03	<0.03	ND	20	99	90	110	103	75	125
Nitrate (as N)	DIO0313-MAY25	mg/L	0.06	<0.06	0	20	102	90	110	104	75	125



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Biochemical Oxygen Demand

Method: SM 5210 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Biochemical Oxygen Demand (BOD5)	BOD0022-MAY25	mg/L	2	< 2	11	30	97	70	130	125	70	130

Carbon by SFA

Method: SM 5310 | Internal ref.: ME-CA-IENVISFA-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Dissolved Organic Carbon	SKA0110-MAY25	mg/L	1	<1	1	20	100	90	110	99	75	125

Chemical Oxygen Demand

Method: HACH 8000 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chemical Oxygen Demand	EWL0248-MAY25	mg/L	8	<8	ND	20	96	80	120	92	75	125
Chemical Oxygen Demand	EWL0249-MAY25	mg/L	8	<8	29	20	98	80	120	90	75	125



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0244-MAY25	uS/cm	2	< 2	1	20	99	90	110	NA		

Mercury by CVAAS

Method: EPA 7471A/SM 3112B | Internal ref.: ME-CA-IENVISPE-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Mercury (total)	EHG0015-MAY25	mg/L	0.00001	< 0.00001	ND	20	112	80	120	120	70	130



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Uranium (dissolved)	EMS0117-MAY25	mg/L	0.000002	<0.000002	7	20	99	90	110	94	70	130
Vanadium (dissolved)	EMS0117-MAY25	mg/L	0.00001	<0.00001	1	20	101	90	110	93	70	130
Tungsten (dissolved)	EMS0117-MAY25	mg/L	0.0002	<0.0002	ND	20	100	90	110	NV	70	130
Zinc (dissolved)	EMS0117-MAY25	mg/L	0.002	<0.002	0	20	102	90	110	99	70	130
Silver (dissolved)	EMS0117-MAY25	mg/L	0.00005	<0.00005	ND	20	108	90	110	78	70	130
Aluminum (dissolved)	EMS0117-MAY25	mg/L	0.001	<0.001	0	20	98	90	110	80	70	130
Arsenic (dissolved)	EMS0117-MAY25	mg/L	0.0002	<0.0002	ND	20	100	90	110	96	70	130
Barium (dissolved)	EMS0117-MAY25	mg/L	0.00008	<0.00008	2	20	99	90	110	71	70	130
Beryllium (dissolved)	EMS0117-MAY25	mg/L	0.000007	<0.000007	ND	20	102	90	110	104	70	130
Boron (dissolved)	EMS0117-MAY25	mg/L	0.002	<0.002	2	20	106	90	110	94	70	130
Bismuth (dissolved)	EMS0117-MAY25	mg/L	0.00001	<0.00001	ND	20	100	90	110	90	70	130
Calcium (dissolved)	EMS0117-MAY25	mg/L	0.01	<0.01	0	20	105	90	110	101	70	130
Cadmium (dissolved)	EMS0117-MAY25	mg/L	0.000003	<0.000003	5	20	101	90	110	91	70	130
Cobalt (dissolved)	EMS0117-MAY25	mg/L	0.000004	<0.000004	2	20	104	90	110	95	70	130
Chromium (dissolved)	EMS0117-MAY25	mg/L	0.00008	<0.00008	15	20	95	90	110	94	70	130
Copper (dissolved)	EMS0117-MAY25	mg/L	0.001	<0.001	2	20	99	90	110	95	70	130
Iron (dissolved)	EMS0117-MAY25	mg/L	0.007	<0.007	ND	20	107	90	110	75	70	130
Potassium (dissolved)	EMS0117-MAY25	mg/L	0.009	<0.009	0	20	101	90	110	94	70	130
Magnesium (dissolved)	EMS0117-MAY25	mg/L	0.001	<0.001	0	20	104	90	110	99	70	130
Manganese (dissolved)	EMS0117-MAY25	mg/L	0.00001	<0.00001	4	20	98	90	110	86	70	130



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Molybdenum (dissolved)	EMS0117-MAY25	mg/L	0.0004	<0.0004	ND	20	102	90	110	88	70	130
Sodium (dissolved)	EMS0117-MAY25	mg/L	0.01	<0.01	1	20	102	90	110	97	70	130
Nickel (dissolved)	EMS0117-MAY25	mg/L	0.0001	<0.0001	0	20	98	90	110	84	70	130
Lead (dissolved)	EMS0117-MAY25	mg/L	0.00009	<0.00009	5	20	97	90	110	91	70	130
Antimony (dissolved)	EMS0117-MAY25	mg/L	0.0009	<0.0009	ND	20	95	90	110	94	70	130
Selenium (dissolved)	EMS0117-MAY25	mg/L	0.00004	<0.00004	ND	20	104	90	110	95	70	130
Tin (dissolved)	EMS0117-MAY25	mg/L	0.00006	<0.00006	11	20	104	90	110	NV	70	130
Strontium (dissolved)	EMS0117-MAY25	mg/L	0.00008	<0.00008	1	20	97	90	110	92	70	130
Titanium (dissolved)	EMS0117-MAY25	mg/L	0.0001	<0.0001	ND	20	107	90	110	NV	70	130
Thallium (dissolved)	EMS0117-MAY25	mg/L	0.000005	<0.000005	ND	20	98	90	110	92	70	130

pH

Method: SM 4500 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0244-MAY25	No unit	0.05	NA	0		100			NA		



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Phenols by SFA

Method: SM 5530B-D | Internal ref.: ME-CA-IENVISFA-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
4AAP-Phenolics	SKA0129-MAY25	mg/L	0.002	<0.002	ND	10	98	80	120	98	75	125

Phosphorus by SFA

Method: SM 4500-P J | Internal ref.: ME-CA-IENVISFA-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Phosphorus (total)	SKA0148-MAY25	mg/L	0.03	<0.03	0	10	98	90	110	94	75	125
Phosphorus (total)	SKA0161-MAY25	mg/L	0.03	<0.03	4	10	104	90	110	89	75	125
Phosphorus (total)	SKA0168-MAY25	mg/L	0.03	<0.03	5	10	100	90	110	92	75	125



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Reactive Phosphorus by SFA

Method: SM 4500-P F | Internal ref.: ME-CA-IENVISFA-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Reactive Phosphorous (o-phosphate as P)	SKA0116-MAY25	mg/L	0.03	<0.03	ND	10	96	90	110	88	75	125
Total Reactive Phosphorous (o-phosphate as P)	SKA0125-MAY25	mg/L	0.03	<0.03	ND	10	95	90	110	74	75	125

Solids Analysis

Method: SM 2540C | Internal ref.: ME-CA-IENVIEWL-LAK-AN-005

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Dissolved Solids	EWL0269-MAY25	mg/L	30	<30	1	20	94	80	120	NA		



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Suspended Solids

Method: SM 2540D | Internal ref.: ME-CA-IENVIEWL-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Suspended Solids	EWL0264-MAY25	mg/L	2	< 2	1	10	96	90	110	NA		
Total Suspended Solids	EWL0296-MAY25	mg/L	2	< 2	4	10	98	90	110	NA		
Total Suspended Solids	EWL0307-MAY25	mg/L	2	< 2	4	10	95	90	110	NA		

Total Nitrogen

Method: SM 4500-N C/4500-NO3- F | Internal ref.: ME-CA-IENVISFA-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Kjeldahl Nitrogen	SKA0149-MAY25	as N mg/L	0.5	<0.5	4	10	96	90	110	87	75 125	



FINAL REPORT

CA15932-MAY25 R1

QC SUMMARY

Turbidity

Method: SM 2130 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Turbidity	EWL0243-MAY25	NTU	0.10	< 0.10	0	10	100	90	110	NA		

Volatile Organics

Method: EPA 5030B/8260C | Internal ref.: ME-CA-IENVIGC-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
1,4-Dichlorobenzene	GCM0194-MAY25	µg/L	0.5	<0.5	ND	30	91	60	130	95	50	140
Benzene	GCM0194-MAY25	µg/L	0.5	<0.5	ND	30	88	60	130	94	50	140
Dichloromethane	GCM0194-MAY25	µg/L	0.5	<0.5	ND	30	88	60	130	93	50	140
Toluene	GCM0194-MAY25	µg/L	0.5	<0.5	ND	30	89	60	130	95	50	140
Vinyl Chloride	GCM0194-MAY25	µg/L	0.2	<0.2	ND	30	91	50	140	98	50	140

QC SUMMARY

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND

FOOTNOTES

- NSS** Insufficient sample for analysis.
- RL** Reporting Limit.
 - ↑ Reporting limit raised.
 - ↓ Reporting limit lowered.
- NA** The sample was not analysed for this analyte
- ND** Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY (General)

SGS Environmental Services - Lakefield: 185 Concession St., Lakefield, ON K0L 2H0 Phone: 705-652-2000 Toll Free: 877-747-7658 Fax: 705-652-6365 Web: www.ca.sgs.com (4)

SGS Environmental Services - London: 657 Consortium Court, London, ON, N6E 2S8 Phone: 519-672-4500 Toll Free: 877-848-8060 Fax: 519-672-0361 Web: www.ca.sgs.com (4)

Laboratory Information Section

Received Date (mm/dd/yyyy): MAY 09 2025

LAB LIMS #: A-15932-May 25 NP

Received Time (After Hours Only): _____

Temperature Upon Receipt (°C): 7, 7.8

Billing & Reporting Information

Invoice/Receipt to (3):

Company: Pinchin
 Attention: Alana Valle
 Address: 662 Falconbridge Rd, Unit 3
 Sudbury, Ontario
 P3A 4S4
 Email: avalle@pinchin.com

Quote #: 2023 544

Attached Parameter List: YES NO

Turnaround Time

Is *Rush Turnaround Time Required? YES NO

Specify: _____

* Rush TA Requests Require Lab Approval

Project Name/Number: 225335.010-Chapman Landfill GW

P.O. #: _____

Client Information/Report To:

Client Lab #: _____

Company Name: Pinchin Ltd.

Contact Name: Alana Valle

Address: 662 Falconbridge Rd, Unit 3

Copy to: avalle@pinchin.com

Phone Number: 705.507.9479

Fax Number: _____

E-mail: _____

Sample Information

Sample Identifier	Date Sampled (mm/dd/yy)	Time Sampled	# of Bottles	Analysis Requested (please enter the analysis required below and check off which analysis applies to each sample)					
				Field Filtered	Photo Temp (°C)	Electrode	GW Package	VOC's & Dissolved Hg	
BH1	05/07/25	9:30	11	Y			X		
BH2			11	Y			X		
BH3-II			11	Y			X		
BH4			11	Y			X		
BH4-II			14	Y			X	X	
BH5-II		3:00	11	Y			X		
BH6-II							X		
BH6-III	05/07/25	9:30	11	Y			X		
BH7-II			11	Y			X		
BH8-I			11	Y			X		
BH9-I			11	Y			X		
BH10-I			11	Y			X		
BH11-I			11	Y			X		
GW DUP 1			11	Y			X		
GW DUP 2		3:00	11	Y			X		

Sampled By {1}: (Name) Julia Hayes + Katie Binsidi (Signature) [Signature] Date: 05/07/25 (mm/dd/yy)

Relinquished by {2}: (Name) Katie Binsidi (Signature) [Signature] Date: 05/08/25 (mm/dd/yy)

Note: {1} Submission of samples to SGS is acknowledgement that you have been provided direction on sample collection/handling and transportation of samples. {2} Submission of samples to SGS is considered authorization for completion of work. Signatures may appear on this form or be retained on file in the contract, or in an alternative format (e.g. shipping documents). {3} Results may be sent by email to an unlimited number of addresses for no additional cost. Fax is available upon request. {4} Completion of work may require the subcontracting of samples between the London and Lakefield laboratories.

This document is issued by the Company under its General Conditions of Service accessible at http://www.sgs.com/terms_and_conditions.htm. (Printed copies are available upon request.) Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.



FINAL REPORT

CA15851-SEP25 R

225335.010, Chapman Landfill SW

Prepared for

Pinchin Ltd

First Page

CLIENT DETAILS

Client Pinchin Ltd

Address 662 Falconbridge Road, Unit 3, Sudbury
Canada, P3A 4S4
Phone: 705-521-0560. Fax:

Contact Alana Valle
Telephone 705-521-0560
Facsimile
Email avalue@Pinchin.com
Project 225335.010, Chapman Landfill SW
Order Number
Samples Surface Water (5)

LABORATORY DETAILS

Project Specialist Brad Moore Hon. B.Sc
Laboratory SGS Canada Inc.
Address 185 Concession St., Lakefield ON, K0L 2H0

Telephone 705-652-2143
Facsimile 705-652-6365
Email brad.moore@sgs.com
SGS Reference CA15851-SEP25
Received 09/27/2025
Approved 10/06/2025
Report Number CA15851-SEP25 R
Date Reported 10/06/2025

COMMENTS

Temperature of Sample upon Receipt: 3 degrees C

SIGNATORIES

Brad Moore Hon. B.Sc




TABLE OF CONTENTS

First Page.....	1
Index.....	2
Results.....	3-5
Exceedance Summary.....	6
QC Summary.....	7-15
Legend.....	16
Annexes.....	17



FINAL REPORT

CA15851-SEP25 R

Client: Pinchin Ltd

Project: 225335.010, Chapman Landfill SW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

L1 = PWQQ_L / WATER / - - Table 2 - General - July 1999 PIBS 3303E

Sample Number	6	7	8	9	10
Sample Name	SW1	SW2	SW3	SEEP	SW DUP
Sample Matrix	Surface Water	Surface Water	Surface Water	Surface Water	Surface Water
Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

Parameter	Units	RL	L1	Result	Result	Result	Result	Result
General Chemistry								
Biochemical Oxygen Demand (BOD5)	mg/L	2		< 4 †	< 4 †	< 4 †	5	< 4 †
Prep BOD	Prep	no		45930	45930	45930	45930	45930
Total Suspended Solids	mg/L	2		27	8	3	88	37
Alkalinity	mg/L as CaCO3	2		7	25	137	101	8
Conductivity	uS/cm	2		75	134	337	279	83
Total Dissolved Solids	mg/L	30		51	77	183	154	80
Chemical Oxygen Demand	mg/L	8		10	9	22	17	8
Colour	TCU	3		16	9	27	8	16
Total Kjeldahl Nitrogen	as N mg/L	0.5		< 0.5	< 0.5	4.0	1.3	< 0.5
Ammonia+Ammonium (N)	as N mg/L	0.1		< 0.1	< 0.1	3.9	0.9	< 0.1
Total Reactive Phosphorous (o-phosphate as P)	mg/L	0.03		< 0.03	< 0.03	< 0.03	< 0.03	< 0.03
Dissolved Organic Carbon	mg/L	1		3	3	7	5	3

Metals and Inorganics

Sulphate	mg/L	2		4	13	11	9	4
Nitrite (as N)	as N mg/L	0.03		< 0.03	< 0.03	< 0.03	< 0.03	< 0.03
Nitrate (as N)	as N mg/L	0.06		0.06	0.35	0.42	1.20	0.07
Hardness	mg/L as CaCO3	0.05		26.4	44.9	114	101	25.9
Silver (total)	mg/L	0.00005	0.0001	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005
Aluminum (0.2µm)	mg/L	0.001	0.075	0.040	0.016	0.006	0.004	0.045
Arsenic (total)	mg/L	0.0002	0.005	< 0.0002	< 0.0002	0.0004	< 0.0002	< 0.0002
Barium (total)	mg/L	0.00008		0.0289	0.0401	0.0874	0.0757	0.0287



FINAL REPORT

CA15851-SEP25 R

Client: Pinchin Ltd

Project: 225335.010, Chapman Landfill SW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

L1 = PWQQ_L / WATER / - - Table 2 - General - July 1999 PIBS 3303E

Sample Number	6	7	8	9	10
Sample Name	SW1	SW2	SW3	SEEP	SW DUP
Sample Matrix	Surface Water	Surface Water	Surface Water	Surface Water	Surface Water
Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

Parameter	Units	RL	L1	Result	Result	Result	Result	Result
Metals and Inorganics (continued)								
Beryllium (total)	mg/L	0.000007	0.011 1.1	0.000032	0.000007	0.000010	0.000008	0.000032
Bismuth (total)	mg/L	0.00001		< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001
Boron (total)	mg/L	0.002	0.2	0.012	0.057	0.207	0.213	0.008
Calcium (total)	mg/L	0.01		8.13	13.4	35.5	32.3	7.97
Cadmium (total)	mg/L	0.000003	0.0001 0.0005	0.000011	0.000009	0.000018	0.000011	0.000019
Cobalt (total)	mg/L	0.000004	0.0009	0.000312	0.000253	0.00947	0.00734	0.000291
Chromium (total)	mg/L	0.00008		0.00021	0.00022	0.00057	0.00047	0.00023
Copper (total)	mg/L	0.001	0.005	< 0.001	< 0.001	< 0.001	0.001	< 0.001
Iron (total)	mg/L	0.007	0.3	0.258	0.074	3.70	2.84	0.247
Potassium (total)	mg/L	0.009		1.08	2.34	9.18	8.75	1.07
Magnesium (total)	mg/L	0.001		1.49	2.77	6.16	5.01	1.45
Manganese (total)	mg/L	0.00001		0.0228	0.0628	3.60	2.62	0.0239
Molybdenum (total)	mg/L	0.0004	0.04	< 0.0004	< 0.0004	< 0.0004	< 0.0004	< 0.0004
Sodium (total)	mg/L	0.01		4.79	8.00	17.6	16.7	4.66
Nickel (total)	mg/L	0.0001	0.025	0.0003	0.0002	0.0016	0.0013	0.0002
Lead (total)	mg/L	0.00009	0.005 0.01 0.025	0.00027	< 0.00009	< 0.00009	< 0.00009	0.00024
Phosphorus (total)	mg/L	0.003	0.01	0.010	< 0.003	0.003	0.016	0.013
Antimony (total)	mg/L	0.0009	0.02	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009
Selenium (total)	mg/L	0.00004	0.1	< 0.00004	< 0.00004	< 0.00004	< 0.00004	< 0.00004



FINAL REPORT

CA15851-SEP25 R

Client: Pinchin Ltd

Project: 225335.010, Chapman Landfill SW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

Sample Number	6	7	8	9	10
Sample Name	SW1	SW2	SW3	SEEP	SW DUP
Sample Matrix	Surface Water	Surface Water	Surface Water	Surface Water	Surface Water
Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

L1 = PWQQ_L / WATER / - - Table 2 - General - July 1999 PIBS 3303E

Parameter	Units	RL	L1	Result	Result	Result	Result	Result
Metals and Inorganics (continued)								
Silicon (total)	mg/L	0.02		4.99	4.12	5.57	5.36	5.06
Tin (total)	mg/L	0.00006		< 0.00006	0.00007	0.00006	0.00009	0.00007
Strontium (total)	mg/L	0.00008		0.0904	0.100	0.209	0.199	0.0889
Titanium (total)	mg/L	0.0001		0.0021	0.0014	0.0004	0.0005	0.0026
Uranium (total)	mg/L	0.000002	0.005	0.000033	0.000026	0.000406	0.000151	0.000026
Vanadium (total)	mg/L	0.00001	0.006	0.00020	0.00019	0.00059	0.00015	0.00019
Zinc (total)	mg/L	0.002	0.02	0.003	0.003	0.003	0.003	0.003
Other (ORP)								
pH	No unit	0.05	8.6	6.56	7.22	7.13	7.02	6.54
Chloride	mg/L	1		20	20	27	25	19
Phenols								
4AAP-Phenolics	mg/L	0.001	0.001	< 0.001	< 0.001	< 0.001	< 0.001	< 0.001

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	PWQO_L / WATER / - - Table 2 - General - July 1999 PIBS 3303E L1
-----------	--------	-------	--------	--

SW3

Boron	SM 3030/EPA 200.8	mg/L	0.207	0.2
Cobalt	SM 3030/EPA 200.8	mg/L	0.00947	0.0009
Iron	SM 3030/EPA 200.8	mg/L	3.70	0.3

SEEP

Boron	SM 3030/EPA 200.8	mg/L	0.213	0.2
Cobalt	SM 3030/EPA 200.8	mg/L	0.00734	0.0009
Iron	SM 3030/EPA 200.8	mg/L	2.84	0.3
Phosphorus	SM 3030/EPA 200.8	mg/L	0.016	0.01

SW DUP

Phosphorus	SM 3030/EPA 200.8	mg/L	0.013	0.01
------------	-------------------	------	-------	------



FINAL REPORT

CA15851-SEP25 R

QC SUMMARY

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-1ENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0684-SEP25	mg/L as CaCO3	2	< 2	2	20	102	80	120	NA		

Ammonia by SFA

Method: SM 4500 | Internal ref.: ME-CA-1ENVISFA-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Ammonia+Ammonium (N)	SKA0011-OCT25	as N mg/L	0.1	<0.1	2	10	101	90	110	105	75	125

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO8001-OCT25	mg/L	1	<1	6	20	94	70	130	89	70	130
Nitrite (as N)	DIO8001-OCT25	mg/L	0.03	< 0.03	ND	20	102	80	120	101	75	125
Sulphate	DIO8001-OCT25	mg/L	2	<2	2	20	95	80	120	100	75	125

Biochemical Oxygen Demand

Method: SM 5210 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Biochemical Oxygen Demand (BOD5)	BOD0061-SEP25	mg/L	2	< 2	7	30	105	70	130	81	70	130



FINAL REPORT

CA15851-SEP25 R

QC SUMMARY

Carbon by SFA

Method: SM 5310 | Internal ref.: ME-CA-IENVISFA-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Dissolved Organic Carbon	SKA0001-OCT25	mg/L	1	<1	0	20	103	90	110	97	75	125

Chemical Oxygen Demand

Method: HACH 8000 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chemical Oxygen Demand	EWL0018-OCT25	mg/L	8	<8	3	20	102	80	120	114	75	125
Chemical Oxygen Demand	EWL0698-SEP25	mg/L	8	<8	ND	20	98	80	120	105	75	125
Chemical Oxygen Demand	EWL0699-SEP25	mg/L	8	<8	8	20	90	80	120	104	75	125



FINAL REPORT

CA15851-SEP25 R

QC SUMMARY

Colour

Method: SM 2120 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Colour	EWL0058-OCT25	TCU	3	< 3	ND	10	100	80	120	NA		

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0684-SEP25	uS/cm	2	< 2	1	10	98	90	110	NA		



FINAL REPORT

CA15851-SEP25 R

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Cadmium (total)	EMS0002-OCT25	mg/L	0.000003	<0.000003	ND	20	102	90	110	89	70	130
Silver (total)	EMS0307-SEP25	mg/L	0.00005	<0.00005	ND	20	104	90	110	NV	70	130
Aluminum (0.2µm)	EMS0307-SEP25	mg/L	0.001	<0.001	2	20	108	90	110	90	70	130
Arsenic (total)	EMS0307-SEP25	mg/L	0.0002	<0.0002	ND	20	103	90	110	90	70	130
Barium (total)	EMS0307-SEP25	mg/L	0.00008	<0.00008	0	20	106	90	110	98	70	130
Beryllium (total)	EMS0307-SEP25	mg/L	0.000007	<0.000007	ND	20	104	90	110	91	70	130
Boron (total)	EMS0307-SEP25	mg/L	0.002	<0.002	6	20	99	90	110	100	70	130
Bismuth (total)	EMS0307-SEP25	mg/L	0.00001	<0.00001	ND	20	106	90	110	100	70	130
Calcium (total)	EMS0307-SEP25	mg/L	0.01	<0.01	2	20	101	90	110	76	70	130
Cadmium (total)	EMS0307-SEP25	mg/L	0.000003	<0.000003	ND	20	102	90	110	79	70	130
Cobalt (total)	EMS0307-SEP25	mg/L	0.000004	<0.000004	ND	20	105	90	110	92	70	130
Chromium (total)	EMS0307-SEP25	mg/L	0.00008	<0.00008	ND	20	104	90	110	83	70	130
Copper (total)	EMS0307-SEP25	mg/L	0.001	<0.001	7	20	104	90	110	96	70	130
Iron (total)	EMS0307-SEP25	mg/L	0.007	<0.007	7	20	101	90	110	100	70	130
Potassium (total)	EMS0307-SEP25	mg/L	0.009	<0.009	1	20	100	90	110	93	70	130
Magnesium (total)	EMS0307-SEP25	mg/L	0.001	<0.001	3	20	97	90	110	100	70	130
Manganese (total)	EMS0307-SEP25	mg/L	0.00001	<0.00001	ND	20	104	90	110	110	70	130
Molybdenum (total)	EMS0307-SEP25	mg/L	0.0004	<0.0004	ND	20	100	90	110	90	70	130
Sodium (total)	EMS0307-SEP25	mg/L	0.01	<0.01	2	20	98	90	110	100	70	130
Nickel (total)	EMS0307-SEP25	mg/L	0.0001	<0.0001	ND	20	104	90	110	89	70	130



FINAL REPORT

CA15851-SEP25 R

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Lead (total)	EMS0307-SEP25	mg/L	0.00009	<0.00009	ND	20	103	90	110	86	70	130
Phosphorus (total)	EMS0307-SEP25	mg/L	0.003	<0.003	2	20	99	90	110	NV	70	130
Antimony (total)	EMS0307-SEP25	mg/L	0.0009	<0.0005	ND	20	109	90	110	79	70	130
Selenium (total)	EMS0307-SEP25	mg/L	0.00004	<0.00004	ND	20	104	90	110	102	70	130
Silicon (total)	EMS0307-SEP25	mg/L	0.02	<0.02	4	20	99	90	110	NV	70	130
Tin (total)	EMS0307-SEP25	mg/L	0.00006	<0.00006	ND	20	100	90	110	NV	70	130
Strontium (total)	EMS0307-SEP25	mg/L	0.00008	<0.00008	1	20	104	90	110	93	70	130
Titanium (total)	EMS0307-SEP25	mg/L	0.0001	<0.0001	11	20	95	90	110	NV	70	130
Uranium (total)	EMS0307-SEP25	mg/L	0.000002	<0.000002	ND	20	105	90	110	87	70	130
Vanadium (total)	EMS0307-SEP25	mg/L	0.00001	<0.00001	ND	20	105	90	110	90	70	130
Zinc (total)	EMS0307-SEP25	mg/L	0.002	<0.002	ND	20	100	90	110	95	70	130

pH

Method: SM 4500 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0684-SEP25	No unit	0.05	NA	0		100			NA		



FINAL REPORT

CA15851-SEP25 R

QC SUMMARY

Phenols by SFA

Method: SM 5530B-D | Internal ref.: ME-CA-IENVISFA-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
4AAP-Phenolics	SKA0010-OCT25	mg/L	0.001	<0.001	ND	10	99	80	120	99	75	125

Reactive Phosphorus by SFA

Method: SM 4500-P F | Internal ref.: ME-CA-IENVISFA-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Reactive Phosphorous (o-phosphate as P)	SKA0243-SEP25	mg/L	0.03	<0.03	6	10	101	90	110	80	75	125

Solids Analysis

Method: SM 2540C | Internal ref.: ME-CA-IENVIEWL-LAK-AN-005

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Dissolved Solids	EWL0677-SEP25	mg/L	30	<30	1	20	100	80	120	NA		



FINAL REPORT

CA15851-SEP25 R

QC SUMMARY

Suspended Solids

Method: SM 2540D | Internal ref.: ME-CA-IENVIEWL-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Suspended Solids	EWL0023-OCT25	mg/L	2	< 2	1	10	102	90	110	NA		

Total Nitrogen

Method: SM 4500-N C/4500-NO3- F | Internal ref.: ME-CA-IENVISFA-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Kjeldahl Nitrogen	SKA0020-OCT25	as N mg/L	0.5	<0.5	0	10	100	90	110	103	75	125

QC SUMMARY

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND**FOOTNOTES**

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY (General)

SGS Environmental Services - Lakefield: 185 Concession St., Lakefield, ON K0L 2H0 Phone: 705-652-2000 Toll Free: 877-747-7658 Fax: 705-652-6365 Web: www.ca.sgs.com {4}

SGS Environmental Services - London: 657 Consortium Court, London, ON, N6E 2S8 Phone: 519-672-4500 Toll Free: 877-848-8060 Fax: 519-672-0361 Web: www.ca.sgs.com {4}

Laboratory Information Section

Received Date (mm/dd/yyyy): SEP 27 2025

LAB LIMS #: CA 15851 SEP 25

Received Time (After Hours Only):

Temperature Upon Receipt (°C): 3x3

Billing & Reporting Information

Company: Pinchin
Attention: Alana Valle
Address: 662 Falconbridge Rd, Unit 3
Sudbury, Ontario
P3A 4S4
Email: avalue@pinchin.com

Quote #: 2023 544
Attached Parameter List: YES NO
Turnaround Time
Is *Rush Turnaround Time Required? YES NO

Project Name/Number: 225335.010-Chapman Landfill SW
P.O. #:

* Rush TA Requests Require Lab Approval

Client Information/Report To:

Client Lab #:

Company Name: same as above

Phone Number: 705.507.9479

Contact Name:

Fax Number:

Address:

E-mail:

Copy to:

Sample Information

Table with columns: Sample Identifier, Date Sampled, Time Sampled, # of Bottles, Analysis Requested (Field Filtered, Field Temp, Field pH, SW Package). Rows include SW1, SW2, SW3, SEEP, SW DUP.

Sampled By (1): Jenny + MJ (Signature) Date: 09/26/25

Relinquished by (2): Jenny + MJ (Signature) Date: 09/26/25

Note: (1) Submission of samples to SGS is acknowledgement that you have been provided direction on sample collection/handling and transportation of samples. (2) Submission of samples to SGS is considered authorization for completion of work.

This document is issued by the Company under its General Conditions of Service accessible at http://www.sgs.com/terms_and_conditions.htm.

cooler not sealed
335668604648
SAT PP 1215



FINAL REPORT

CA15852-SEP25 R1

225335.010, Chapman GW

Prepared for

Pinchin Ltd

First Page

CLIENT DETAILS

Client Pinchin Ltd
 Address 662 Falconbridge Road, Unit 3, Sudbury
 Canada, P3A 4S4
 Phone: 705-521-0560. Fax:
 Contact Alana Valle
 Telephone 705-521-0560
 Facsimile
 Email avalue@Pinchin.com
 Project 225335.010, Chapman GW
 Order Number
 Samples Ground Water (13)

LABORATORY DETAILS

Project Specialist Brad Moore Hon. B.Sc
 Laboratory SGS Canada Inc.
 Address 185 Concession St., Lakefield ON, K0L 2H0
 Telephone 705-652-2143
 Facsimile 705-652-6365
 Email brad.moore@sgs.com
 SGS Reference CA15852-SEP25
 Received 09/27/2025
 Approved 10/10/2025
 Report Number CA15852-SEP25 R1
 Date Reported 10/10/2025

COMMENTS

Temperature of Sample upon Receipt: 4 degrees C
 Nitrates spike low, results accepted based on all other QC

SIGNATORIES

Brad Moore Hon. B.Sc




TABLE OF CONTENTS

First Page.....	1
Index.....	2
Results.....	3-10
Exceedance Summary.....	11-12
QC Summary.....	13-23
Legend.....	24
Annexes.....	25



FINAL REPORT

CA15852-SEP25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

	Sample Number	7	8	9	10	11	12	13	14
	Sample Name	BH1	BH2	BH3-II	BH4-II	BH5-II	BH6-III	BH7-II	BH8-I
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result	Result	Result
Acid Rock Drainage												
pH Check <2	pH	0.05			1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

BTEX

Benzene	µg/L	0.5		1	---	---	---	< 0.5	---	---	---	---
Toluene	µg/L	0.5		60	---	---	---	< 0.5	---	---	---	---

General Chemistry

Biochemical Oxygen Demand (BOD5)	mg/L	2			< 4 †	< 4 †	< 4 †	< 4 †	< 4 †	< 4 †	< 4 †	4	
Prep BOD	Prep	no			45930	45930	45930	45930	45930	45930	45930	45930	
Total Suspended Solids	mg/L	2			6	23	1240	8	558	215	1040	236	
Alkalinity	mg/L as CaCO3	2		500	22	313	10	280	98	159	11	117	
Conductivity	uS/cm	2			53	719	37	706	406	406	46	374	
Total Dissolved Solids	mg/L	30		500	< 30	426	< 30	440	223	246	37	194	
Chemical Oxygen Demand	mg/L	8			< 8	24	< 8	27	16	9	< 8	17	
Turbidity	NTU	0.10		5	1	5.2	20	300	8.8	190	8.4	850	37
Total Kjeldahl Nitrogen	as N mg/L	0.5			< 0.5	1.3	< 0.5	0.7	< 0.5	< 0.5	< 0.5	1.6	
Ammonia+Ammonium (N)	as N mg/L	0.1			< 0.1	0.8	< 0.1	0.4	0.2	< 0.1	< 0.1	1.4	
Total Reactive Phosphorous (o-phosphate as P)	mg/L	0.03			< 0.03	< 0.03	0.43	< 0.03	0.10	< 0.03	0.04	0.04	
Dissolved Organic Carbon	mg/L	1		5		3	10	3	10	6	6	2	6



FINAL REPORT

CA15852-SEP25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

	Sample Number	7	8	9	10	11	12	13	14
	Sample Name	BH1	BH2	BH3-II	BH4-II	BH5-II	BH6-III	BH7-II	BH8-I
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result	Result	Result
Metals and Inorganics												
Phosphorus (total)	mg/L	0.03			< 0.03	0.04	0.89	< 0.03	0.37	0.03	0.34	0.91
Sulphate	mg/L	2	500		< 2	58	12	85	81	86	14	30
Nitrite (as N)	as N mg/L	0.03		1	< 0.03	< 0.03	< 0.03	< 0.03	0.04	< 0.03	< 0.03	0.20
Nitrate (as N)	as N mg/L	0.06		10	0.82	< 0.06	< 0.06	4.17	2.24	1.56	< 0.06	2.46
Nitrate + Nitrite (as N)	as N mg/L	0.06			0.82	< 0.06	< 0.06	4.17	2.28	1.56	< 0.06	2.66
Hardness (dissolved)	mg/L as CaCO3	0.05	100		13.6	325	3.9	330	176	185	10.5	122
Silver (dissolved)	mg/L	0.00005			< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005
Aluminum (dissolved)	mg/L	0.001			0.009	0.009	0.062	0.020	0.017	0.005	0.131	0.019
Arsenic (dissolved)	mg/L	0.0002		0.01	< 0.0002	0.0005	0.0007	0.0005	0.0004	0.0003	< 0.0002	0.0003
Barium (dissolved)	mg/L	0.00008		1	0.00493	0.178	0.00250	0.105	0.122	0.116	0.0142	0.120
Beryllium (dissolved)	mg/L	0.000007			0.000007	0.000010	0.000030	0.000018	0.000007	0.000013	0.000068	0.000011
Bismuth (dissolved)	mg/L	0.00001			< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001
Boron (dissolved)	mg/L	0.002		5	0.062	0.488	0.014	0.511	0.286	0.291	0.013	0.266
Calcium (dissolved)	mg/L	0.01			4.23	94.6	1.20	108	56.1	56.5	2.23	37.7
Cadmium (dissolved)	mg/L	0.000003		0.005	< 0.000003	0.000061	0.000008	0.000026	0.000014	0.000006	0.000018	0.000048
Cobalt (dissolved)	mg/L	0.000004			0.000216	0.00318	0.000080	0.00125	0.000217	0.000148	0.000579	0.000470
Chromium (dissolved)	mg/L	0.00008		0.05	0.00029	0.00035	0.00020	0.00061	0.00038	0.00021	0.00033	0.00026
Copper (dissolved)	mg/L	0.001	1		0.002	0.003	0.001	0.008	0.003	0.003	0.002	0.004
Iron (dissolved)	mg/L	0.007	0.3		< 0.007	2.21	0.024	0.020	0.007	< 0.007	0.172	0.008
Potassium (dissolved)	mg/L	0.009			2.00	7.43	0.483	11.0	5.36	5.85	1.73	8.72
Magnesium (dissolved)	mg/L	0.001			0.726	21.6	0.228	14.7	8.67	10.6	1.20	6.82
Manganese (dissolved)	mg/L	0.00001	0.05		0.0271	2.40	0.00914	0.289	0.107	0.0318	0.0185	1.57



FINAL REPORT

CA15852-SEP25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

	Sample Number	7	8	9	10	11	12	13	14
	Sample Name	BH1	BH2	BH3-II	BH4-II	BH5-II	BH6-III	BH7-II	BH8-I
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result	Result	Result
Metals and Inorganics (continued)												
Molybdenum (dissolved)	mg/L	0.0004			< 0.0004	0.0008	< 0.0004	0.0011	< 0.0004	< 0.0004	< 0.0004	< 0.0004
Sodium (dissolved)	mg/L	0.01	200	20	4.04	21.6	4.59	12.1	10.2	9.52	4.02	18.3
Nickel (dissolved)	mg/L	0.0001			0.0002	0.0017	0.0001	0.0019	0.0010	0.0009	0.0007	0.0007
Lead (dissolved)	mg/L	0.00009		0.01	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009	0.00034	< 0.00009
Antimony (dissolved)	mg/L	0.0009		0.006	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009
Selenium (dissolved)	mg/L	0.00004		0.05	0.00007	0.00012	< 0.00004	0.00016	0.00008	0.00008	0.00008	0.00010
Tin (dissolved)	mg/L	0.00006			< 0.00006	0.00007	< 0.00006	0.00007	< 0.00006	< 0.00006	< 0.00006	< 0.00006
Strontium (dissolved)	mg/L	0.00008			0.0206	0.613	0.0131	0.412	0.293	0.327	0.0193	0.241
Titanium (dissolved)	mg/L	0.0001			< 0.0001	0.0002	0.0005	0.0014	0.0003	0.0002	0.0058	0.0003
Thallium (dissolved)	mg/L	0.000005			0.000009	< 0.000005	0.000007	0.000036	0.000013	0.000013	0.000021	0.000077
Uranium (dissolved)	mg/L	0.000002		0.02	0.000083	0.00427	0.000207	0.00660	0.000370	0.000337	0.000167	0.000262
Vanadium (dissolved)	mg/L	0.00001			0.00006	0.00075	0.00011	0.00037	0.00017	0.00010	0.00037	0.00015
Tungsten (dissolved)	mg/L	0.0002			< 0.0002	< 0.0002	< 0.0002	0.00057	< 0.0002	0.00045	< 0.0002	< 0.0002
Zinc (dissolved)	mg/L	0.002	5		0.009	0.010	0.010	0.009	0.010	0.011	0.014	0.009



FINAL REPORT

CA15852-SEP25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

	Sample Number	7	8	9	10	11	12	13	14
	Sample Name	BH1	BH2	BH3-II	BH4-II	BH5-II	BH6-III	BH7-II	BH8-I
	Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
	Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result	Result	Result	Result
-----------	-------	----	----	----	--------	--------	--------	--------	--------	--------	--------	--------

Other (ORP)

pH	No unit	0.05	8.5		6.65	7.40	6.41	7.29	6.90	6.93	6.37	7.01
Chloride	mg/L	1	250		< 1	20	2	6	7	6	2	24
Mercury (dissolved)	mg/L	0.00001		0.001	---	---	---	< 0.00001	---	---	---	---

Phenols

4AAP-Phenolics	mg/L	0.002			< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002	< 0.002
----------------	------	-------	--	--	---------	---------	---------	---------	---------	---------	---------	---------

VOCs

1,4-Dichlorobenzene	µg/L	0.5			---	---	---	< 0.5	---	---	---	---
Dichloromethane	µg/L	0.5			---	---	---	< 0.5	---	---	---	---
Vinyl Chloride	µg/L	0.2			---	---	---	< 0.2	---	---	---	---



FINAL REPORT

CA15852-SEP25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Sample Number	15	16	17	18	19
Sample Name	BH9-I	BH10-I	BH11-I	GW DUP 1	GW DUP 2
Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result
Acid Rock Drainage									
pH Check <2	pH	0.05			1.00	1.00	1.00	1.00	1.00

General Chemistry

Biochemical Oxygen Demand (BOD5)	mg/L	2			< 4 †	< 4 †	< 4 †	< 4 †	< 4 †
Prep BOD	Prep	no			45930	45930	45930	45930	45930
Total Suspended Solids	mg/L	2			714	354	183	205	8
Alkalinity	mg/L as CaCO3	2	500		207	161	9	8	284
Conductivity	uS/cm	2			544	571	100	101	707
Total Dissolved Solids	mg/L	30	500		274	337	77	49	429
Chemical Oxygen Demand	mg/L	8			28	22	< 8	< 8	27
Turbidity	NTU	0.10	5	1	600	100	18	16	7.4
Total Kjeldahl Nitrogen	as N mg/L	0.5			3.9	< 0.5	< 0.5	< 0.5	0.7
Ammonia+Ammonium (N)	as N mg/L	0.1			3.7	< 0.1	< 0.1	< 0.1	0.4
Total Reactive Phosphorous (o-phosphate as P)	mg/L	0.03			0.18	0.04	< 0.03	< 0.03	< 0.03
Dissolved Organic Carbon	mg/L	1	5		8	10	2	2	10



FINAL REPORT

CA15852-SEP25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Sample Number	15	16	17	18	19
Sample Name	BH9-I	BH10-I	BH11-I	GW DUP 1	GW DUP 2
Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result
Metals and Inorganics									
Phosphorus (total)	mg/L	0.03			0.55	0.09	0.60	0.36	< 0.03
Sulphate	mg/L	2	500		42	120	4	4	83
Nitrite (as N)	as N mg/L	0.03		1	< 0.03	< 0.03	< 0.03	< 0.03	< 0.03
Nitrate (as N)	as N mg/L	0.06		10	< 0.06	2.29	0.17	0.19	3.85
Nitrate + Nitrite (as N)	as N mg/L	0.06			< 0.06	2.29	0.17	0.19	3.85
Hardness (dissolved)	mg/L as CaCO3	0.05	100		198	270	31.3	31.2	323
Silver (dissolved)	mg/L	0.00005			< 0.00005	< 0.00005	< 0.00005	< 0.00005	< 0.00005
Aluminum (dissolved)	mg/L	0.001			0.080	0.029	0.025	0.025	0.020
Arsenic (dissolved)	mg/L	0.0002		0.01	0.0011	0.0008	< 0.0002	< 0.0002	0.0004
Barium (dissolved)	mg/L	0.00008		1	0.105	0.253	0.0244	0.0237	0.105
Beryllium (dissolved)	mg/L	0.000007			0.000027	0.000007	0.000055	0.000059	0.000019
Bismuth (dissolved)	mg/L	0.00001			< 0.00001	< 0.00001	< 0.00001	< 0.00001	< 0.00001
Boron (dissolved)	mg/L	0.002		5	0.319	0.564	0.005	0.004	0.506
Calcium (dissolved)	mg/L	0.01			64.6	71.9	10.2	10.1	106
Cadmium (dissolved)	mg/L	0.000003		0.005	0.000009	0.000011	0.000029	0.000028	0.000038
Cobalt (dissolved)	mg/L	0.000004			0.00971	0.000378	0.000047	0.000055	0.00123
Chromium (dissolved)	mg/L	0.00008		0.05	0.00086	0.00039	0.00009	0.00012	0.00051
Copper (dissolved)	mg/L	0.001	1		0.002	0.005	< 0.001	< 0.001	0.008
Iron (dissolved)	mg/L	0.007	0.3		9.52	0.027	0.024	0.023	0.023
Potassium (dissolved)	mg/L	0.009			9.95	8.77	1.54	1.49	11.0
Magnesium (dissolved)	mg/L	0.001			8.86	22.0	1.43	1.46	14.3
Manganese (dissolved)	mg/L	0.00001	0.05		3.37	0.00815	0.0210	0.0205	0.289



FINAL REPORT

CA15852-SEP25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Sample Number	15	16	17	18	19
Sample Name	BH9-I	BH10-I	BH11-I	GW DUP 1	GW DUP 2
Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result
Metals and Inorganics (continued)									
Molybdenum (dissolved)	mg/L	0.0004			0.0006	< 0.0004	< 0.0004	< 0.0004	0.0012
Sodium (dissolved)	mg/L	0.01	200	20	18.8	13.0	4.95	4.83	11.9
Nickel (dissolved)	mg/L	0.0001			0.0021	0.0018	0.0002	0.0002	0.0020
Lead (dissolved)	mg/L	0.00009		0.01	< 0.00009	< 0.00009	< 0.00009	< 0.00009	< 0.00009
Antimony (dissolved)	mg/L	0.0009		0.006	< 0.0009	< 0.0009	< 0.0009	< 0.0009	< 0.0009
Selenium (dissolved)	mg/L	0.00004		0.05	0.00012	0.00011	< 0.00004	< 0.00004	0.00019
Tin (dissolved)	mg/L	0.00006			< 0.00006	< 0.00006	< 0.00006	< 0.00006	0.00007
Strontium (dissolved)	mg/L	0.00008			0.312	0.498	0.106	0.105	0.409
Titanium (dissolved)	mg/L	0.0001			0.0044	0.0003	0.0002	0.0002	0.0007
Thallium (dissolved)	mg/L	0.000005			0.000027	0.000044	0.000011	0.000008	0.000038
Uranium (dissolved)	mg/L	0.000002		0.02	0.00150	0.00357	0.000051	0.000045	0.00674
Vanadium (dissolved)	mg/L	0.00001			0.00170	0.00059	0.00008	0.00006	0.00036
Tungsten (dissolved)	mg/L	0.0002			< 0.0002	0.00139	< 0.0002	< 0.0002	0.00056
Zinc (dissolved)	mg/L	0.002	5		0.010	0.010	0.010	0.009	0.010



FINAL REPORT

CA15852-SEP25 R1

Client: Pinchin Ltd

Project: 225335.010, Chapman GW

Project Manager: Alana Valle

Samplers: Jenny + MJ

MATRIX: WATER

Sample Number	15	16	17	18	19
Sample Name	BH9-I	BH10-I	BH11-I	GW DUP 1	GW DUP 2
Sample Matrix	Ground Water	Ground Water	Ground Water	Ground Water	Ground Water
Sample Date	26/09/2025	26/09/2025	26/09/2025	26/09/2025	26/09/2025

L1 = ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03

L2 = ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03

Parameter	Units	RL	L1	L2	Result	Result	Result	Result	Result
Other (ORP)									
pH	No unit	0.05	8.5		7.21	7.34	6.26	6.27	7.35
Chloride	mg/L	1	250		28	6	22	23	6
Phenols									
4AAP-Phenolics	mg/L	0.002			< 0.002	< 0.002	< 0.002	< 0.002	< 0.002

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	ODWS_AO_OG / WATER / - - Table 4 - Drinking Water - Reg O.169_03		ODWS_MAC / WATER / - - Table 1,2 and 3 - Drinking Water - Reg O.169_03	
				L1	L2	L1	L2

BH1

Turbidity	SM 2130	NTU	5.2	5	1
-----------	---------	-----	-----	---	---

BH2

Turbidity	SM 2130	NTU	20	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO ₃	325	100	
Iron (dissolved)	SM 3030/EPA 200.8	mg/L	2.21	0.3	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	2.40	0.05	
Sodium (dissolved)	SM 3030/EPA 200.8	mg/L	21.6		20
Dissolved Organic Carbon	SM 5310	mg/L	10	5	

BH3-II

Turbidity	SM 2130	NTU	300	5	1
-----------	---------	-----	-----	---	---

BH4-II

Turbidity	SM 2130	NTU	8.8	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO ₃	330	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	0.289	0.05	
Dissolved Organic Carbon	SM 5310	mg/L	10	5	

BH5-II

Turbidity	SM 2130	NTU	190	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO ₃	176	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	0.107	0.05	
Dissolved Organic Carbon	SM 5310	mg/L	6	5	

BH6-III

Turbidity	SM 2130	NTU	8.4	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO ₃	185	100	
Dissolved Organic Carbon	SM 5310	mg/L	6	5	

BH7-II

Turbidity	SM 2130	NTU	850	5	1
-----------	---------	-----	-----	---	---

BH8-I

Turbidity	SM 2130	NTU	37	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO ₃	122	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	1.57	0.05	
Dissolved Organic Carbon	SM 5310	mg/L	6	5	

BH9-I

Turbidity	SM 2130	NTU	600	5	1
-----------	---------	-----	-----	---	---

EXCEEDANCE SUMMARY

Parameter	Method	Units	Result	ODWS_AO_OG /	ODWS_MAC /
				WATER / - - Table 4	WATER / - - Table
				- Drinking Water -	1,2 and 3 -
				Reg O.169_03	Drinking Water -
					Reg O.169_03
				L1	L2

BH9-I (continued)

Parameter	Method	Units	Result	L1	L2
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	198	100	
Iron (dissolved)	SM 3030/EPA 200.8	mg/L	9.52	0.3	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	3.37	0.05	
Dissolved Organic Carbon	SM 5310	mg/L	8	5	

BH10-I

Parameter	Method	Units	Result	L1	L2
Turbidity	SM 2130	NTU	100	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	270	100	
Dissolved Organic Carbon	SM 5310	mg/L	10	5	

BH11-I

Parameter	Method	Units	Result	L1	L2
Turbidity	SM 2130	NTU	18	5	1

GW DUP 1

Parameter	Method	Units	Result	L1	L2
Turbidity	SM 2130	NTU	16	5	1

GW DUP 2

Parameter	Method	Units	Result	L1	L2
Turbidity	SM 2130	NTU	7.4	5	1
Hardness (dissolved)	SM 3030/EPA 200.7	mg/L as CaCO3	323	100	
Manganese (dissolved)	SM 3030/EPA 200.8	mg/L	0.289	0.05	
Dissolved Organic Carbon	SM 5310	mg/L	10	5	



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Alkalinity

Method: SM 2320 | Internal ref.: ME-CA-1ENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Alkalinity	EWL0674-SEP25	mg/L as CaCO3	2	< 2	1	20	109	80	120	NA		

Ammonia by SFA

Method: SM 4500 | Internal ref.: ME-CA-1ENVISFA-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Ammonia+Ammonium (N)	SKA0011-OCT25	as N mg/L	0.1	<0.1	2	10	101	90	110	105	75	125
Ammonia+Ammonium (N)	SKA0028-OCT25	as N mg/L	0.1	<0.1	ND	10	100	90	110	100	75	125



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Anions by discrete analyzer

Method: US EPA 325.2 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-026

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chloride	DIO8002-OCT25	mg/L	1	<1	0	20	93	70	130	92	70	130
Nitrate + Nitrite (as N)	DIO8002-OCT25	mg/L	0.06	< 0.06	ND	20	107	80	120	70	75	125
Nitrite (as N)	DIO8002-OCT25	mg/L	0.03	< 0.03	ND	20	103	80	120	101	75	125
Sulphate	DIO8002-OCT25	mg/L	2	<2	6	20	96	80	120	96	75	125

Biochemical Oxygen Demand

Method: SM 5210 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-007

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Biochemical Oxygen Demand (BOD5)	BOD0061-SEP25	mg/L	2	< 2	7	30	105	70	130	81	70	130



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Carbon by SFA

Method: SM 5310 | Internal ref.: ME-CA-IENVISFA-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Dissolved Organic Carbon	SKA0017-OCT25	mg/L	1	<1	3	20	102	90	110	98	75	125

Chemical Oxygen Demand

Method: HACH 8000 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-009

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Chemical Oxygen Demand	EWL0698-SEP25	mg/L	8	<8	ND	20	98	80	120	105	75	125
Chemical Oxygen Demand	EWL0699-SEP25	mg/L	8	<8	8	20	90	80	120	104	75	125

Conductivity

Method: SM 2510 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Conductivity	EWL0674-SEP25	uS/cm	2	< 2	0	10	99	90	110	NA		



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Mercury by CVAAS

Method: EPA 7471A/SM 3112B | Internal ref.: ME-CA-IENVISPE-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Mercury (dissolved)	EHG0055-SEP25	mg/L	0.00001	< 0.00001	ND	20	118	80	120	129	70	130



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Metals in aqueous samples - ICP-MS

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Silver (dissolved)	EMS0303-SEP25	mg/L	0.00005	<0.00005	ND	20	91	90	110	NV	70	130
Aluminum (dissolved)	EMS0303-SEP25	mg/L	0.001	<0.001	ND	20	103	90	110	103	70	130
Arsenic (dissolved)	EMS0303-SEP25	mg/L	0.0002	<0.0002	ND	20	102	90	110	109	70	130
Barium (dissolved)	EMS0303-SEP25	mg/L	0.00008	<0.00008	2	20	101	90	110	97	70	130
Beryllium (dissolved)	EMS0303-SEP25	mg/L	0.000007	<0.000007	ND	20	102	90	110	100	70	130
Boron (dissolved)	EMS0303-SEP25	mg/L	0.002	<0.002	3	20	95	90	110	97	70	130
Bismuth (dissolved)	EMS0303-SEP25	mg/L	0.00001	<0.00001	ND	20	99	90	110	86	70	130
Calcium (dissolved)	EMS0303-SEP25	mg/L	0.01	<0.01	0	20	98	90	110	103	70	130
Cadmium (dissolved)	EMS0303-SEP25	mg/L	0.000003	<0.000003	ND	20	102	90	110	98	70	130
Cobalt (dissolved)	EMS0303-SEP25	mg/L	0.000004	<0.000004	15	20	96	90	110	90	70	130
Chromium (dissolved)	EMS0303-SEP25	mg/L	0.00008	<0.00008	ND	20	105	90	110	97	70	130
Copper (dissolved)	EMS0303-SEP25	mg/L	0.001	<0.001	1	20	97	90	110	82	70	130
Iron (dissolved)	EMS0303-SEP25	mg/L	0.007	<0.007	2	20	100	90	110	100	70	130
Potassium (dissolved)	EMS0303-SEP25	mg/L	0.009	<0.009	2	20	105	90	110	99	70	130
Magnesium (dissolved)	EMS0303-SEP25	mg/L	0.001	<0.001	0	20	104	90	110	100	70	130
Manganese (dissolved)	EMS0303-SEP25	mg/L	0.00001	<0.00001	1	20	103	90	110	90	70	130
Molybdenum (dissolved)	EMS0303-SEP25	mg/L	0.0004	<0.0004	ND	20	105	90	110	99	70	130
Sodium (dissolved)	EMS0303-SEP25	mg/L	0.01	<0.01	1	20	99	90	110	96	70	130
Nickel (dissolved)	EMS0303-SEP25	mg/L	0.0001	<0.0001	1	20	102	90	110	97	70	130
Lead (dissolved)	EMS0303-SEP25	mg/L	0.00009	<0.00009	4	20	99	90	110	80	70	130



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Metals in aqueous samples - ICP-MS (continued)

Method: SM 3030/EPA 200.8 | Internal ref.: ME-CA-IENVISPE-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Antimony (dissolved)	EMS0303-SEP25	mg/L	0.0009	<0.0005	ND	20	109	90	110	105	70	130
Selenium (dissolved)	EMS0303-SEP25	mg/L	0.00004	<0.00004	7	20	101	90	110	97	70	130
Tin (dissolved)	EMS0303-SEP25	mg/L	0.00006	<0.00006	6	20	98	90	110	NV	70	130
Strontium (dissolved)	EMS0303-SEP25	mg/L	0.00008	<0.00008	1	20	105	90	110	100	70	130
Titanium (dissolved)	EMS0303-SEP25	mg/L	0.0001	<0.0001	ND	20	100	90	110	NV	70	130
Thallium (dissolved)	EMS0303-SEP25	mg/L	0.000005	<0.000005	ND	20	98	90	110	80	70	130
Uranium (dissolved)	EMS0303-SEP25	mg/L	0.000002	<0.000002	3	20	107	90	110	95	70	130
Vanadium (dissolved)	EMS0303-SEP25	mg/L	0.00001	<0.00001	ND	20	103	90	110	106	70	130
Tungsten (dissolved)	EMS0303-SEP25	mg/L	0.0002	<0.0002	ND	20	102	90	110	NV	70	130
Zinc (dissolved)	EMS0303-SEP25	mg/L	0.002	<0.002	1	20	105	90	110	105	70	130

pH

Method: SM 4500 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
pH	EWL0674-SEP25	No unit	0.05	NA	0		100			NA		



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Phenols by SFA

Method: SM 5530B-D | Internal ref.: ME-CA-IENVISFA-LAK-AN-006

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
4AAP-Phenolics	SKA0010-OCT25	mg/L	0.002	<0.002	ND	10	99	80	120	99	75	125

Phosphorus by SFA

Method: SM 4500-P J | Internal ref.: ME-CA-IENVISFA-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Phosphorus (total)	SKA0006-OCT25	mg/L	0.03	<0.03	2	10	98	90	110	100	75	125
Phosphorus (total)	SKA0015-OCT25	mg/L	0.03	<0.03	4	10	100	90	110	99	75	125



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Reactive Phosphorus by SFA

Method: SM 4500-P F | Internal ref.: ME-CA-IENVISFA-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Reactive Phosphorous (o-phosphate as P)	SKA0243-SEP25	mg/L	0.03	<0.03	6	10	101	90	110	80	75	125

Solids Analysis

Method: SM 2540C | Internal ref.: ME-CA-IENVIEWL-LAK-AN-005

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Dissolved Solids	EWL0676-SEP25	mg/L	30	<30	7	20	100	80	120	NA		
Total Dissolved Solids	EWL0677-SEP25	mg/L	30	<30	1	20	100	80	120	NA		



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Suspended Solids

Method: SM 2540D | Internal ref.: ME-CA-IENVIEWL-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Suspended Solids	EWL0020-OCT25	mg/L	2	< 2	7	10	99	90	110	NA		
Total Suspended Solids	EWL0021-OCT25	mg/L	2	< 2	8	10	92	90	110	NA		

Total Nitrogen

Method: SM 4500-N C/4500-NO3- F | Internal ref.: ME-CA-IENVISFA-LAK-AN-002

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Total Kjeldahl Nitrogen	SKA0020-OCT25	as N mg/L	0.5	<0.5	0	10	100	90	110	103	75	125
Total Kjeldahl Nitrogen	SKA0027-OCT25	as N mg/L	0.5	<0.5	2	10	96	90	110	97	75	125



FINAL REPORT

CA15852-SEP25 R1

QC SUMMARY

Turbidity

Method: SM 2130 | Internal ref.: ME-CA-IENVIEWL-LAK-AN-003

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
Turbidity	EWL0647-SEP25	NTU	0.10	< 0.10	0	10	100	90	110	NA		

Volatile Organics

Method: EPA 5030B/8260C | Internal ref.: ME-CA-IENVIGC-LAK-AN-004

Parameter	QC batch Reference	Units	RL	Method Blank	Duplicate		LCS/Spike Blank			Matrix Spike / Ref.		
					RPD	AC (%)	Spike Recovery (%)	Recovery Limits (%)		Spike Recovery (%)	Recovery Limits (%)	
								Low	High		Low	High
1,4-Dichlorobenzene	GCM0469-SEP25	µg/L	0.5	<0.5	ND	30	115	60	130	101	50	140
Benzene	GCM0469-SEP25	µg/L	0.5	<0.5	ND	30	98	60	130	97	50	140
Dichloromethane	GCM0469-SEP25	µg/L	0.5	<0.5	ND	30	94	60	130	80	50	140
Toluene	GCM0469-SEP25	µg/L	0.5	<0.5	ND	30	97	60	130	100	50	140
Vinyl Chloride	GCM0469-SEP25	µg/L	0.2	<0.2	ND	30	100	50	140	107	50	140

QC SUMMARY

Method Blank: a blank matrix that is carried through the entire analytical procedure. Used to assess laboratory contamination.

Duplicate: Paired analysis of a separate portion of the same sample that is carried through the entire analytical procedure. Used to evaluate measurement precision.

LCS/Spike Blank: Laboratory control sample or spike blank refer to a blank matrix to which a known amount of analyte has been added. Used to evaluate analyte recovery and laboratory accuracy without sample matrix effects.

Matrix Spike: A sample to which a known amount of the analyte of interest has been added. Used to evaluate laboratory accuracy with sample matrix effects.

Reference Material: a material or substance matrix matched to the samples that contains a known amount of the analyte of interest. A reference material may be used in place of a matrix spike.

RL: Reporting limit

RPD: Relative percent difference

AC: Acceptance criteria

Multielement Scan Qualifier: as the number of analytes in a scan increases, so does the chance of a limit exceedance by random chance as opposed to a real method problem. Thus, in multielement scans, for the LCS and matrix spike, up to 10% of the analytes may exceed the quoted limits by up to 10% absolute and the spike is considered acceptable.

Duplicate Qualifier: for duplicates as the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Matrix Spike Qualifier: for matrix spikes, as the concentration of the native analyte increases, the uncertainty of the matrix spike recovery increases. Thus, the matrix spike acceptance limits apply only when the concentration of the matrix spike is greater than or equal to the concentration of the native analyte.

LEGEND

FOOTNOTES

NSS Insufficient sample for analysis.
RL Reporting Limit.
 ↑ Reporting limit raised.
 ↓ Reporting limit lowered.
NA The sample was not analysed for this analyte
ND Non Detect

Results relate only to the sample tested.

Data reported represent the sample as submitted to SGS. Solid samples expressed on a dry weight basis.

"Temperature Upon Receipt" is representative of the whole shipment and may not reflect the temperature of individual samples.

Analysis conducted on samples submitted pursuant to or as part of Reg. 153/04, are in accordance to the "Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act and Excess Soil Quality" published by the Ministry and dated March 9, 2004 as amended.

SGS provides criteria information (such as regulatory or guideline limits and summary of limit exceedances) as a service. Every attempt is made to ensure the criteria information in this report is accurate and current, however, it is not guaranteed. Comparison to the most current criteria is the responsibility of the client and SGS assumes no responsibility for the accuracy of the criteria levels indicated.

SGS Canada Inc. statement of conformity decision rule does not consider uncertainty when analytical results are compared to a specified standard or regulation.

This document is issued, on the Client's behalf, by the Company under its General Conditions of Service available on request and accessible at http://www.sgs.com/terms_and_conditions.htm.

The Client's attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any other holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. Reproduction of this analytical report in full or in part is prohibited.

This report supersedes all previous versions.

-- End of Analytical Report --



Request for Laboratory Services and CHAIN OF CUSTODY (General)

SGS Environmental Services - Lakefield: 185 Concession St., Lakefield, ON K0L 2H0 Phone: 705-652-2000 Toll Free: 877-747-7658 Fax: 705-652-6365 Web: www.ca.sgs.com (4)

SGS Environmental Services - London: 657 Consortium Court, London, ON, N6E 2S8 Phone: 519-672-4500 Toll Free: 877-848-8060 Fax: 519-672-0361 Web: www.ca.sgs.com (4)

Laboratory Information Section

Received Date (mm/dd/yyyy): SEP 27 2025 LAB LIMS #: CA 15852 SEP 25
Received Time (After Hours Only): 3:45 Temperature Upon Receipt (°C): 3, 4, 5

Billing & Reporting Information

Invoice/Receipt to (3):	Company:	Pinchin	Quote #:	2023 544
	Attention:	Alana Valle	Attached Parameter List:	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO
	Address:	662 Falconbridge Rd, Unit 3 Sudbury, Ontario P3A 4S4	Turnaround Time	
	Email:	avalle@pinchin.com	Is *Rush Turnaround Time Required?	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Project Name/Number:	225335.010-Chapman Landfill GW	P.O. #:	* Rush TA Requests Require Lab Approval	

Client Information/Report To:

Company Name:	<u>S.A.A.</u>	Phone Number:	705.507.9479
Contact Name:		Fax Number:	
Address:		E-mail:	
Copy to:			

Sample Information

Sample Identifier	Date Sampled (mm/dd/yy)	Time Sampled	# of Bottles	Analysis Requested (please enter the analysis required below and check off which analysis applies to each sample)						
				Field Filtered	Field Temp (°C)	Field pH		GW Package	VOC's & Dissolved Hg	
BH1	09/26/25	830	11	Y				X		
BH2	09/26/25		11	Y				X		
BH3-II	09/26/25		11	Y				X		
BH4								X		
BH4-II	09/26/25		14	Y				X	X	
BH5-II	09/26/25		11	Y				X		
BH6-II								X		
BH6-III	09/26/25		11	Y				X		
BH7-II	09/26/25		11	Y				X		
BH8-I	09/26/25		11	Y				X		
BH9-I	09/26/25		11	Y				X		
BH10-I	09/26/25		11	Y				X		
BH11-I	09/26/25	1230	11	Y				X		
GW DUP 1	09/26/25	AM	11	Y				X		
GW DUP 2	09/26/25	AM	11	Y				X		

Sampled By (1): (Name)	<u>Jenny + MJ</u>	(Signature)	<u>[Signature]</u>	Date:	<u>09/26/25</u>	(mm/dd/yy)
Relinquished by (2): (Name)	<u>Jenny + MJ</u>	(Signature)	<u>[Signature]</u>	Date:	<u>09/26/25</u>	(mm/dd/yy)


Note: (1) Submission of samples to SGS is acknowledgement that you have been provided direction on sample collection/handling and transportation of samples. (2) Submission of samples to SGS is considered authorization for completion of work. Signatures may appear on this form or be retained on file in the contract, or in an alternative format (e.g. shipping documents). (3) Results may be sent by email to an unlimited number of addresses for no additional cost. Fax is available upon request. (4) Completion of work may require the subcontracting of samples between the London and Lakefield laboratories.

This document is issued by the Company under its General Conditions of Service accessible at http://www.sgs.com/terms_and_conditions.htm. (Printed copies are available upon request.) Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.


335668604663/4671/4689 SAT PP 1215 MW

APPENDIX VII
Groundwater Trend Analysis


Alkalintiy Trend Analysis - Groundwater




Chloride Trend Analysis - Groundwater




Nitrate Trend Analysis - Groundwater



pH Trend Analysis - Groundwater




Dissolved Organic Carbon Trend Analysis - Groundwater




APPENDIX VIII
Surface Water Trend Analysis


Alkalinity Trend Analysis - Surface water




Chloride Trend Analysis - Surface Water




Nitrate Trend Analysis - Surface Water



pH Trend Analysis - Surface Water



Dissolved Organic Carbon Trend Analysis - Surface Water



APPENDIX IX
Monitoring and Screening Checklist

Appendix D-Monitoring and Screening Checklist

General Information and Instructions

General Information: The checklist is to be completed, and submitted with the Monitoring Report.

Instructions: A complete checklist consists of:

- (a) a completed and signed checklist, including any additional pages of information which can be attached as needed to provide further details where indicated.
- (b) completed contact information for the Competent Environmental Practitioner (CEP)
- (c) self-declaration that CEP(s) meet(s) the qualifications as set out below and in Section 1.2 of the Technical Guidance Document.

Definition of Groundwater CEP:

For groundwater, the CEP must have expertise in hydrogeology and meet one of the following:

- (a) the person holds a licence, limited licence or temporary licence under the *Professional Engineers Act*; or
- (b) the person holds a certificate of registration under the *Professional Geoscientists Act, 2000* and is a practicing member, temporary, member or limited member of the Association of Professional Geoscientists of Ontario. O. Reg. 66/08, s. 2..

Definition of Surface water CEP:

A CEP for surface water assessments is a scientist, professional engineer or professional geoscientist as described in (a) and (b) above with demonstrated experience and post-secondary education, either a diploma or degree, in hydrology, aquatic ecology, limnology, aquatic biology, physical geography with specialization in surface water, and/or water resource management.

The type of scientific work that a CEP performs must be consistent with that person's education and experience. If an individual has appropriate training and credentials in both groundwater and surface water and is responsible for both areas of expertise, the CEP may then complete and validate both sections of the checklist.

Monitoring Report and Site Information

Monitoring Report and Site Information	
Waste Disposal Site Name	Chapman Waste Disposal Site
Location (e.g. street address, lot, concession)	Lot 108, Concession A, within the Municipality of Magnetawan, District of Parry Sound, Ontario
GPS Location (taken within the property boundary at front gate/ front entry)	Universal Transverse Mercator (UTM) coordinates Zone 17U, 606831 meters (m) Easting and 5063200 m Northing (North American Datum 1983)
Municipality	Magnetawan
Client and/or Site Owner	Corporation of the Municipality of Magnetawan
Monitoring Period (Year)	2025
This Monitoring Report is being submitted under the following:	
Certificate of Approval No.:	A521202
Director's Order No.:	Type Here
Provincial Officer's Order No.:	Type Here
Other:	Type Here

Report Submission Frequency	<input checked="" type="radio"/> Annual <input type="radio"/> Other	Specify (Type Here):
The site is:	<input checked="" type="radio"/> Active <input type="radio"/> Inactive <input type="radio"/> Closed	
If closed, specify C of A, control or authorizing document closure date:		Select Date
Has the nature of the operations at the site changed during this monitoring period?	<input type="radio"/> Yes <input checked="" type="radio"/> No	
If yes, provide details:	Type Here	
Have any measurements been taken since the last reporting period that indicate landfill gas volumes have exceeded the MOE limits for subsurface or adjacent buildings? (i. e. exceeded the LEL for methane)	<input type="radio"/> Yes <input checked="" type="radio"/> No	

Groundwater WDS Verification:

Based on all available information about the site and site knowledge, it is my opinion that:

Sampling and Monitoring Program Status:

<p>1) The monitoring program continues to effectively characterize site conditions and any groundwater discharges from the site. All monitoring wells are confirmed to be in good condition and are secure:</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>	<p>If no, list exceptions (Type Here):</p>
<p>2) All groundwater, leachate and WDS gas sampling and monitoring for the monitoring period being reported on was successfully completed as required by Certificate(s) of Approval or other relevant authorizing/control document(s):</p>	<p><input type="radio"/> Yes <input type="radio"/> No <input checked="" type="radio"/> Not Applicable</p>	<p>If no, list exceptions below or attach information.</p>

Groundwater Sampling Location	Description/Explanation for change (change in name or location, additions, deletions)	Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date

3) a) Some or all groundwater, leachate and WDS gas sampling and monitoring requirements have been established or defined outside of a ministry C of A, authorizing, or control document.	<input checked="" type="radio"/> Yes <input type="radio"/> No <input type="radio"/> Not Applicable	
b) If yes, the sampling and monitoring identified under 3(a) for the monitoring period being reported on was successfully completed in accordance with established protocols, frequencies, locations, and parameters developed as per the Technical Guidance Document:	<input type="radio"/> Yes <input checked="" type="radio"/> No <input type="radio"/> Not Applicable	If no, list exceptions below or attach additional information.
Groundwater Sampling Location	Description/Explanation for change (change in name or location, additions, deletions)	Date
BH6-II	Dry	Spring and Fall 2025
BH4-II	Insufficient volume	Fall 2025
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
4) All field work for groundwater investigations was done in accordance with standard operating procedures as established/outlined per the Technical Guidance Document (including internal/external QA/QC requirements) (Note: A SOP can be from a published source, developed internally by the site owner's consultant, or adopted by the consultant from another organization):	<input checked="" type="radio"/> Yes <input type="radio"/> No	If no, specify (Type Here):

Sampling and Monitoring Program Results/WDS Conditions and Assessment:

<p>5) The site has an adequate buffer, Contaminant Attenuation Zone (CAZ) and/or contingency plan in place. Design and operational measures, including the size and configuration of any CAZ, are adequate to prevent potential human health impacts and impairment of the environment.</p>	<p><input type="radio"/> Yes <input checked="" type="radio"/> No</p>	<p>A CAZ has not been established for the Site. However, it should be noted that based on the current observed water quality data, landfill derived leachate impacts appear to attenuate prior to the property boundary. Future investigations should involve the development/formal approval of a CAZ for this Site.</p>	
<p>6) The site meets compliance and assessment criteria.</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>	<p>If no, list and explain exceptions (Type Here):</p>	
<p>7) The site continues to perform as anticipated. There have been no unusual trends/ changes in measured leachate and groundwater levels or concentrations.</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>	<p>If no, list exceptions and explain reason for increase/change (Type Here):</p>	
<p>1) Is one or more of the following risk reduction practices in place at the site:</p> <p>(a) There is minimal reliance on natural attenuation of leachate due to the presence of an effective waste liner and active leachate collection/treatment; or</p> <p>(b) There is a predictive monitoring program in-place (modeled indicator concentrations projected over time for key locations); or</p> <p>(c) The site meets the following two conditions (typically achieved after 15 years or longer of site operation):</p> <p><i>i.</i> The site has developed stable leachate mound(s) and stable leachate plume geometry/concentrations; and</p> <p><i>ii.</i> Seasonal and annual water levels and water quality fluctuations are well understood.</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>	<p>Note which practice(s):</p>	<p><input type="checkbox"/> (a) <input type="checkbox"/> (b) <input checked="" type="checkbox"/> (c)</p>
<p>9) Have trigger values for contingency plans or site remedial actions been exceeded (where they exist):</p>	<p><input type="radio"/> Yes <input type="radio"/> No <input checked="" type="radio"/> Not Applicable</p>	<p>If yes, list value(s) that are/have been exceeded and follow-up action taken (Type Here):</p>	

Groundwater CEP Declaration:

I am a licensed professional Engineer or a registered professional geoscientist in Ontario with expertise in hydrogeology, as defined in Appendix D under Instructions. Where additional expertise was needed to evaluate the site monitoring data, I have relied on individuals who I believe to be experts in the relevant discipline, who have co-signed the compliance monitoring report or monitoring program status report, and who have provided evidence to me of their credentials.

I have examined the applicable Certificate of Approval and any other environmental authorizing or control documents that apply to the site. I have read and followed the Monitoring and Reporting for Waste Disposal Sites Groundwater and Surface Water Technical Guidance Document (MOE, 2010, or as amended), and associated monitoring and sampling guidance documents, as amended from time to time. I have reviewed all of the data collected for the above-referenced site for the monitoring period(s) identified in this checklist. Except as otherwise agreed with the ministry for certain parameters, all of the analytical work has been undertaken by a laboratory which is accredited for the parameters analysed to *ISO/IEC 17025:2005 (E)- General requirements for the competence of testing and calibration laboratories*, or as amended from time to time by the ministry.

If any exceptions or potential concerns have been noted in the questions in the checklist attached to this declaration, it is my opinion that these exceptions and concerns are minor in nature and will be rectified for the next monitoring/reporting period. Where this is not the case, the circumstances concerning the exception or potential concern and my client's proposed action have been documented in writing to the Ministry of the Environment District Manager in a letter from me dated:

12-Feb-2026

Recommendations:

Based on my technical review of the monitoring results for the waste disposal site:




No changes to the monitoring program are recommended

The following change(s) to the monitoring program is/are recommended:

Type Here

No Changes to site design and operation are recommended

The following change(s) to the site design and operation is/are recommended:

Name:	Tim McBride		
Seal:	Add Image		
Signature:		Date:	13-Feb-2026
CEP Contact Information:	Tim McBride		
Company:	Pinchin Ltd.		
Address:	662 Falconbridge Road, Unit 3 Sudbury, ON P3A 4S4		
Telephone No.:	705.521.0560	Fax No. :	
E-mail Address:	tmcbride@pinchin.com		
Co-signers for additional expertise provided:			
Signature:		Date:	Select Date
Signature:		Date:	Select Date

Surface Water WDS Verification:

Provide the name of surface water body/bodies potentially receiving the WDS effluent and the approximate distance to the waterbody (including the nearest surface water body/bodies to the site):

Name (s)	Unnamed creek to the south of the Site Unnamed creek to the east of the Site
Distance(s)	Approximately 50 m south of the Site Approximately 50 m east of the Site

Based on all available information and site knowledge, it is my opinion that:

Sampling and Monitoring Program Status:

1) The current surface water monitoring program continues to effectively characterize the surface water conditions, and includes data that relates upstream/background and downstream receiving water conditions:	<input checked="" type="radio"/> Yes <input type="radio"/> No	If no, identify issues (Type Here):
2) All surface water sampling for the monitoring period being reported was successfully completed in accordance with the Certificate(s) of Approval or relevant authorizing/control document(s) (if applicable):	<input type="radio"/> Yes <input type="radio"/> No <input checked="" type="radio"/> Not applicable (No C of A, authorizing / control document applies)	If no, specify below or provide details in an attachment.

Surface Water Sampling Location	Description/Explanation for change (change in name or location, additions, deletions)	Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date
Type Here	Type Here	Select Date

<p>3) a) Some or all surface water sampling and monitoring program requirements for the monitoring period have been established outside of a ministry C of A or authorizing/control document.</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No <input type="radio"/> Not Applicable</p>		
<p>b) If yes, all surface water sampling and monitoring identified under 3 (a) was successfully completed in accordance with the established program from the site, including sampling protocols, frequencies, locations and parameters) as developed per the Technical Guidance Document:</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No <input type="radio"/> Not Applicable</p>	<p>If no, specify below or provide details in an attachment.</p>	
Surface Water Sampling Location	Description/Explanation for change (change in name or location, additions, deletions)		Date
Type Here	Type Here		Select Date
Type Here	Type Here		Select Date
Type Here	Type Here		Select Date
Type Here	Type Here		Select Date
<p>4) All field work for surface water investigations was done in accordance with standard operating procedures, including internal/external QA/QC requirements, as established/ outlined as per the Technical Guidance Document, MOE 2010, or as amended. (Note: A SOP can be from a published source, developed internally by the site owner's consultant, or adopted by the consultant from another organization):</p>	<p><input checked="" type="radio"/> Yes <input type="radio"/> No</p>	<p>If no, specify (Type Here):</p>	

Sampling and Monitoring Program Results/WDS Conditions and Assessment:

5) The receiving water body meets surface water-related compliance criteria and assessment criteria: i.e., there are no exceedances of criteria, based on MOE legislation, regulations, Water Management Policies, Guidelines and Provincial Water Quality Objectives and other assessment criteria (e.g., CWQGs, APVs), as noted in Table A or Table B in the Technical Guidance Document (Section 4.6):	<input type="radio"/> Yes <input checked="" type="radio"/> No
--	--

If no, list parameters that exceed criteria outlined above and the amount/percentage of the exceedance as per the table below or provide details in an attachment:

Parameter	Compliance or Assessment Criteria or Background	Amount by which Compliance or Assessment Criteria or Background Exceeded
e.g. Nickel	e.g. C of A limit, PWQO, background	e.g. X% above PWQO
pH	PWQO: 6.5-8.5 CWQG: 6.5-9.0	SW1: 6.30 (spring)
Iron	PWQO: 0.3 mg/L CWQG: 0.3 mg/L	SW3: 1.490 (spring) and 3.70 (fall) SEEP: 0.74 (spring) and 2.84 (fall)
Aluminum	PWQO: 0.075 mg/L CWQG: 0.1 mg/L	SW1: 0.176 (spring) SW2: 0.079 (spring)
Boron	PWQO: 0.20 mg/L CWQG: 1.50 mg/L	SW3: 0.201 (spring) and 0.207 (fall) SEEP: 0.364 mg/L (spring) and 0.213 (fall)
Chromium	PWQO: 0.0089 mg/L CWQG: 0.001 mg/L	SEEP: 0.00868 (spring)
Cobalt	PWQO: 0.0064 mg/L	SW3: 0.00947 (fall) SEEP: 0.00734 (fall)

6) In my opinion, any exceedances listed in Question 5 are the result of non-WDS related influences (such as background, road salting, sampling site conditions)?	<input type="radio"/> Yes <input checked="" type="radio"/> No	If yes, specify (Type Here)
--	--	-----------------------------

<p>7) All monitoring program surface water parameter concentrations fall within a stable or decreasing trend. The site is not characterized by historical ranges of concentrations above assessment and compliance criteria.</p>	<p><input checked="" type="radio"/> Yes</p> <p><input type="radio"/> No</p>	<p>If no, list parameters and stations that is outside the expected range. Identify whether parameter concentrations show an increasing trend or are within a high historical range (Type Here)</p>
<p>8) For the monitoring program parameters, does the water quality in the groundwater zones adjacent to surface water receivers exceed assessment or compliance criteria (e.g. , PWQOs, CWQGs, or toxicity values for aquatic biota (APVs)):</p>	<p><input checked="" type="radio"/> Yes</p> <p><input type="radio"/> No</p> <p><input type="radio"/> Not Known</p> <p><input type="radio"/> Not Applicable</p>	<p>Only marginal cobalt exceedance at BH9-I.</p>
<p>9) Have trigger values for contingency plans or site remedial actions been exceeded (where they exist):</p>	<p><input type="radio"/> Yes</p> <p><input type="radio"/> No</p> <p><input checked="" type="radio"/> Not Applicable</p>	<p>If yes, list value(s) that are/have been exceeded and follow-up action taken (Type Here)</p>

Surface Water CEP Declaration:

I, the undersigned hereby declare that I am a Competent Environmental Practitioner as defined in Appendix D under Instructions, holding the necessary level of experience and education to design surface water monitoring and sampling programs, conduct appropriate surface water investigations and interpret the related data as it pertains to the site for this monitoring period.

I have examined the applicable Certificate of Approval and any other environmental authorizing or control documents that apply to the site. I have read and followed the Monitoring and Reporting for Waste Disposal Sites Groundwater and Surface Water Technical Guidance Document (MOE, 2010, or as amended) and associated monitoring and sampling guidance documents, as amended from time to time. I have reviewed all of the data collected for the above-referenced site for the monitoring period(s) identified in this checklist. Except as otherwise agreed with the ministry for certain parameters, all of the analytical work has been undertaken by a laboratory which is accredited for the parameters analysed to *ISO/IEC 17025:2005 (E)- General requirements for the competence of testing and calibration laboratories*, or as amended from time to time by the ministry.

If any exceptions or potential concerns have been noted in the questions in the checklist attached to this declaration, it is my opinion that these exceptions and concerns are minor in nature or will be rectified for future monitoring events. Where this is not the case, the circumstances concerning the exception or potential concern and my client's proposed action have been documented in writing to the Ministry of the Environment District Manager in a letter from me dated:

12-Feb-2026

Recommendations:

Based on my technical review of the monitoring results for the waste disposal site:

No Changes to the monitoring program are recommended


Type Here

The following change(s) to the monitoring program is/are recommended:

No changes to the site design and operation are recommended

Type Here

The following change(s) to the site design and operation is/are recommended:

CEP Signature		
Relevant Discipline	Hydrogeologist	
Date:	13-Feb-2026	
CEP Contact Information:	Tim McBride	
Company:	Pinchin Ltd.	
Address:	662 Falconbridge Road, Unit 3 Sudbury, ON P3A 4S4	
Telephone No.:	705.521.0560	
Fax No. :		
E-mail Address:	tmcbride@pinchin.com	
Save As		Print Form